

Public Information Meeting

**State Project No. 53-189
Removal of Route 17 SB Off-Ramp to East
Glastonbury/New London Turnpike
(Including Bridge Nos. 00388 and 00389)**

Glastonbury, Connecticut

Thursday, June 7, 2018 at 7:00 pm
Council Chambers at Town Hall
2155 Main Street
Glastonbury, CT

Connecticut Department of Transportation





Project Location Map





Introductions

- Connecticut Department of Transportation
 - Theodore Nezames – Transportation Division Chief
 - Rabih Barakat – Transportation Principal Engineer
 - Andrew Cardinali – Transportation Supervising Engineer
 - Dobieslawa Kania – Transportation Project Engineer
 - Colin Baummer – Transportation Supervising Engineer

- CME Associates, Inc.
 - Donald Wurst – Department Manager
 - Tracey Brais – Project Engineer
 - Aaron Foster – Project Engineer




CTDOT Bridge Program Goals

- Provide a safe crossing for the traveling public.
- Rehabilitate and/or replace bridges on State transportation network to a state of good repair.
- Efficient use of Federal and State funds.
- Design solution beneficial to all.



Typical Bridge Components

- Deck
- Superstructure
- Substructure





Purpose and Need

- Bridge No. 00388 needs to be rehabilitated
 - Structurally deficient bridge with an inspection rating of "4" – Deck is in poor condition, per October 2016 inspection
 - Functionally obsolete structure due to substandard vertical underclearance
- Investigate the area for additional rehabilitation needs or improvements
 - Bridge No. 00389 was included in the study area
 - Undesirable intersection geometry at New London Turnpike/Oak Street/Williams Street E/Route 17 Off-Ramp intersection
 - Crash data in the region of the project
 - Long term fiscal responsibility – cost benefit analysis
 - Pedestrian improvements



Project Overview

- Project is in the preliminary design stage
 - We are looking for your input
- Will provide overview of project and key details tonight, including:
 - Existing Site, Traffic and Collision Information
 - Potential Solutions
 - Proposed Plans and Detour
 - Intersection Wait Times, and Travel Times
 - Schedule




Bridge No. 00388 Rte 17 NB over Route 17 SB Ramp 007

General Information

- Built in 1952
- Single-span steel girder bridge supported by reinforced concrete abutments
- Beyond its estimated service life of 50-years

Existing Condition

- Deck: "4" Poor
- Horizontal and Vertical Underclearance: "3"
- Structure is structurally deficient and functionally obsolete





Bridge No. 00388 Rte 17 NB over Route 17 SB Ramp 007



Underside of Bridge and
West Abutment

Typical Deterioration Seen on
Underside of Deck





Bridge No. 00389 Rte 17 SB Ramp 007 over New London Tpke

General Information

- Built in 1952 (same year as 00388)
- Single-span steel girder bridge supported by reinforced concrete abutments



Existing Condition

- Previous repair of deteriorated concrete deck






Route 17 SB Ramp 007

- Approx. Length of Ramp: 2100 ft
- Avg. Daily Traffic (2015):
3200 vehicles
- AM Peak Hourly Traffic Count:
200 vehicles
- PM Peak Hourly Traffic Count:
380 vehicles
- Projected Avg. Daily Traffic (2039):
4500 vehicles






Off Ramp 007 ADT – Actual and Projection (No-Build)



Note: Estimate incorporates "The Tannery" traffic increase




Oak/Williams/NLT Intersection Traffic – Total Projected ADT (All Options)



Note: Estimate incorporates "The Tannery" traffic increase



Project No. 53-189: Collision Diagram





Potential Solutions

- Reconfiguring traffic movement from Route 17 SB onto New London Turnpike by modifying Ramp 005 to accommodate left-turning traffic
 - Allows for free flow of traffic and improves safety
- Reconfiguring existing five-leg intersection of Ramp 007, New London Turnpike, Oak Street and Williams Street into a four-leg intersection
 - Decreases average traffic wait-time
- Removal of two bridges from service
 - Saves CTDOT on capital costs over long term



Potential Solutions (cont.)

- Sidewalks will be installed along the New London Turnpike
 - Improves pedestrian access
- Previously presented "Build Option 1" – minimal work along New London Turnpike
- Tonight will also present "Build Option 2" – additional EB lane along New London Turnpike
 - Improves travel time from Rt. 17 SB



Proposed Limits of Project No. 53-189 Build Option 1





Proposed Limits of Project No. 53-189

Build Option 2





Project No. 53-189: Construction Stage 1






Project No. 53-189: Construction Stage 2





Project No. 53-189: Construction Stage 1




LEGEND

- SIDEWALKS
- EXISTING STRUCTURES
- WATERCOURSE
- CUT
- FILL
- R.O.W. LINES
- FULL DEPTH PAVEMENT
- EXISTING PAVEMENT
- AREA OF MILL & OVERLAY
- WORK ZONE
- TPBCB
- TRAFFIC DRUM
- TEMPORARY IMPACT ATTENUATION SYSTEM
- TRAFFIC BARRICADE, TYPE III
- DIRECTION OF TRAFFIC
- PAVEMENT MARKING ARROW LEFT
- PAVEMENT MARKING ARROW THROUGH
- PAVEMENT MARKING ARROW RIGHT
- FLASHING ARROW BOARD
- TRAFFIC SIGN




Project No. 53-189: Construction Stage 2








Project No. 53-189: Construction Stage 2

REMOVE DECK, PARAPETS,
BRIDGE RAILING, STEEL
GIRDERS, AND
SUBSTRUCTURE DOWN TO
THE FOOTINGS




BRIDGE NO. 00389 ELEVATION

LEGEND

-  PORTION OF STRUCTURE TO BE REMOVED
-  EXISTING GROUND ABOVE GRADE LINE
-  FINISHED GRADE LINE



Project No. 53-189: Construction Stage 2




**NEW LONDON TURNPIKE WESTBOUND
DETOUR MAP - OPTION 1**
N.T.S.

**NLT WB Detour #1:
During Off-Peak Hours while Br. 00389 is Removed**



Project No. 53-189: Construction Stage 2




**NEW LONDON TURNPIKE WESTBOUND
DETOUR MAP - OPTION 2**

N.T.S.

**NLT WB Detour #2:
During Off-Peak Hours while Br. 00389 is Removed**



Project No. 53-189: Construction Stage 2




**NEW LONDON TURNPIKE
EASTBOUND DETOUR MAP**
N.T.S.

**NLT EB Detour:
During Off-Peak Hours while Br. 00389 is Removed**




Project No. 53-189: Construction Stage 2





Project No. 53-189: Construction Stage 2




Duration of Detour: 55 Hours Period (1 Weekend)




Route 17 SB Ramp 007

- Approx. Length of Ramp: 2100 ft
- Avg. Daily Traffic (2015):
3200 vehicles
- AM Peak Hourly Traffic Count:
200 vehicles
- PM Peak Hourly Traffic Count:
380 vehicles
- Projected Avg. Daily Traffic (2039):
4500 vehicles






Off Ramp 007 ADT – Actual and Projection (No-Build)



Note: Estimate incorporates "The Tannery" traffic increase



Oak/Williams/NLT Intersection Traffic – Total Projected ADT (All Options)



Note: Estimate incorporates "The Tannery" traffic increase



Project No. 53-189: Preliminary Intersection Traffic Analysis – 2019 Peak PM

No Build

Approach	Approach Delay (sec)
New London Tpke EB	27
New London Tpke WB	42
Williams St. East	45
Oak Street	78
Route 17 SB Off-Ramp	56
New London Turnpike at Oak St. and Williams St. East	Avg. Delay (sec)
	53
Intersection Level of Service	D
*All are an average of all traffic movements on the specified intersection leg	

Build Option 1

Approach	Approach Delay (sec)
New London Tpke EB	21
New London Tpke WB	26
Williams St. East	39
Oak Street	16
New London Turnpike at Oak St. and Williams St. East	Avg. Delay (sec)
	21
Intersection Level of Service	C
*All are an average of all traffic movements on the specified intersection leg	

Build Option 2

Approach	Approach Delay (sec)
New London Tpke EB	15
New London Tpke WB	26
Williams St. East	31
Oak Street	16
New London Turnpike at Oak St. and Williams St. East	Avg. Delay (sec)
	19
Intersection Level of Service	B
*All are an average of all traffic movements on the specified intersection leg	



Project No. 53-189: Preliminary Intersection Traffic Analysis - 2039 Peak PM

No Build

Approach	Approach Delay (sec)
New London Tpke EB	28
New London Tpke WB	43
Williams St. East	49
Oak Street	148
Route 17 SB Off-Ramp	83
New London Turnpike at Oak St. and Williams St. East	Avg. Delay (sec)
	83
Intersection Level of Service	F
*All are an average of all traffic movements on the specified intersection leg	

Build Option 1

Approach	Approach Delay (sec)
New London Tpke EB	23
New London Tpke WB	33
Williams St. East	46
Oak Street	20
New London Turnpike at Oak St. and Williams St. East	Avg. Delay (sec)
	25
Intersection Level of Service	C
*All are an average of all traffic movements on the specified intersection leg	


Build Option 2

Approach	Approach Delay (sec)
New London Tpke EB	18
New London Tpke WB	34
Williams St. East	44
Oak Street	19
New London Turnpike at Oak St. and Williams St. East	Avg. Delay (sec)
	23
Intersection Level of Service	C
*All are an average of all traffic movements on the specified intersection leg	

Estimated Growth Rate = 2% Annually




Rt. 17 SB – Off-Ramp - 2019





Rt. 17 NB – On-Ramp - 2019



Option	AM/PM	Travel Time (sec)
No-Build	AM	89.5
	PM	91.0
Build 1	AM	78.4
	PM	75.0
Build 2	AM	77.7
	PM	64.6





Project No. 53-189: Utility Impacts

Anticipated Impacts to Utilities

- Utility poles along New London Turnpike will need to be relocated.
- Communications lines on Bridge No. 00389 need to be protected in place or relocated.
- A fire hydrant adjacent to New London Turnpike and near the existing Route 17 SB Ramp 005 will need to be relocated.



Project No. 53-189: Drainage, Right-of-Way & Environmental Impacts

- Drainage system modifications may be needed
 - Relocation of catch basins near Route 17 SB Ramp 005, on north and south sides of New London Turnpike
- No Anticipated Impacts to Wetlands
- Construction work to be done within State and Town Rights-of-Way



Project Funding and Cost

Funding

- Construction will be undertaken using State Funds under the "Fix it First Transportation Initiative"
- If Federal Funds are available, then they will be applied for
 - Project funding will become an 80% Fed/20% State split
- The cost and schedule are preliminary, and are subject to change

Cost

- Total construction cost for the project is currently estimated at \$4,000,000



Project Schedule and Construction

Schedule

- Construction Start: Spring 2020
- Completion: Summer 2021
- Construction anticipated to last 1½ to 2 construction seasons
 - some construction activities have minimal to no impact to the traveling public

Construction Impacts to Traffic

- Detours will only be during the weekends in order to minimize impacts
 - Only two weekends anticipated for detours



Contact Information

Thank You Questions and Comments

Dobieslawa Kania – Transportation Engineer 3
Connecticut DOT
2800 Berlin Turnpike
P.O. Box 317546
Newington, CT 06131

Email: Dobieslawa.Kania@ct.gov
Phone: 860-594-3389




Back-up information



Back-up information


Life Cycle Cost Analysis



- Cost Benefit Analysis over a 75-year period
- Cost for today based on evaluation of repairs and rehabilitation



Back-up information Studied – not part of current design



PRELIMINARY

<p>NOTES:</p> <ol style="list-style-type: none">1. SURVEY BY District-12. FIELD BOOKS 170-334 Glastonbury3. 400 FOOT GRID BASED ON CONNECTICUT COORDINATE SYSTEM N. A. S. REF. 20114. VERTICAL DATUM BASED ON NAVD 885. THE PROPERTY AND STREET LINES SHOWN HAVE BEEN COMPILED FROM VARIOUS SOURCES AND ARE NOT TO BE CONSIDERED AS NECESSARILY BEING OBTAINED AS THE RESULT OF A FIELD SURVEY, NOR DO THEY REPRESENT A PROPERTY BOUNDARY OPINION6. UNDERGROUND UTILITY, STRUCTURE AND FACILITY LOCATIONS SHOWN AND NOTED HEREON HAVE BEEN COMPILED, IN PART, FROM RECORD MAPS SUPPLIED BY THE RESPECTIVE UTILITY COMPANIES OR GOVERNMENT AGENCIES. LIMITED FIELD LOCATIONS AND OTHER SOURCES. THESE LOCATIONS MUST BE CONSIDERED AS APPROXIMATE IN NATURE. ADDITIONALLY, OTHER SUCH FEATURES MAY EXIST ON THE SITE, THE EXISTENCE OF WHICH ARE UNKNOWN. THE SIZE, LOCATION AND EXISTENCE OF ALL SUCH FEATURES MUST BE FIELD DETERMINED AND VERIFIED BY THE APPROPRIATE AUTHORITIES PRIOR TO CONSTRUCTION. CALL BEFORE YOU DIG 1-800-322-4400.7. UTILITIES ARE SUPPLIED BY THE FOLLOWING COMPANIES: M&C, ONE	<p>STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION Route 17 SB Ramp AT New London Turnpike IN THE TOWN OF GLASTONBURY</p> <p>PROJECT NO. 170-3250</p> <p>SCALE IN FEET 0 10 20</p> <p>SURVEYED BY: Hwy PLOTTED BY: CHECKED BY: Subtotal FILE: 170_334_Glastonbury_8/14/01.dwg May 2006</p>
---	--