#### TOWN OF GLASTONBURY

GL-2019-35

#### FIRE ALARM REPLACEMENT - SMITH MIDDLE SCHOOL ADDENDUM NO. 1 May 16, 2019

Bid Due Date: 05-22-19 @ 11:00 A.M.

The attention of bidders submitting proposals for the above-referenced project is called to the following Addendum to the specifications. The items set forth herein, whether of omission, addition, substitution or other change, are all to be included in and form a part of the proposed Contract Documents for the work. Bidders shall acknowledge this Addendum on the Bid Proposal Page (BP-1).

The following questions were asked during the mandatory pre-bid conference.

Question 1: Do you have a list of devices with quantities? And a building Floor Plan?

**Answer:** A list of devices is attached. Contractor shall verify quantities. The building floor plan

will be distributed to bidders that attended the mandatory pre-bid meeting.

Question 2: Is the Fire Alarm upgrade part of a larger code update?

**Answer:** No. The existing fire alarm system is an addressable system and code compliant however

due to its age and unavailable parts by the manufacturer it needs to be replaced. The new Fire Alarm Control panel and all devices are being replaced one for one with the new specified system. All existing wire will remain as well as device locations. The new specified system will also be expandable if necessary in the future. This project has the

approval of the local Fire Marshal.

Question 3: What is the square footage of the school?

**Answer:** 178,838 square feet.

Question 4: Can a copy of the Pre-Bid meeting attendees list be provided?

**Answer:** Please see attached.

Question 5: Will the bid open date be extended and what will be the last day for questions?

Answer: The bid due date will remain May 22, 2019 11am. As stated in the bid documents, all

questions must be received at least five (5) business days prior to the advertised response

deadline. The last day for questions was May 15, 2019.

Question 6: When can contractors return to visit the site?

**Answer:** Weekdays after 3pm. Please notify Mr. Costa of what day 860-652-7992.

Ouestion 7: When is the completion day for the work?

**Answer:** July 10, 2019 with a working system and tested by the Fire Marshal. Contractor shall

coordinate all work with Fire Marshal an obtain approvals.

Note: This addendum consists of 4 pages including the above text.

## GLASTONBURY MIDDLE SCHOOL PROJECT

## GLASTONBURY, CONNECTICUT LOCATION

## ANCHOR ELECTRICAL CONTRACTORS INSTALLER

#### **EQUIPMENT LIST**

FIRE ALARM EQUIPMENT				
<u>QTY</u>	MODEL#	<u>DESCRIPTION</u>		
1	4020-8001	FIRE ALARM CONTROL PANEL		
1	4020-7003	-MASTER CONTROLLER		
1	4020-6081	-VERSION 8 SOFTWARE		
1	4020-2003	-6 NIT PACKAGE		
1	4020-0305	-8 POINT I/O MODULE		
1	4020-0155	-SERIAL D.A.C.T.		
2	4020-0110	-MAPNET II ADDRESSABLE MODULE		
1	2081-9365	CHGR 15AMP A-12-B-15-24 120VAC		
1	2081-9280	BATT CAB ONLY F/2081-9279		
2	2081-9279	BATTERY 110AH		
3	4603-9101	LCD ANNUNCIATOR		
6	4009-9001	NAC POWER EXT 4 PT ST Y 120V		
3	4003-9001	VOICE CONTROL PANEL 120V CL B		
18	2081-9274	BATTERY 10AH		
24	4098-9753	SSD SENSOR DUCT HOUSING W/REL		
24	4098-9714	SSD PHOTO SENSOR		
24	2098-9798	SAMPLING TUBE 73"		
24	2098-9808	REMOTE ALARM INDICATOR		
149	4098-9714	SSD PHOTO SENSOR		
22	4098-9733	SSD HEAT SENSOR		
171	4098-9792	SSD SENSOR BASE		
50	2099-9795	PULL STATION MAPII S/A		
50	2975-9178	BOX/ADDRESSABLE PULL STATION		
214	4903-9418	A/V 75CD RED SYNC QUICK ALERT		
2	4903-9235	MT/STRB WP UL1638 MT-24-WM-VFR		
2	4905-9934	MULTITONE BOX SURF RED 10B-R		
21	4904-9331	V/O 15CD RED SYNC QUICKALERT		
16	4903-9303	A/V 24VDC 30CD RED 1HZ SYNC		
44	2088-9608	DOOR HOLDER, SEMI-FLUSH		

(CONTINUE ON NEXT PAGE)

CT LIC #106166 A.HANK/C. SCHLEIF SEPT. 16, 1999

# PAGE 2 GLASTONBURY MIDDLE SCHOOL PROJECT

## GLASTONBURY, CONNECTICUT LOCATION

## ANCHOR ELECTRICAL CONTRACTORS INSTALLER

SPRINKLER DEVICES				
<u>QTY</u>	MODEL#	<u>DESCRIPTION</u>		
44	2190-9172	SUPERVISED 1AM		
FIRE CURTAIN CONTROL				
2	2190-9163	ADDRESSABLE CONTROL ZAM-SURF		
ELEVATOR RECALL				
3	4098-9601	SSD PHOTO DETECTOR		
3	4098-9682	SSD 4-WIRE DET RELAY BASE		
3	2098-9734	120V DETECTOR POWER PACK		
2	2098-9462	HD 2N/O FX135 W/REPLAC COLLECT		
<u>CALL-FOR-AID EQUIPMENT</u>				
1	LI123B	DOME LAMP W/BUZZER		
15	SF117/2B	CALL SWITCH		
15	SS106	TRANSFORMER		
AREA OF REFUGE EQUIPMENT				
1	A4208	REFUGE ANNUNCIATOR 8 ZONE		
1	BB41	FLUSH MOUNT BOX 8 ZONE		
8	A4201	AREA OF REFUGE STATION		
1	C5243	POWER SUPPLY W/BATTERY		

CT LIC #106166 A.HANK/C. SCHLEIF SEPT. 16, 1999

### Fire Alarm Replacement – Smith Middle School

Bid # GL-2019-35

Date: 5/10/19

Name Jond	Company than brida & CSilom	<u>Phone</u>
Jonathan Breda		203-228-7588
Jim Buller	JButer@customelectre Custon Electre	
Ac COSTA	GHAST, PS,	860-652-7792
Dave Sacchitella	•	<u>860652-770</u>
	W	