



DUTTON ASSOCIATES, LLC

DRAINAGE COMPUTATIONS CASELLA SUBDIVISION

KNOLLWOOD DRIVE
GLASTONBURY, CT

PREPARED BY
DUTTON ASSOCIATES, LLC
MARCH 16, 2020

TABLE OF CONTENTS

SUMMARY	1
HYDROLOGY COMPUTATIONS	
Watershed Model Schematic	2
Tr-55 Curve Numbers	3-4
Existing Conditions	
Area & Tc	5-8
Flow Summary	9
Hydrographs (Existing 2yr to 100yr)	10-18
Proposed conditions	
Area & Tc	19-25
Flow Summary	26
Hydrographs (Proposed 2yr to 100yr)	27- 56
Water Quality Volume Computation	57
Detention Pond Data	58-61
Detention Pond Outlet Protection Computation	62
Detention Pond Outlet Swale Computation	63-65
STORM SEWER COMPUTATIONS	
Plan of Drainage System	66
Area to inlets & Tc	67-71
Gutter Flow Analysis	72
Pipe Design	73
Headwater Analysis	74
APPENDIX	
Soils Report	75-78
NRCS Soils Map & Information	79-88
Runoff Values (NOAA Atlas 14, Vol. 10, V. 3 Hartford)	89
Rational Rainfall Intensity Values	90-91
Drainage System Design Charts	92-93

SUMMARY

The Casella Subdivision proposal is a 3-lot subdivision of an 11.7-acre parcel located southeasterly of the Knollwood Drive cul-de-sac. The subdivision contains two rear lots and 1 frontage lot. All lots will be accessed by a common driveway from Knollwood Drive. Additionally, a previously approved rear lot (owned by the applicant but not a part of this application) will also be accessed by the common drive.

Topography of the site is moderately steep with approximately 41,200 s.f. (0.95 acres) of the site with slopes over 20%. The steep slope areas are scattered throughout the site. The site also contains some ledge outcrops and many large boulders. Sols on the site are predominantly Charlton and Hollis series (hydrologic soil groups B & D). Vegetation on the site consists of a mixed hardwood forest with scattered pines. Surface water runoff generally flows from the northeast to the southwest. A wetland area exists which was delineated by Cynthia Rabinowitz and field surveyed by Dutton Associates.

Storm water runoff generally flows from the northeast to the southwest and ultimately to a wetland area east, southeast of the site, then water flows southerly through the wetland area to Hebron Avenue, and easterly along the northerly gutter of Hebron Avenue to a catch basin inlet by building #2390, thence southerly through a pipe system to a discharge locates at a wetland area just easterly of Sturgeon River Road.

A subsurface drainage system has been designed to collect runoff from the common driveway. The flows are directed to a detention pond located at the southwesterly corner of the site. The storm drain system was designed for the 10-year storm using the rational method. The gutter flow analysis, pipe design, and headwater analysis were conducted per the Connecticut DOT Drainage manual.

Proposed storm flows from the site are directed to a detention pond located along the southerly end of the site. Hydrology computations were conducted using the TR-55 Method with routing computations run using the Hydraflow Hydrographs program. The detention pond was sized to mitigate for any increase in flow for the 2-year through the 100-year storms.

The detention pond will also be used to treat the water quality volume (WQV) from the site. The detention pond has been designed to contain the entire water quality volume below the first outlet flow structure. The WQV will be collected using an underdrain system located at the bottom of the detention pond with the outflow from the underdrain regulated by an orifice sized to drain the WQV over a 40-hour period.

Below is a summary of the pre and post development flows from the site.


STORM	EXIST. "A"	EXIST. "B"	PROP. "A"	PROP. "B"
2-YEAR	1.4 CFS	1.7 CFS	1.3 CFS	1.5 CFS
10-YEAR	4.1 CFS	6.8 CFS	3.7 CFS	6.1 CFS
25-YEAR	6.1 CFS	10.8 CFS	5.5 CFS	10.2 CFS
50-YEAR	7.5 CFS	14.0 CFS	6.9 CFS	13.5 CFS
100-YEAR	9.2 CFS	17.8 CFS	8.4 CFS	17.4 CFS

CONCLUSION

Based on the analysis conducted, the proposed Casella Development will not have an adverse impact on downstream properties.

Watershed Model Schematic

Hydraflow Hydrographs by Intelisolve v9.1



Legend

Hyd.	Origin	Description
1	SCS Runoff	EXIST. POINT B
2	SCS Runoff	EXIST. POINT A
3	SCS Runoff	PROP. POINT A
4	SCS Runoff	PROP. POINT B NO DET.
5	SCS Runoff	PROP. POINT B TO DET
6	SCS Runoff	PROP. POINT B DET. BY-PASS
7	Reservoir	DETENTION POND 1
9	Combine	TOTAL PROPOSED ANALYSIS POINT B

Table 2-2a.—Runoff curve numbers for urban areas¹

Cover description		Curve numbers for hydrologic soil group—			
		A	B	C	D
Cover type and hydrologic condition	Average percent impervious area ²				
<i>Fully developed urban areas (vegetation established)</i>					
Open space (lawns, parks, golf courses, cemeteries, etc.) ³ :					
Poor condition (grass cover < 50%)		68	79	86	89
Fair condition (grass cover 50% to 75%).....		49	69	79	84
Good condition (grass cover > 75%)		39	61	74	80
Impervious areas:					
Paved parking lots, roofs, driveways, etc. (excluding right-of-way)					
		98	98	98	98
Streets and roads:					
Paved; curbs and storm sewers (excluding right-of-way)					
		98	98	98	98
Paved; open ditches (including right-of-way)					
		83	89	92	93
Gravel (including right-of-way)					
		76	85	89	91
Dirt (including right-of-way)					
		72	82	87	89
Western desert urban areas:					
Natural desert landscaping (pervious areas only) ⁴ ...					
		63	77	85	88
Artificial desert landscaping (impervious weed barrier, desert shrub with 1- to 2-inch sand or gravel mulch and basin borders)					
		96	96	96	96
Urban districts:					
Commercial and business.....	85	89	92	94	95
Industrial	72	81	88	91	93
Residential districts by average lot size:					
1/8 acre or less (town houses).....	65	77	85	90	92
1/4 acre	38	61	75	83	87
1/3 acre	30	57	72	81	86
1/2 acre	25	54	70	80	85
1 acre	20	51	68	79	84
2 acres	12	46	65	77	82
<i>Developing urban areas</i>					
Newly graded areas (pervious areas only, no vegetation) ⁵					
		77	86	91	94
Idle lands (CN's are determined using cover types similar to those in table 2-2c).					

¹Average runoff condition, and $I_{11} = 0.2S$.

²The average percent impervious area shown was used to develop the composite CN's. Other assumptions are as follows: impervious areas are directly connected to the drainage system, impervious areas have a CN of 98, and pervious areas are considered equivalent to open space in good hydrologic condition. CN's for other combinations of conditions may be computed using figure 2-3 or 2-4.

³CN's shown are equivalent to those of pasture. Composite CN's may be computed for other combinations of open space cover type.

⁴Composite CN's for natural desert landscaping should be computed using figures 2-3 or 2-4 based on the impervious area percentage (CN = 98) and the pervious area CN. The pervious area CN's are assumed equivalent to desert shrub in poor hydrologic condition.

⁵Composite CN's to use for the design of temporary measures during grading and construction should be computed using figure 2-3 or 2-4, based on the degree of development (impervious area percentage) and the CN's for the newly graded pervious areas.

4

Table 2-2c.—Runoff curve numbers for other agricultural lands¹

Cover description		Curve numbers for hydrologic soil group—			
Cover type	Hydrologic condition	A	B	C	D
Pasture, grassland, or range—continuous forage for grazing. ²	Poor	68	79	86	89
	Fair	49	69	79	84
	Good	39	61	74	80
Meadow—continuous grass, protected from grazing and generally mowed for hay.	—	30	58	71	78
Brush—brush-weed-grass mixture with brush the major element. ³	Poor	48	67	77	83
	Fair	35	56	70	77
	Good	30	48	65	73
Woods—grass combination (orchard or tree farm). ⁵	Poor	57	73	82	86
	Fair	43	65	76	82
	Good	32	58	72	79
Woods. ⁶	Poor	45	66	77	83
	Fair	36	60	73	79
	Good	30	55	70	77
Farmsteads—buildings, lanes, driveways, and surrounding lots.	—	59	74	82	86

¹Average runoff condition, and $I_n = 0.2S$.

²*Poor*: <50% ground cover or heavily grazed with no mulch.

Fair: 50 to 75% ground cover and not heavily grazed.

Good: >75% ground cover and lightly or only occasionally grazed.

³*Poor*: <50% ground cover.

Fair: 50 to 75% ground cover.

Good: >75% ground cover.

⁴Actual curve number is less than 30; use CN = 30 for runoff computations.

⁵CN's shown were computed for areas with 50% woods and 50% grass (pasture) cover. Other combinations of conditions may be computed from the CN's for woods and pasture.

⁶*Poor*: Forest litter, small trees, and brush are destroyed by heavy grazing or regular burning.

Fair: Woods are grazed but not burned, and some forest litter covers the soil.

Good: Woods are protected from grazing, and litter and brush adequately cover the soil.

PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER 5
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

EASTING - ANALYSIS POINT A

TOTAL AREA = 177,037 SF

TOTAL AREA B = 95,553 SF

TOTAL AREA D = 82,084 SF

(HYDROGRAPH #2)

B WOODS = 34,885 + 15,851 = 50,736 SF = 1.16 AC
 GRASS = 30,971 SF = 0.71 AC
 PAVED = 276 + 8089 + 4938 + 543 = 13,846 SF = 0.32 AC

D WOODS = 180,879 SF = 4.12 AC
 GRASS = 1205 SF = 0.03 AC
 PAVED = 0

TC

150' C 14.7% WOODS, MANN. = 0.10
 590' C 20% UNPAVED
 68' C 1% PAVED

TR55 Tc Worksheet

6

Hyd. No. 2

EXIST. POINT A

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.100	0.011	0.011	
Flow length (ft)	= 150.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 3.07	0.00	0.00	
Land slope (%)	= 0.15	0.00	0.00	
Travel Time (min)	= 28.42	+ 0.00	+ 0.00	= 28.42
Shallow Concentrated Flow				
Flow length (ft)	= 590.00	68.00	0.00	
Watercourse slope (%)	= 0.20	0.01	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	= 0.72	0.20	0.00	
Travel Time (min)	= 13.63	+ 5.58	+ 0.00	= 19.20
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	= 0.00	0.00	0.00	
Flow length (ft)	= 0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				47.62 min

PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

7

EXISTING - ANALYSIS POINT B

TOTAL AREA = 539,230 (HYDROGRAPH # 1)

TOTAL AREA D = 163,955

TOTAL B = 375,275

B WOODS = 10,975 + 304,085 SF = 315,060 SF = 7.23 AC
 GRASS = 21,652 + 26,397 = 48,049 = 1.10 AC
 PAVED = 11,989 SF = 0.03 AC

D WOODS = 148,663 + 22,300 SF = 170,963 SF = 3.92 AC
 GRASS = 0
 PAVED = 0

TC

150' @ 14.6% WOODS, IMPAV = 0.10
 660' @ 20.0% UNPAVED
 682' @ 4.4% UNPAVED

TR55 Tc Worksheet

8

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No. 1

EXIST. POINT B

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.100	0.011	0.011	
Flow length (ft)	= 150.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 3.07	0.00	0.00	
Land slope (%)	= 0.19	0.00	0.00	
Travel Time (min)	= 25.65	+ 0.00	+ 0.00	= 25.65
Shallow Concentrated Flow				
Flow length (ft)	= 660.00	682.00	0.00	
Watercourse slope (%)	= 0.20	0.04	0.00	
Surface description	= Unpaved	Unpaved	Paved	
Average velocity (ft/s)	= 0.72	0.34	0.00	
Travel Time (min)	= 15.24	+ 33.59	+ 0.00	= 48.83
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.050	0.015	0.015	
Velocity (ft/s)	= 0.00	0.00	0.00	
Flow length (ft)	= 0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				74.48 min

EXISTING

9

Hydrograph Return Period Recap

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No.	Hydrograph type (origin)	Inflow Hyd(s)	Peak Outflow (cfs)								Hydrograph description
			1-Yr	2-Yr	3-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr	
1	SCS Runoff	-----	-----	1.722	-----	-----	6.801	10.82	14.04	17.75	EXIST. POINT B
2	SCS Runoff	-----	-----	1.441	-----	-----	4.124	6.050	7.550	9.240	EXIST. POINT A
3	SCS Runoff	-----	-----	1.306	-----	-----	3.745	5.494	6.859	8.397	PROP. POINT A
4	SCS Runoff	-----	-----	1.895	-----	-----	7.088	11.12	14.34	18.05	PROP. POINT B NO DET.
5	SCS Runoff	-----	-----	1.451	-----	-----	3.762	5.376	6.616	8.002	PROP. POINT B TO DET
6	SCS Runoff	-----	-----	0.977	-----	-----	4.342	7.113	9.363	11.97	PROP. POINT B DET. BY-PASS
7	Reservoir	5	-----	0.552	-----	-----	1.839	3.125	4.184	5.457	DETENTION POND 1
9	Combine	6, 7,	-----	1.512	-----	-----	6.092	10.15	13.46	17.37	TOTAL PROPOSED ANALYSIS PO

Hydrograph Report

10

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 2

EXIST. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 2 yrs
Time interval = 2 min
Drainage area = 4.080 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 3.07 in
Storm duration = 24 hrs

Peak discharge = 1.441 cfs
Time to peak = 760 min
Hyd. volume = 11,160 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.60 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(1.160 \times 55) + (0.710 \times 61) + (0.320 \times 98) + (1.860 \times 77) + (0.030 \times 80)] / 4.080$



Hydrograph Report

//

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 1

EXIST. POINT B

Hydrograph type = SCS Runoff
Storm frequency = 2 yrs
Time interval = 2 min
Drainage area = 12.280 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 3.07 in
Storm duration = 24 hrs

Peak discharge = 1.722 cfs
Time to peak = 784 min
Hyd. volume = 20,731 cuft
Curve number = 63*
Hydraulic length = 0 ft
Time of conc. (Tc) = 74.50 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(7.230 x 55) + (1.100 x 61) + (0.030 x 98) + (3.920 x 77)] / 12.280



Hydrograph Report

12

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 2

EXIST. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 10 yrs
Time interval = 2 min
Drainage area = 4.080 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 4.87 in
Storm duration = 24 hrs

Peak discharge = 4.124 cfs
Time to peak = 756 min
Hyd. volume = 28,739 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.60 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(1.160 x 55) + (0.710 x 61) + (0.320 x 98) + (1.860 x 77) + (0.030 x 80)] / 4.080



Hydrograph Report

13

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 1

EXIST. POINT B

Hydrograph type = SCS Runoff
Storm frequency = 10 yrs
Time interval = 2 min
Drainage area = 12.280 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 4.87 in
Storm duration = 24 hrs

Peak discharge = 6.801 cfs
Time to peak = 774 min
Hyd. volume = 63,980 cuft
Curve number = 63*
Hydraulic length = 0 ft
Time of conc. (Tc) = 74.50 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(7.230 x 55) + (1.100 x 61) + (0.030 x 98) + (3.920 x 77)] / 12.280



Hydrograph Report

4

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 2

EXIST. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 25 yrs
Time interval = 2 min
Drainage area = 4.080 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 5.99 in
Storm duration = 24 hrs

Peak discharge = 6.050 cfs
Time to peak = 754 min
Hyd. volume = 41,429 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.60 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(1.160 x 55) + (0.710 x 61) + (0.320 x 98) + (1.860 x 77) + (0.030 x 80)] / 4.080



Hydrograph Report

15

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 1

EXIST. POINT B

Hydrograph type = SCS Runoff
Storm frequency = 25 yrs
Time interval = 2 min
Drainage area = 12.280 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 5.99 in
Storm duration = 24 hrs

Peak discharge = 10.82 cfs
Time to peak = 772 min
Hyd. volume = 97,256 cuft
Curve number = 63*
Hydraulic length = 0 ft
Time of conc. (Tc) = 74.50 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(7.230 \times 55) + (1.100 \times 61) + (0.030 \times 98) + (3.920 \times 77)] / 12.280$



Hydrograph Report

16

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 2

EXIST. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 50 yrs
Time interval = 2 min
Drainage area = 4.080 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 6.82 in
Storm duration = 24 hrs

Peak discharge = 7.550 cfs
Time to peak = 754 min
Hyd. volume = 51,382 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.60 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(1.160 \times 55) + (0.710 \times 61) + (0.320 \times 98) + (1.860 \times 77) + (0.030 \times 80)] / 4.080$



Hydrograph Report

17

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 1

EXIST. POINT B

Hydrograph type = SCS Runoff
Storm frequency = 50 yrs
Time interval = 2 min
Drainage area = 12.280 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 6.82 in
Storm duration = 24 hrs

Peak discharge = 14.04 cfs
Time to peak = 772 min
Hyd. volume = 124,040 cuft
Curve number = 63*
Hydraulic length = 0 ft
Time of conc. (Tc) = 74.50 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(7.230 x 55) + (1.100 x 61) + (0.030 x 98) + (3.920 x 77)] / 12.280



Hydrograph Report


Hyd. No. 3

PROP. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 50 yrs
Time interval = 2 min
Drainage area = 4.000 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 6.82 in
Storm duration = 24 hrs

Peak discharge = 6.859 cfs
Time to peak = 758 min
Hyd. volume = 50,004 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 54.90 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(1.040 x 55) + (0.760 x 61) + (0.340 x 98) + (1.800 x 77) + (0.060 x 61)] / 4.000



PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER 19
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

PROPOSED ANALYSIS POINT A

TOTAL AREA = 173,964 SF

TOTAL AREA B = 93,079

(HYDROGRAPH #3)

TOTAL AREA D = 80,885 SF

B WOODS 34,541 + 10,699 = 45,240 SF = 1.04 AC
 GRASS 33,054 SF = 0.76 AC
 PAVED 13,846 + 870 = 14,716 SF 0.34 AC

D WOODS = 78,442 SF = 1.80 AC
 GRASS = 12,051 + 1238 = 24,339 SF = 0.56 AC
 PAVED = 0

TL 150' C 14.7% MAINT = 0.10
 600' C 19.5% UNPAVED
 75' C 1.0% PAVED

TR55 Tc Worksheet

20

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No. 3

PROP. POINT A

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.100	0.011	0.011	
Flow length (ft)	= 150.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 3.07	0.00	0.00	
Land slope (%)	= 0.15	0.00	0.00	
Travel Time (min)	= 28.42	+ 0.00	+ 0.00	= 28.42
Shallow Concentrated Flow				
Flow length (ft)	= 563.00	165.00	0.00	
Watercourse slope (%)	= 0.20	0.01	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	= 0.72	0.20	0.00	
Travel Time (min)	= 12.97	+ 13.53	+ 0.00	= 26.50
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	= 0.00	0.00	0.00	
Flow length (ft)	= 0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				54.92 min

PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER 21
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

ANALYSIS POINT B PROPOSED NO DETENTION

TOTAL AREA = 542,915 SF

TOTAL B = 375,616 SF

(HYDROGRAPH # 4)

TOTAL D = 167,299 SF

B WOODS = 296,251 SF = 6.80 AC

B GRASS = 68,420 SF = 1.57 AC

B PAVED = 10,945 SF = 0.25 AC

D WOODS = 128,584 SF = 2.95 AC

D GRASS = 29,820 SF = 0.68 AC

D PAVED = 8,895 SF = 0.20 AC

TC

150' @ 14.6% WOODS m = 0.10

659' @ 24.5% UNPAVED

710' @ 4.4% UNPAVED

TR55 Tc Worksheet

22

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No. 4

PROP. POINT B NO DET.

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.100	0.011	0.011	
Flow length (ft)	= 150.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 3.07	0.00	0.00	
Land slope (%)	= 0.15	0.00	0.00	
Travel Time (min)	= 28.50	+ 0.00	+ 0.00	= 28.50
Shallow Concentrated Flow				
Flow length (ft)	= 658.00	682.00	0.00	
Watercourse slope (%)	= 0.20	0.04	0.00	
Surface description	= Unpaved	Unpaved	Paved	
Average velocity (ft/s)	= 0.72	0.34	0.00	
Travel Time (min)	= 15.20	+ 33.59	+ 0.00	= 48.78
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	= 0.00	0.00	0.00	
Flow length (ft)	= 0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				77.28 min

PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER 23
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

PROPOSED ANALYSIS POINT B DETENTION BY-PASS

TOTAL AREA = 400,423 SF

TOTAL AREA B = 314,452 SF (HYDROGRAPH # 6)

TOTAL AREA D = 85,971 SF

B WOODS = 3213 + 125,792 + 117,985 + 6055 + 964 = 254,009 SF = 5.83 AC
 GRASS = 48,931 SF = 1.12 AC
 PAVED = 1204 = 0.03 AC

D WOODS = 32,714 + 22,595 + 26,300 = 81,609 SF = 1.87 AC
 GRASS = 14,670 SF = 0.34 AC
 PAVED = 0

TC
 150' @ 14.6% WOODS M = 0.10
 659' @ 24.5' UNPAVED
 710 @ 4.4% UNPAVED

PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER 24
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

ANALYSIS POINT B, PROPOSED TO DETENTION POND

TOTAL AREA = 142,492 SF

TOTAL B = 50318 + 4846 = 61,164 SF

TOTAL D = 81,328 SF

B WOODS = 4846 + 23,547 + 3541 = 31,934 SF = 0.73 AC

B GRASS = 19,489 SF = 0.45 AC

B PAVED = 6863 + 2878 = 9741 SF = 0.22 AC

D WOODS = 9086 + 48,197 = 57,283 SF = 1.32 AC

D GRASS = 15,150 SF = 0.35 AC

D PAVED = 8895 = 0.20 AC

TC

150' @ 11.8% WOODS (M=0.10)

546' @ 19.6% UNPAVED

515' PIPE ROW - 14% - 12" ϕ

TR55 Tc Worksheet

25

Hyd. No. 6

PROP. POINT B DET. BY-PASS

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.100	0.011	0.011	
Flow length (ft)	= 150.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 3.07	0.00	0.00	
Land slope (%)	= 0.15	0.00	0.00	
Travel Time (min)	= 28.50	+ 0.00	+ 0.00	= 28.50
Shallow Concentrated Flow				
Flow length (ft)	= 659.00	710.00	0.00	
Watercourse slope (%)	= 0.24	0.04	0.00	
Surface description	= Unpaved	Unpaved	Paved	
Average velocity (ft/s)	= 0.79	0.34	0.00	
Travel Time (min)	= 13.90	+ 34.96	+ 0.00	= 48.86
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	= 0.00	0.00	0.00	
Flow length (ft)	= 0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				77.36 min

Hydrograph Return Period Recap

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No.	Hydrograph type (origin)	Inflow Hyd(s)	Peak Outflow (cfs)								Hydrograph description
			1-Yr	2-Yr	3-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr	
1	SCS Runoff	-----	-----	1.722	-----	-----	6.801	10.82	14.04	17.75	EXIST. POINT B
2	SCS Runoff	-----	-----	1.441	-----	-----	4.124	6.050	7.550	9.240	EXIST. POINT A
3	SCS Runoff	-----	-----	1.306	-----	-----	3.745	5.494	6.859	8.397	PROP. POINT A
4	SCS Runoff	-----	-----	1.895	-----	-----	7.088	11.12	14.34	18.05	PROP. POINT B NO DET.
5	SCS Runoff	-----	-----	1.451	-----	-----	3.762	5.376	6.616	8.002	PROP. POINT B TO DET
6	SCS Runoff	-----	-----	0.977	-----	-----	4.342	7.113	9.363	11.97	PROP. POINT B DET. BY-PASS
7	Reservoir	5	-----	0.552	-----	-----	1.839	3.125	4.184	5.457	DETENTION POND 1
9	Combine	6, 7,	-----	1.512	-----	-----	6.092	10.15	13.46	17.37	TOTAL PROPOSED ANALYSIS PO

Hydrograph Report

27

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 3

PROP. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 2 yrs
Time interval = 2 min
Drainage area = 4.000 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 3.07 in
Storm duration = 24 hrs

Peak discharge = 1.306 cfs
Time to peak = 764 min
Hyd. volume = 10,861 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 54.90 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(1.040 \times 55) + (0.760 \times 61) + (0.340 \times 98) + (1.800 \times 77) + (0.060 \times 61)] / 4.000$



Hydrograph Report

28

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020

Hyd. No. 4


PROP. POINT B NO DET.

Hydrograph type = SCS Runoff
Storm frequency = 2 yrs
Time interval = 2 min
Drainage area = 12.450 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 3.07 in
Storm duration = 24 hrs

Peak discharge = 1.895 cfs
Time to peak = 784 min
Hyd. volume = 22,460 cuft
Curve number = 64*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.30 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(6.800 x 55) + (1.570 x 61) + (0.250 x 98) + (2.950 x 77) + (0.680 x 80) + (0.200 x 98)] / 12.450

PROP. POINT B NO DET.



Hydrograph Report

29

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 5

PROP. POINT B TO DET

Hydrograph type = SCS Runoff
Storm frequency = 2 yrs
Time interval = 2 min
Drainage area = 3.270 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 3.07 in
Storm duration = 24 hrs

Peak discharge = 1.451 cfs
Time to peak = 758 min
Hyd. volume = 10,691 cuft
Curve number = 73*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.70 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(0.730 \times 55) + (0.450 \times 61) + (0.220 \times 98) + (1.320 \times 77) + (0.350 \times 80) + (0.200 \times 98)] / 3.270$



Hydrograph Report

30

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020

Hyd. No. 6


PROP. POINT B DET. BY-PASS

Hydrograph type = SCS Runoff
Storm frequency = 2 yrs
Time interval = 2 min
Drainage area = 9.190 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 3.07 in
Storm duration = 24 hrs

Peak discharge = 0.977 cfs
Time to peak = 788 min
Hyd. volume = 13,007 cuft
Curve number = 61*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.40 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(5.830 x 55) + (1.120 x 61) + (0.030 x 98) + (1.870 x 77) + (0.340 x 80)] / 9.190

PROP. POINT B DET. BY-PASS



Hydrograph Report

31

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 7

DETENTION POND 1

Hydrograph type = Reservoir
Storm frequency = 2 yrs
Time interval = 2 min
Inflow hyd. No. = 5 - PROP. POINT B TO DET
Reservoir name = <New Pond>

Peak discharge = 0.552 cfs
Time to peak = 804 min
Hyd. volume = 10,575 cuft
Max. Elevation = 521.23 ft
Max. Storage = 4,050 cuft

Storage Indication method used.



Hydrograph Report

32

Hydraflow Hydrographs by Intelisolve v9.1


Saturday, Jan 4, 2020

Hyd. No. 9

TOTAL PROPOSED ANALYSIS POINT B

Hydrograph type = Combine
Storm frequency = 2 yrs
Time interval = 2 min
Inflow hyds. = 6, 7

Peak discharge = 1.512 cfs
Time to peak = 794 min
Hyd. volume = 23,582 cuft
Contrib. drain. area = 9.190 ac



Hydrograph Report

33

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 3

PROP. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 10 yrs
Time interval = 2 min
Drainage area = 4.000 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 4.87 in
Storm duration = 24 hrs

Peak discharge = 3.745 cfs
Time to peak = 760 min
Hyd. volume = 27,968 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 54.90 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(1.040 \times 55) + (0.760 \times 61) + (0.340 \times 98) + (1.800 \times 77) + (0.060 \times 61)] / 4.000$



Hydrograph Report

3A

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020

Hyd. No. 4

PROP. POINT B NO DET.


Hydrograph type = SCS Runoff
Storm frequency = 10 yrs
Time interval = 2 min
Drainage area = 12.450 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 4.87 in
Storm duration = 24 hrs

Peak discharge = 7.088 cfs
Time to peak = 776 min
Hyd. volume = 67,278 cuft
Curve number = 64*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.30 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(6.800 x 55) + (1.570 x 61) + (0.250 x 98) + (2.950 x 77) + (0.680 x 80) + (0.200 x 98)] / 12.450

PROP. POINT B NO DET.

Hyd. No. 4 -- 10 Year



Hydrograph Report

35

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 5

PROP. POINT B TO DET

Hydrograph type = SCS Runoff
Storm frequency = 10 yrs
Time interval = 2 min
Drainage area = 3.270 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 4.87 in
Storm duration = 24 hrs

Peak discharge = 3.762 cfs
Time to peak = 754 min
Hyd. volume = 25,865 cuft
Curve number = 73*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.70 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(0.730 \times 55) + (0.450 \times 61) + (0.220 \times 98) + (1.320 \times 77) + (0.350 \times 80) + (0.200 \times 98)] / 3.270$



Hydrograph Report

36

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020

Hyd. No. 6

PROP. POINT B DET. BY-PASS


Hydrograph type = SCS Runoff
Storm frequency = 10 yrs
Time interval = 2 min
Drainage area = 9.190 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 4.87 in
Storm duration = 24 hrs

Peak discharge = 4.342 cfs
Time to peak = 778 min
Hyd. volume = 42,857 cuft
Curve number = 61*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.40 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(5.830 \times 55) + (1.120 \times 61) + (0.030 \times 98) + (1.870 \times 77) + (0.340 \times 80)] / 9.190$

PROP. POINT B DET. BY-PASS

Hyd. No. 6 -- 10 Year



Hydrograph Report

37

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 7

DETENTION POND 1

Hydrograph type = Reservoir
Storm frequency = 10 yrs
Time interval = 2 min
Inflow hyd. No. = 5 - PROP. POINT B TO DET
Reservoir name = <New Pond>

Peak discharge = 1,839 cfs
Time to peak = 792 min
Hyd. volume = 25,744 cuft
Max. Elevation = 522.47 ft
Max. Storage = 9,210 cuft

Storage Indication method used.



Hydrograph Report

30

Hydraflow Hydrographs by Intelisolve v9.1


Saturday, Jan 4, 2020

Hyd. No. 9

TOTAL PROPOSED ANALYSIS POINT B

Hydrograph type = Combine
Storm frequency = 10 yrs
Time interval = 2 min
Inflow hyds. = 6, 7

Peak discharge = 6.092 cfs
Time to peak = 782 min
Hyd. volume = 68,601 cuft
Contrib. drain. area = 9.190 ac



Hydrograph Report

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 3

PROP. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 25 yrs
Time interval = 2 min
Drainage area = 4.000 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 5.99 in
Storm duration = 24 hrs

Peak discharge = 5.494 cfs
Time to peak = 758 min
Hyd. volume = 40,318 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 54.90 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(1.040 x 55) + (0.760 x 61) + (0.340 x 98) + (1.800 x 77) + (0.060 x 61)] / 4.000



Hydrograph Report

40

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020

Hyd. No. 4

PROP. POINT B NO DET.


Hydrograph type = SCS Runoff
Storm frequency = 25 yrs
Time interval = 2 min
Drainage area = 12.450 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 5.99 in
Storm duration = 24 hrs

Peak discharge = 11.12 cfs
Time to peak = 774 min
Hyd. volume = 101,414 cuft
Curve number = 64*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.30 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(6.800 x 55) + (1.570 x 61) + (0.250 x 98) + (2.950 x 77) + (0.680 x 80) + (0.200 x 98)] / 12.450

PROP. POINT B NO DET.

Hyd. No. 4 -- 25 Year



Hydrograph Report

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 5

PROP. POINT B TO DET

Hydrograph type = SCS Runoff
Storm frequency = 25 yrs
Time interval = 2 min
Drainage area = 3.270 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 5.99 in
Storm duration = 24 hrs

Peak discharge = 5.376 cfs
Time to peak = 754 min
Hyd. volume = 36,564 cuft
Curve number = 73*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.70 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(0.730 \times 55) + (0.450 \times 61) + (0.220 \times 98) + (1.320 \times 77) + (0.350 \times 80) + (0.200 \times 98)] / 3.270$



Hydrograph Report

42

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020

Hyd. No. 6


PROP. POINT B DET. BY-PASS

Hydrograph type = SCS Runoff
Storm frequency = 25 yrs
Time interval = 2 min
Drainage area = 9.190 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 5.99 in
Storm duration = 24 hrs

Peak discharge = 7.113 cfs
Time to peak = 776 min
Hyd. volume = 66,318 cuft
Curve number = 61*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.40 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(5.830 x 55) + (1.120 x 61) + (0.030 x 98) + (1.870 x 77) + (0.340 x 80)] / 9.190

PROP. POINT B DET. BY-PASS



Hydrograph Report

49

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 7

DETENTION POND 1

Hydrograph type = Reservoir
Storm frequency = 25 yrs
Time interval = 2 min
Inflow hyd. No. = 5 - PROP. POINT B TO DET
Reservoir name = <New Pond>

Peak discharge = 3.125 cfs
Time to peak = 786 min
Hyd. volume = 36,441 cuft
Max. Elevation = 523.10 ft
Max. Storage = 12,199 cuft

Storage Indication method used.



Hydrograph Report

44

Hydraflow Hydrographs by Intelisolve v9.1


Saturday, Jan 4, 2020

Hyd. No. 9

TOTAL PROPOSED ANALYSIS POINT B

Hydrograph type = Combine
Storm frequency = 25 yrs
Time interval = 2 min
Inflow hyds. = 6, 7

Peak discharge = 10.15 cfs
Time to peak = 780 min
Hyd. volume = 102,758 cuft
Contrib. drain. area = 9.190 ac



Hydrograph Report

45

Hydraflow Hydrographs by Intelisolve v9.1

Friday, Mar 13, 2020


Hyd. No. 3

PROP. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 50 yrs
Time interval = 2 min
Drainage area = 4.000 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 6.82 in
Storm duration = 24 hrs

Peak discharge = 6.859 cfs
Time to peak = 758 min
Hyd. volume = 50,004 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 54.90 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(1.040 \times 55) + (0.760 \times 61) + (0.340 \times 98) + (1.800 \times 77) + (0.060 \times 61)] / 4.000$



Hydrograph Report

AG

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020

Hyd. No. 4


PROP. POINT B NO DET.

Hydrograph type = SCS Runoff
Storm frequency = 50 yrs
Time interval = 2 min
Drainage area = 12.450 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 6.82 in
Storm duration = 24 hrs

Peak discharge = 14.34 cfs
Time to peak = 774 min
Hyd. volume = 128,781 cuft
Curve number = 64*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.30 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(6.800 \times 55) + (1.570 \times 61) + (0.250 \times 98) + (2.950 \times 77) + (0.680 \times 80) + (0.200 \times 98)] / 12.450$

PROP. POINT B NO DET.



Hydrograph Report

A7

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 5

PROP. POINT B TO DET

Hydrograph type = SCS Runoff
Storm frequency = 50 yrs
Time interval = 2 min
Drainage area = 3.270 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 6.82 in
Storm duration = 24 hrs

Peak discharge = 6.616 cfs
Time to peak = 754 min
Hyd. volume = 44,876 cuft
Curve number = 73*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.70 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(0.730 \times 55) + (0.450 \times 61) + (0.220 \times 98) + (1.320 \times 77) + (0.350 \times 80) + (0.200 \times 98)] / 3.270$



Hydrograph Report

AB

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020

Hyd. No. 6

PROP. POINT B DET. BY-PASS


Hydrograph type = SCS Runoff
Storm frequency = 50 yrs
Time interval = 2 min
Drainage area = 9.190 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 6.82 in
Storm duration = 24 hrs

Peak discharge = 9.363 cfs
Time to peak = 774 min
Hyd. volume = 85,362 cuft
Curve number = 61*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.40 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(5.830 \times 55) + (1.120 \times 61) + (0.030 \times 98) + (1.870 \times 77) + (0.340 \times 80)] / 9.190$

PROP. POINT B DET. BY-PASS

Hyd. No. 6 -- 50 Year



Hydrograph Report

A9

Hydraflow Hydrographs by Intelisolve v9.1

Saturday, Jan 4, 2020


Hyd. No. 7

DETENTION POND 1

Hydrograph type = Reservoir
Storm frequency = 50 yrs
Time interval = 2 min
Inflow hyd. No. = 5 - PROP. POINT B TO DET
Reservoir name = <New Pond>

Peak discharge = 4.184 cfs
Time to peak = 782 min
Hyd. volume = 44,752 cuft
Max. Elevation = 523.47 ft
Max. Storage = 14,206 cuft

Storage Indication method used.



Hydrograph Report

60

Hydraflow Hydrographs by Intelisolve v9.1


Saturday, Jan 4, 2020

Hyd. No. 9

TOTAL PROPOSED ANALYSIS POINT B

Hydrograph type = Combine
Storm frequency = 50 yrs
Time interval = 2 min
Inflow hyds. = 6, 7

Peak discharge = 13.46 cfs
Time to peak = 778 min
Hyd. volume = 130,115 cuft
Contrib. drain. area = 9.190 ac



Hydrograph Report

51

Hydraflow Hydrographs by Intelisolve v9.1

Friday, Mar 13, 2020


Hyd. No. 3

PROP. POINT A

Hydrograph type = SCS Runoff
Storm frequency = 100 yrs
Time interval = 2 min
Drainage area = 4.000 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 7.73 in
Storm duration = 24 hrs

Peak discharge = 8.397 cfs
Time to peak = 758 min
Hyd. volume = 61,014 cuft
Curve number = 70*
Hydraulic length = 0 ft
Time of conc. (Tc) = 54.90 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(1.040 \times 55) + (0.760 \times 61) + (0.340 \times 98) + (1.800 \times 77) + (0.060 \times 61)] / 4.000$



Hydrograph Report

52

Hydraflow Hydrographs by Intelisolve v9.1

Friday, Mar 13, 2020

Hyd. No. 4

PROP. POINT B NO DET.


Hydrograph type = SCS Runoff
Storm frequency = 100 yrs
Time interval = 2 min
Drainage area = 12.450 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 7.73 in
Storm duration = 24 hrs

Peak discharge = 18.05 cfs
Time to peak = 772 min
Hyd. volume = 160,335 cuft
Curve number = 64*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.30 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(6.800 x 55) + (1.570 x 61) + (0.250 x 98) + (2.950 x 77) + (0.680 x 80) + (0.200 x 98)] / 12.450

PROP. POINT B NO DET.

Hyd. No. 4 -- 100 Year



Hydrograph Report

53

Hydraflow Hydrographs by Intelisolve v9.1

Friday, Mar 13, 2020

Hyd. No. 5

PROP. POINT B TO DET


Hydrograph type = SCS Runoff
Storm frequency = 100 yrs
Time interval = 2 min
Drainage area = 3.270 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 7.73 in
Storm duration = 24 hrs

Peak discharge = 8.002 cfs
Time to peak = 754 min
Hyd. volume = 54,264 cuft
Curve number = 73*
Hydraulic length = 0 ft
Time of conc. (Tc) = 47.70 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = $[(0.730 \times 55) + (0.450 \times 61) + (0.220 \times 98) + (1.320 \times 77) + (0.350 \times 80) + (0.200 \times 98)] / 3.270$

PROP. POINT B TO DET

Hyd. No. 5 -- 100 Year



Hydrograph Report

SA

Hydraflow Hydrographs by Intelisolve v9.1

Friday, Mar 13, 2020

Hyd. No. 6

PROP. POINT B DET. BY-PASS


Hydrograph type = SCS Runoff
Storm frequency = 100 yrs
Time interval = 2 min
Drainage area = 9.190 ac
Basin Slope = 0.0 %
Tc method = TR55
Total precip. = 7.73 in
Storm duration = 24 hrs

Peak discharge = 11.97 cfs
Time to peak = 774 min
Hyd. volume = 107,504 cuft
Curve number = 61*
Hydraulic length = 0 ft
Time of conc. (Tc) = 77.40 min
Distribution = Type III
Shape factor = 484

* Composite (Area/CN) = [(5.830 x 55) + (1.120 x 61) + (0.030 x 98) + (1.870 x 77) + (0.340 x 80)] / 9.190

PROP. POINT B DET. BY-PASS

Hyd. No. 6 -- 100 Year



Hydrograph Report

55

Hydraflow Hydrographs by Intelisolve v9.1

Friday, Mar 13, 2020


Hyd. No. 7

DETENTION POND 1

Hydrograph type = Reservoir
Storm frequency = 100 yrs
Time interval = 2 min
Inflow hyd. No. = 5 - PROP. POINT B TO DET
Reservoir name = <New Pond>

Peak discharge = 5.457 cfs
Time to peak = 778 min
Hyd. volume = 54,139 cuft
Max. Elevation = 523.84 ft
Max. Storage = 16,160 cuft

Storage Indication method used.



Hydrograph Report

56

Hydraflow Hydrographs by Intelisolve v9.1


Friday, Mar 13, 2020

Hyd. No. 9

TOTAL PROPOSED ANALYSIS POINT B

Hydrograph type = Combine
Storm frequency = 100 yrs
Time interval = 2 min
Inflow hyds. = 6, 7

Peak discharge = 17.37 cfs
Time to peak = 776 min
Hyd. volume = 161,643 cuft
Contrib. drain. area = 9.190 ac



PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER 57
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

WATER QUALITY VOLUME (WQV)

SEE 7.4.1 OF THE 2004 CONNECTICUT STORMWATER QUALITY MANUAL

$$WQV = \frac{(1") (R) (A)}{12}$$

THE TOTAL IMPERVIOUS AREA OF THE PROPOSED DEVELOPMENT IS 19,790 SF (0.454 AC), ALL BUT 1,204 SF (0.028 AC) FLOWS TO THE DETENTION POND. THE 1,204 SF IS A SMALL PORTION OF THE PROPOSED SITE DRIVE WHERE IT APPROACHES KNOWWOOD DR. IT IS NOT PRACTICABLE TO DIRECT THE 1204 SF TO THE DETENTION POND. 96% OF THE IMPERVIOUS AREA IS DIRECTED TO THE DETENTION POND

WQV

$$\begin{aligned} \text{AREA TO DETENTION POND} &= 142,492 \text{ SF (3.27 AC)} \\ \text{TOTAL IMPERVIOUS AREA TO POND} &= 18,586 \text{ SF (0.43 AC)} \\ \% \text{ IMPERVIOUS} &= 18,586 / 142,492 = 13.04\% (I) \end{aligned}$$


$$\begin{aligned} R &= 0.05 + 0.009 \times I = 0.05 + 0.009 \times 13.04 \\ &= 0.1674 \end{aligned}$$

$$\begin{aligned} WQV &= \frac{(1) \times 0.1674 \times 3.27}{12} = 0.0456 \text{ AC/FT} \\ &= \underline{1,987 \text{ FT}^3} \approx 0.64' \text{ DEPTH IN POND} \end{aligned}$$

USE 0.7' DEPTH, VOL = 2161 FT³

AVG Q (40 HOUR DRAIN TIME) = 0.0150 CFS = 6.735 GPM

Stage / Storage



Pond Report

Hydraflow Hydrographs by Intelisolve v9.1

Friday, Mar 13, 2020

Pond No. 1 - <New Pond>

Pond Data

Contours - User-defined contour areas. Conic method used for volume calculation. Begining Elevation = 520.00 ft

Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	520.00	2,862	0	0
1.00	521.00	3,514	3,182	3,182
2.00	522.00	4,223	3,863	7,045
3.00	523.00	4,988	4,600	11,645
4.00	524.00	5,810	5,393	17,038
5.00	525.00	6,689	6,244	23,281
6.00	526.00	7,623	7,150	30,432


Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 15.00	5.25	0.81	0.00
Span (in)	= 15.00	5.25	0.81	0.00
No. Barrels	= 1	1	1	0
Invert El. (ft)	= 518.20	520.70	519.50	0.00
Length (ft)	= 55.40	0.50	0.00	0.00
Slope (%)	= 3.07	0.00	0.00	n/a
N-Value	= .012	.015	.013	n/a
Orifice Coeff.	= 0.60	0.80	0.61	0.60
Multi-Stage	= n/a	Yes	Yes	No

Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 0.00	8.00	Inactive	Inactive
Crest El. (ft)	= 521.20	524.00	0.00	0.00
Weir Coeff.	= 0.33	3.33	3.33	3.33
Weir Type	= 15 degV	Rect	---	---
Multi-Stage	= Yes	Yes	No	No
Exfil.(in/hr)	= 0.000 (by Wet area)			
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice condilions (ic) and submergence (s).



Submerged Orifices

Flow through a submerged orifice may be computed by applying Bernoulli's equation to points 1 and 2 in figure below


$$V_2 = \sqrt{2g \left(h_1 - h_2 + \frac{V_1^2}{2g} - h_L \right)}$$

where h_L = losses in head, ft (m), between 1 and 2.

By assuming $V_1 \approx 0$, setting $h_1 - h_2 = \Delta h$, and using a coefficient of discharge C to account for losses, the following formula is obtained:

$$Q = C_a \sqrt{2g \Delta h}$$

C = ORIFICE COEFFICIENT (0.61)
 FOR SHARP EDGE ORIFICE
 g = 32.2 FT/SEC²
 a = ORIFICE AREA
 h = HEAD



Values of C for submerged orifices do not differ greatly from those for nonsubmerged orifices.

Advertisements

ORIFICE SIZING

AVG Q REQUIRED FOR 40HR, 2161 FT³ =

$$\frac{2161}{144,000} = 0.0150 \text{ CFS}$$

$$0.0150 = 0.61a \sqrt{64.4 \times 0.7}$$

$$0.0150 = 4.0956a$$

$$a = 0.00366 \text{ FT}^2 = 0.5274 \text{ IN}^2 \quad \phi \approx \underline{\underline{13/16}}$$



Free Business Insurance Quote

Contact Us Today To Get Your Free Quote! - CV Mason Insurance Agency

3. DISCHARGE COEFFICIENT VALUES

3.1 Relationship to Resistance coefficient K

The discharge coefficient may be directly related to the [resistance coefficient](#) via the follow equation:

$$K = \frac{1}{C_d^2}$$

3.2 Typical Values for Discharge Coefficient C_d

For simple pressure loss or flow rate calculations where high accuracy is not critical the following typical values may be used:

Equipment Type	β min	β max	C_d
Orifice Plate, thin sharp edged	-	-	0.61
Venturi Nozzle, Machined	0.4	0.75	0.995
Venturi Nozzle, Rough Welded Sheet Metal	0.4	0.70	0.985
Venturi Nozzle, Rough Cast	0.3	0.77	0.984

3.3 Precise Relationships for Discharge Coefficient

Where a higher degree of accuracy is required, such as for flow rate measurement, the relationships below may be used.

$$C_d = C_{\infty} + \frac{b}{Re^n}$$

Values for C_{∞} , b and n are presented below. Dimensions in millimeters.


Device	$C_{d,\infty}$
Venturi Nozzle, Machined Inlet	0.995
Venturi Nozzle, Cast Inlet	0.984
	0.985

PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER 12
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

RETENTION POND OUTLET PROTECTION

SEE 2002 GUIDELINES FOR EROSION & SEDIMENT CONTROL
FIGURE LS-4 PG 5-10-5

TAILWATER $< 0.5 D_o$, $Q_{100} = 5.47 \text{ CFS}$



$$L_g = \frac{1.7 Q}{D_o^{3/2}} + 8 D_o$$

$$= \frac{1.7 \times 5.47}{1.25^{1.5}} + 8 \times 1.25$$

$$= 16.65', \text{ USE } 17'$$

$$W = 3 D_o + L_g$$

$$= 3 \times 1.25 + 16.65$$

$$= 20.4', \text{ USE } 21'$$

STONE SIZE

$$D_{50} = \left(\frac{0.02}{T_{10}} \right) \left(\frac{Q}{D_o} \right)^{4/3}$$

$$= \left(\frac{0.02}{0.06} \right) \left(\frac{5.47}{1.25} \right)^{1.333}$$

$$\approx 0.23' (3'') \text{ USE MODIFIED RIPRAP}$$

07



North American Green
 5401 St. Wendel-Cynthiana Rd.
 Poseyville, Indiana 47633
 Tel. 800.772.2040
 >Fax 812.867.0247
 www.nagreen.com
 ECMDS v7.0

CHANNEL ANALYSIS

> > Detention Pond Outlet

Name Detention Pond Outlet
 Discharge 5.5
 Peak Flow Period 12
 Channel Slope 0.14
 Channel Bottom Width 6
 Left Side Slope 2
 Right Side Slope 2
 Existing Bend Radius 53
 Low Flow Liner
 Retardence Class C 6-12 in
 Vegetation Type None
 Vegetation Density None
 Soil Type Fine Sand (ML)

Rock Riprap

Phase	Reach	Discharge	Velocity	Normal Depth	Mannings N	Permissible Shear Stress	Calculated Shear Stress	Safety Factor	Remarks	Staple Pattern
Rock Riprap Unvegetated	Straight	5.5 cfs	5.1 ft/s	0.17 ft	0.032	2 lbs/ft ²	1.39 lbs/ft ²	1.44	STABLE	--
Rock Riprap Unvegetated	Bend	5.5 cfs	5.1 ft/s	0.17 ft	0.032	2 lbs/ft ²	1.68 lbs/ft ²	1.19	STABLE	--



CA

North American Green
 5401 St. Wendel-Cynthiana Rd.
 Poseyville, Indiana 47633
 Tel. 800.772.2040
 >Fax 812.867.0247
 www.nagreen.com
 ECMDS v7.0

ANALYSIS COMPUTATIONS

>>> [View Computation](#)

Inputs	
Channel Discharge (Q):	5.5 cfs
Peak Flow Period (H):	12 hours
Channel Slope (S0):	0.14 ft/ft
Bottom Width (B):	6 ft
Left Side Slope (ZL):	2 (H : V)
Right Side Slope (ZR):	2 (H : V)
Existing Channel Bend:	Yes
Bend Coefficient (Kb):	
Channel Bend Radius:	53 ft
Retardance Class of Vegetation:	C 6-12 in
Vegetation Type:	None
Vegetation Density:	None
Soil Type:	Fine Sand (ML)
Channel Lining Options	
Rock Riprap Protection Type	Permanent

Basic Relationships
$A = \text{Cross sectional area, ft}^2 \text{ (m}^2\text{)} = (B * D) + (Z_L / 2 * D^2) + (Z_R / 2 * D^2)$
Where:
B = Base width of channel, ft (m)
D = Flow depth, ft (m)
Z _L = Left side bank slope (H : 1 V)
Z _R = Right side bank slope (H : 1 V)
P = Wetted perimeter, ft (m) = B + Z _L * D + Z _R * D
R = Hydraulic radius, ft (m) = A / P
V = Flow velocity, ft/s (m/s) = Q / A
Where:
Q = Channel discharge, cfs (cms)
$\tau_{avg} = \text{Average bed shear stress, psf (Pa)} = 62.4 * R * S_0$
Where:
S ₀ = Gradient of channel, ft/ft (m/m)
$\tau_{max} = \text{Maximum bed shear stress, psf (Pa)} = 62.4 * D * S_0$

Unvegetated Conditions Computations:
$n = \text{Manning's } n = a * \tau_{avg}^b$
and (iteratively solved)
$n = 1.486 / Q * A * R^{(2/3)} S_0^{0.5}$
Where:
n = Manning's n
a = Product specific coefficient from performance testing
b = Product specific coefficient from performance testing
SF _p = Product factor of safety = τ_{avg} / τ_{max}


65

Where:
τ_{uT} = Permissible shear stress from testing, psf (Pa)
τ_{uP} = In place permissible shear, psf (Pa) = $\tau_{uT} / \alpha * (\tau_{us} + \alpha / 4.3)$
Where:
α = unit conversion constant, 0.14 English, 6.5 Metric
τ_{us} = Permissible shear stress of soil
SFL = Factor of safety of installed liner = τ_{uP} / τ_{ua}

Vegetated Computations:
n = Manning's $n = \alpha * C_n * \tau_{ua}^{-0.4}$
and (iteratively solved)
$n = 1.486 / Q * A * R(2/3) S_o^{0.5}$
Where:
α = Unit conversion constant, 0.213 English, 1.0 Metric
C_n = Vegetation retardance coefficient
SF _v = Product factor of safety = τ_{uTv} / τ_{uo}
Where:
τ_{uTv} = Permissible shear stress from testing, psf (Pa)
τ_{uP} = In place permissible shear, psf (Pa) = $\tau_{us} / (1 - C_{TRM}) * (n / n_s)^2$
Where:
C_{TRM} = Coefficient of TRM performance derived from testing τ_{us} = Permissible shear stress of soil
n_s = Manning's of soil bed if left unprotected
SFL = Factor of safety of installed liner = τ_{uP} / τ_{ua}

Rock Riprap

Phase	Mannings N	Predicted flow depth (D)	Cross sectional area (A)	Wetted perimeter (P)	Hydraulic radius (R)	Flow velocity (V)	Froude number (FR)	Calculated Shear Stress	SFP/SFL
Rock Riprap Unvegetated	0.032	0.17 ft	1.08 ft ²	6.76 ft	0.16 ft	5.1 ft/s	2.25	1.39 lbs/ft ²	1.44 (SFP)
Rock Riprap Unvegetated	0.032	0.17 ft	1.08 ft ²	6.76 ft	0.16 ft	5.1 ft/s	2.25	1.68 lbs/ft ²	1.19 (SFL)



STORM SEWER DESIGN - AREA TO INLETS, "I" & TC

RATIONAL METHOD

$Q = CIA$

10 YR STORM

$I = 0.2$ WOODS

$= 0.3$ GRASS

$= 0.9$ PAVEMENT

* 12" HDPE

TOTAL AREA = 4,705 SF = 0.108 AC

	CA
WOODS = 898 + 623 = 1521 = 0.035 AC @ 0.2	= 0.007
GRASS = 3184 SF = 0.073 AC @ 0.3	= 0.022
PAVED = 0	= 0.036
	<u>Σ 0.036</u>

USE $T_c = 5$ MIN (SHALLOW LEDGE) $Q_{10} = 1.076 \times 6.0 = 0.226$ CFS

* YD# 1

TOTAL AREA = 22,610 SF = 0.519 AC

	CA
WOODS = 14778 SF = 0.339 AC @ 0.2	= 0.068
GRASS = 3032 SF = 0.070 AC @ 0.3	= 0.021
PAVED = 4,800 SF = 0.110 AC @ 0.9	= 0.099
	<u>Σ 0.188</u>

T_c 150' @ 15.6% WOODS $m=0.1$
 134' @ 19% UNPAVED
 192' @ 61% PAVED

$Q_{10} =$

} 37 MIN - SEE WORKSHEET

TR55 Tc Worksheet

68

Hyd. No. 2

YD #1

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.100	0.011	0.011	
Flow length (ft)	= 150.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 3.07	0.00	0.00	
Land slope (%)	= 0.16	0.00	0.00	
Travel Time (min)	= 27.75	+ 0.00	+ 0.00	= 27.75
Shallow Concentrated Flow				
Flow length (ft)	= 134.00	192.00	0.00	
Watercourse slope (%)	= 0.19	0.06	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	= 0.70	0.50	0.00	
Travel Time (min)	= 3.18	+ 6.37	+ 0.00	= 9.55
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	= 0.00	0.00	0.00	
Flow length (ft)	= 0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				37.00 min

PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER 19
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

* YD # 2

TOTAL AREA = 5142 SF = 0.118 AC

WOODS = 1141 SF = 0.026 AC @ 0.2 = 0.052

GRASS = 1010 SF = 0.023 AC @ 0.3 = 0.007

PAVED = 2991 SF = 0.069 AC @ 0.9 = 0.062

Σ 0.121

USE TC = 5 MIN (MOSTLY PAVED)

* YD # 3

TOTAL AREA = 1803 SF = 0.041 AC

WOODS = 78 SF = 0.002 AC @ 0.2 = 0.0004

GRASS = 98 SF = 0.002 AC @ 0.3 = 0.0006

PAVED = 1627 SF = 0.037 AC @ 0.9 = 0.0333

Σ 0.034

TC USE 5 MIN - MOSTLY PAVED - USE C = 0.9 FOR ALL

* YD # 4

TOTAL AREA = 43,708 SF = 1.003 AC

WOODS = 35,864 SF = 0.823 AC @ 0.2 = 0.165

GRASS = 5,545 SF = 0.127 AC @ 0.3 = 0.038

PAVED = 2,299 SF = 0.053 AC @ 0.9 = 0.048

Σ 0.251

TC 150' @ 17.3% WOODS m = 0.10

310' @ 21.6 UNPAVED

= 34' - SEE WORKSHEET

@ 0.10 = .251 x 2.7 = 0.68

TR55 Tc Worksheet

10

Hyd. No. 5

YD #4

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.100	0.011	0.011	
Flow length (ft)	= 150.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 3.07	0.00	0.00	
Land slope (%)	= 0.17	0.00	0.00	
Travel Time (min)	= 26.63	+ 0.00	+ 0.00	= 26.63
Shallow Concentrated Flow				
Flow length (ft)	= 318.00	0.00	0.00	
Watercourse slope (%)	= 0.22	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	= 0.75	0.00	0.00	
Travel Time (min)	= 7.07	+ 0.00	+ 0.00	= 7.07
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	= 0.00	0.00	0.00	
Flow length (ft)	= 0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				34.00 min

PREPARED BY	DATE PREPARED	DUTTON ASSOCIATES, LLC 67 EASTERN BOULEVARD GLASTONBURY, CONNECTICUT 06033 TEL: (860)-633-9401 FAX: (860)-633-8851 EMAIL: JIMD@DUTTONASSOCIATESLLC.COM	JOB NUMBER	PAGE NUMBER
CHECKED BY	DATE CHECKED		CLIENT NAME	TOTAL PAGES

11

X YD # 5

TOTAL AREA = 801 SF = 0.018 AC @ 0.9 = 0.016

ALL PAVED, USE C = 0.9, TC = 5 MIN

X YD # 6

TOTAL AREA = 6055 SF = 0.139 AC

WOODS = 0

CA

GRASS = 3032 SF = 0.07 AC @ 0.2 = 0.014

PAVED = 3023 SF = 0.069 AC @ 0.9 = 0.062
 ± 0.076

USE TC = 5 MIN (50% PAVED)

X HDPE MA # 1

CA

TOTAL AREA = 2450 SF (ROOF) = 0.056 AC @ 0.9 = 0.050

USE TC = 5 MIN (ALL PAVED)

$\phi_{10} = 0.30$

USE C = 0.9 (ALL PAVED)

PROJECT: CASELLA SUBDIVISION
 PROJECT N 3098
 TOWN: GLASTONBURY
 ROUTE:
 LOCATION: KNOLLWOOD DR

DESIGNED BY: JWD DATE: 01/05/20
 CHECKED BY: JRM DATE:

GUTTER FLOW ANALYSIS - 10 YR STORM

Inlet ID	Area in Acres (A)	Time to Inlet (min.)	Rainfall Intensity (in/hr)	AC	Total AC	Q to Inlet (cfs)	Grade of Gutter ft/ft (S _L)	Cross Slope Of Shoulder ft/ft (S _s)	Depth of Flow of Gutter (ft)	Gutter Flow Width (ft)	Q Bypassing Inlet (cfs)	AC Bypassing Inlet	AC Entering Catch Basin	Inlet Type	Grate Width (ft)
YD #1	0.519	37	2.6	0.188	0.188	0.489	0.120	0.031	0.082	2.628	0.061	0.023	0.165	20"SQ	1.7
YD #2	0.118	5	6	0.121	0.144	0.867	0.148	0.031	0.098	3.132	0.181	0.030	0.114	20"SQ	1.7
YD #3	0.041	5	6	0.034	0.064	0.385	0.140	0.031	0.073	2.335	0.028	0.005	0.069	20"SQ	1.7
YD #5	0.018	5	6	0.016	0.021	0.124	0.148	0.031	0.047	1.513	0.000	0.000	0.021	20"SQ	1.7
YD #6 AT LOW POINT															
YD #6	0.139	5	6	0.076	0.076	0.456	0.000	0.031	0.166	5.351				20"SQ	1.7

72

STORM SEWER SYSTEM DESIGN

Client: CASELLA

Project: 3098

Town: GLASTONBURY

Return Period for Design: 10-YR

Prepared By: JWD

Checked By: JRM

Date: 1-/03/2019

Date:

Line Segment From To	Time to Inlet (min.)	Time in Pipe (min.)	Accumul. Time (min.)	A x C Entering System	Sum of A x C in System	Rainfall Intensity, I (in./hr.)	Q in System (c.f.s.)	Pipe Data				Inlet Control HW				
								Size (in.)	Length (ft.)	Slope (ft./ft.)	Avg. Vel. (f.p.s.)	Full Cap. (c.f.s.)	Depth (ft.)	Manning "n"	HW/D	H (ft.)
12"HDPE YD1	5	0.09	5.0	0.036	0.036	6.0	0.22	12	28.4	0.091	5.5	11.66	0.10	0.012	>0.5	>0.5
YD1 YD2	37	0.41	37.0	0.165	0.201	2.6	0.52	12	200	0.141	8.2	14.49	0.13	0.012	>0.5	>0.5
YD2 YD3	5	0.14	37.4	0.114	0.315	2.6	0.82	12	75.5	0.142	9.2	14.52	0.17	0.012	>0.5	>0.5
YD3 YD4	34	0.06	34.0	0.251	0.251	2.7	0.68	12	31.5	0.016	9.0	4.86	0.25	0.012	>0.5	>0.5
YD4 YD5	5	0.10	38.1	0.059	0.374	2.5	0.94	12	60.4	0.099	9.8	12.16	0.13	0.012	>0.5	>0.5
YD5 YD6	5	0.11	38.2	0.021	0.395	2.6	1.03	12	54.6	0.064	8.3	9.77	0.21	0.012	>0.5	>0.5
YD6 MH1	5	0.17	38.3	0.016	0.411	2.5	1.03	12	80.4	0.106	8.0	12.54	0.20	0.012	>0.5	>0.5
MH1 MH2	5	0.13	38.5	0.05	0.461	2.5	1.15	12	93.6	0.107	9.8	12.61	0.19	0.012	0.63	0.63
MH2 MH3	0	0.13	38.6	0	0.461	2.5	1.15	12	100	0.190	13.0	16.82	0.17	0.012	0.63	0.63
MH3 12"CE	0	0.11	38.7	0	0.461	2.5	1.15	12	95.7	0.225	14.0	18.29	0.16	0.012	0.63	0.63

**PROJECT: 03098-CASELLA
DUTTON ASSOCIATES, LLC**

SEE CONNECTICUT DOT DRAINAGE MANUAL SECTION 11-11

BY: JWD

DATE: 01/03/2020

CHECKED BY: JRM

DATE: 01/03/2020

10 YEAR STORM EVENT

Station	Tw	D _o	Q _o	L _o	V _o	V _o ² /2g	H _o	SF _o	H _i	K _s	C _o	C _d	C _o	C _p	C _s	K	K(V _o ² /2g)	EGLo	EGLi	HGL	Surface Elev	Pipe Area	Hyd. Rad.
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
12"HDPE -YD1	636.50	1	0.2	28.4	5.5	0.47	0.5	0.0000	0	0.2	1	1	1	1	1	0.15	0.0705	637.0	637.0	636.6	638.0	0.785	0.3969
YD1 -YD2	633.90	1	0.5	200	8.2	1.044	1	0.0002	0.04	0.2	1	1	1	1	1	0.15	0.1566	634.9	635.1	634.1	636.9	0.785	0.3969
YD2-YD3	605.70	1	1.2	75.5	9.2	1.314	1.3	0.0010	0.07	1.0	1	1	1	1	1	0.95	1.2486	607.0	608.3	607.0	608.7	0.785	0.3969
YD4-YD3	592.50	1	10.9	31.5	9	1.258	1.3	0.0798	2.51	1.5	1	1	1	1	1	1.5	1.8866	593.8	598.2	596.9	598.0	0.785	0.3969
YD3-YD5	586.00	1	10.4	60.4	9.8	1.491	1.5	0.0726	4.39	1.5	1	1	1	1	1	1.5	2.2370	587.5	594.1	592.6	589.0	0.785	0.3969
YD5-YD6	582.50	1	1.2	54.8	8.3	1.07	1.1	0.0010	0.05	1.0	1	1	1	1	1	0.95	1.0162	583.6	584.6	583.6	585.5	0.785	0.3969
YD6-MH1	574.50	1	8.4	80.4	8	0.994	1	0.0474	3.81	0.5	1	1	1	1	1	0.45	0.4472	575.5	579.7	578.8	574.0	0.785	0.3969
MH1-MH2	561.13	1	3.8	93.6	9.8	1.491	1.5	0.0097	0.91	0.2	1	1	1	1	1	0.15	0.2237	562.6	563.8	562.3	654.0	0.785	0.3969
MH2-MH3	542.13	1	7.1	100	13	2.624	2.6	0.0338	3.38	0.2	1	1	1	1	1	0.15	0.3936	544.8	548.5	545.9	545.3	0.785	0.3969
MH3-OUT	523.00	1	6.8	95.7	14	3.043	3	0.0310	2.97	0.2	1	1	1	1	1	0.15	0.4565	526.0	529.5	526.4	526.0	0.785	0.3969

HGL 25-yr PROPOSED



Job No. 4-10-14

8 April 2010

Mr. Jim Dutton
Dutton Associates, LLC
67 Eastern Boulevard
Glastonbury, CT 06033

LOCATION: Casella property,
Knollwood Drive, Glastonbury,
Connecticut

15

SOILS AND WETLANDS REPORT

INSPECTION DATE:	4/7/10
MAP PROVIDED:	topographical
CONTOUR INTERVAL SHOWN	2 ft
SCALE SHOWN:	40
SOIL MOISTURE CONDITIONS:	moist
PROPERTY LINES IDENTIFIABLE:	not clear
WETLAND FLAG NUMBERING SEQUENCE:	#1 - #29

This site inspection was conducted to evaluate the presence of inland-wetlands and watercourses. A detailed classification of the soils was not part of this study. Field observations of the wetland and upland soils together with the classification system of the National Cooperative Soil Survey, USDA, and the County Soil Legend were used in this investigation to identify the soil series names.

In conducting field investigations, soil borings are taken from which many important soil properties are observed, as follows: seasonal soil moisture condition OR the presence of free water and its depth, for each horizon in the soil profile, the thickness, color and texture are also observed. The areas shown on soil maps are called soil map units. Some map units consist of one kind of soil while others consist of two or more kinds of soil. A few have little or no soil material at all. The information in this report is based on examination and interpretation of soils with the use of a hand auger and shovel. Wetland delineation is based on prevailing conditions at the time of investigation and best professional judgment. Field conditions may change over time.

COMMENTS: This parcel is situated south of the cul-de-sac of Knollwood Drive and comprises hilly, rocky land which slopes to the south and southwest. Shallow bedrock controls the topography and outcroppings are noted in the vicinity. Southwest of the parcel property line, on property of Mr. and Mrs. George Mikk, is a valley/swale area that receives drainage from the surrounding hillsides. A wetland was identified at the top of this valley and behind a house located on the west side of the cul-de-sac. The boundary of the wetland was delineated and continued along the watercourse which drains out of the wetland towards the south. At the bottom of the steep incline, the watercourse broadens out into a larger wetland. As requested, only the east side of the wetlands and watercourse were delineated since this drainage is not on the subject parcel of Mr. Casella.

Soils formed in glacial till and descriptions are included below for convenience.

WETLAND SOILS

SOIL TYPE:	LEICESTER
DEPTH TO MOTTLING:	6"
DEPTH TO BEDROCK:	>60"
DEPTH TO SEASONAL HIGH WATER TABLE:	0-8"

A poorly drained soil on nearly level or gently sloping land, the Leicester series consist of soils that developed in friable to firm glacial till. These soils occupy wet, low-lying areas or concave side slope areas. The permeability of the soils is moderate in the surface layer and subsoil and is moderately rapid in the substratum.

SOIL TYPE:	WHITMAN
DEPTH TO MOTTLING:	18"
DEPTH TO BEDROCK:	>60"
DEPTH TO SEASONAL HIGH WATER TABLE:	0-6"

These very poorly drained soils occur in low-lying, small to medium sized areas where they receive runoff and, in places, material washed from surrounding soils. A typical profile has a surface layer of black stony, fine sandy loam or silt loam about 10 inches thick. Next is a strongly gleyed subsurface layer of gray to light gray loamy sand. The subsoil, which is gleyed, consists of gray and greenish-gray fine sandy loam that is distinctly mottled with various shades of brown.

NON-WETLAND SOILS

SOIL TYPE:	CHARLTON-HOLLIS
DEPTH TO MOTTLING:	NO MOTTLING
DEPTH TO BEDROCK:	CHARLTON - >60"; HOLLIS - 10-20"
DEPTH TO SEASONAL HIGH WATER TABLE:	>6'

This is a complex of well-drained soils found on gently sloping and sloping, uplands where the relief is affected by the underlying bedrock. Slopes may be either concave or convex. The areas frequently have a rough surface topography with bedrock outcrops and a few narrow intermittent drainageways and small wet depressions. Included with this complex in mapping, are small areas, generally less than 1 acre in size, of moderately well-drained Sutton soils, well-drained Paxton soils and poorly drained Leicester soils. In a few areas the stones and boulders have been cleared. Also included are many small and intermingled areas where the bedrock is 20-40 inches from the

Page 3
Job No 4-10-12

surface. During construction, conservation measures are essential to prevent excessive runoff, erosion and siltation.


SOIL TYPE:	GLOUCESTER
DEPTH TO MOTTLING:	NONE
DEPTH TO BEDROCK:	>60"
DEPTH TO SEASNAL	
HIGH WATER TABLE:	>40"

A somewhat excessively drained soil that developed in very friable, coarse-textured glacial till derived mainly from coarse-textured granite but in places included some gneiss. The soil material has a relatively high sand content. Permeability is rapid.


Sincerely yours,



Cynthia M. Rabinowitz
Soil Scientist/Landscape Designer



Soil Map—State of Connecticut



Soil Map may not be valid at this scale.

Map Scale: 1:3,550 if printed on A landscape (11" x 8.5") sheet.

Map projection: Web Mercator Corner coordinates: WGS84 Edge tic: UTM Zone 18N WGS84

21

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
3	Ridgebury, Leicester, and Whitman soils, 0 to 8 percent slopes, extremely stony	0.0	0.0%
52C	Sutton fine sandy loam, 2 to 15 percent slopes, extremely stony	1.9	3.5%
62D	Canton and Charlton fine sandy loams, 15 to 35 percent slopes, extremely stony	1.8	3.4%
73C	Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky	16.9	31.5%
73E	Charlton-Chatfield complex, 15 to 45 percent slopes, very rocky	21.1	39.3%
75E	Hollis-Chatfield-Rock outcrop complex, 15 to 45 percent slopes	10.2	18.9%
306	Udorthents-Urban land complex	1.8	3.3%
Totals for Area of Interest		53.7	100.0%

80

State of Connecticut

73E—Charlton-Chatfield complex, 15 to 45 percent slopes, very rocky

Map Unit Setting

National map unit symbol: 9lql
Elevation: 0 to 1,200 feet
Mean annual precipitation: 43 to 56 inches
Mean annual air temperature: 45 to 55 degrees F
Frost-free period: 140 to 185 days
Farmland classification: Not prime farmland

Map Unit Composition

Charlton and similar soils: 45 percent
Chatfield and similar soils: 30 percent
Minor components: 25 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Charlton

Setting

Landform: Hills
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss

Typical profile

Ap - 0 to 4 inches: fine sandy loam
Bw1 - 4 to 7 inches: fine sandy loam
Bw2 - 7 to 19 inches: fine sandy loam
Bw3 - 19 to 27 inches: gravelly fine sandy loam
C - 27 to 65 inches: gravelly fine sandy loam

Properties and qualities

Slope: 15 to 45 percent
Percent of area covered with surface fragments: 1.6 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat):
Moderately high to high (0.57 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s

82

Hydrologic Soil Group: B
Hydric soil rating: No

Description of Chatfield

Setting

Landform: Ridges, hills
Down-slope shape: Convex
Across-slope shape: Linear
Parent material: Coarse-loamy melt-out till derived from granite and/or schist and/or gneiss

Typical profile

Oa - 0 to 1 inches: highly decomposed plant material
A - 1 to 6 inches: gravelly fine sandy loam
Bw1 - 6 to 15 inches: gravelly fine sandy loam
Bw2 - 15 to 29 inches: gravelly fine sandy loam
2R - 29 to 80 inches: unweathered bedrock

Properties and qualities

Slope: 15 to 45 percent
Percent of area covered with surface fragments: 1.6 percent
Depth to restrictive feature: 20 to 40 inches to lithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Low to high (0.01 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 3.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: B
Hydric soil rating: No



Minor Components

Rock outcrop

Percent of map unit: 10 percent
Hydric soil rating: No

Leicester

Percent of map unit: 5 percent
Landform: Drainageways, depressions
Down-slope shape: Linear
Across-slope shape: Concave
Hydric soil rating: Yes

Sutton

Percent of map unit: 5 percent
Landform: Drainageways, depressions
Down-slope shape: Concave

93

Across-slope shape: Linear
Hydric soil rating: No

Hollis

Percent of map unit: 3 percent
Landform: Hills, ridges
Down-slope shape: Convex
Across-slope shape: Convex
Hydric soil rating: No

Unnamed, sandy subsoil

Percent of map unit: 1 percent
Hydric soil rating: No

Unnamed, red parent material

Percent of map unit: 1 percent
Hydric soil rating: No

Data Source Information

Soil Survey Area: State of Connecticut
Survey Area Data: Version 19, Sep 13, 2019

8A

State of Connecticut

73C—Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky

Map Unit Setting

National map unit symbol: 2w698

Elevation: 0 to 1,550 feet

Mean annual precipitation: 36 to 71 inches

Mean annual air temperature: 39 to 55 degrees F

Frost-free period: 140 to 240 days

Farmland classification: Not prime farmland

Map Unit Composition

Charlton, very stony, and similar soils: 50 percent

Chatfield, very stony, and similar soils: 30 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Charlton, Very Stony

Setting

Landform: Hills, ridges

Landform position (two-dimensional): Backslope, shoulder, summit

Landform position (three-dimensional): Crest, side slope, nose slope

Down-slope shape: Linear, convex

Across-slope shape: Convex

Parent material: Coarse-loamy melt-out till derived from granite, gneiss, and/or schist

Typical profile

Oe - 0 to 2 inches: moderately decomposed plant material

A - 2 to 4 inches: fine sandy loam

Bw - 4 to 27 inches: gravelly fine sandy loam

C - 27 to 65 inches: gravelly fine sandy loam

Properties and qualities

Slope: 3 to 15 percent

Percent of area covered with surface fragments: 1.6 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat):

Moderately low to high (0.14 to 14.17 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Salinity, maximum in profile: Nonsaline (0.0 to 1.9 mmhos/cm)

Available water storage in profile: Moderate (about 8.7 inches)

85

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: B
Hydric soil rating: No

Description of Chatfield, Very Stony

Setting

Landform: Hills, ridges
Landform position (two-dimensional): Backslope, summit, shoulder
Landform position (three-dimensional): Crest, side slope, nose slope
Down-slope shape: Convex
Across-slope shape: Linear, convex
Parent material: Coarse-loamy melt-out till derived from granite, gneiss, and/or schist

Typical profile

O_i - 0 to 1 inches: slightly decomposed plant material
A - 1 to 2 inches: fine sandy loam
B_w - 2 to 30 inches: gravelly fine sandy loam
2R - 30 to 40 inches: bedrock

Properties and qualities

Slope: 3 to 15 percent
Percent of area covered with surface fragments: 1.6 percent
Depth to restrictive feature: 20 to 41 inches to lithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (K_{sat}): Very low (0.00 to 0.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline (0.0 to 1.9 mmhos/cm)
Available water storage in profile: Low (about 4.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
→ *Hydrologic Soil Group:* B
Hydric soil rating: No

Minor Components

Sutton, very stony

Percent of map unit: 5 percent
Landform: Hills, ground moraines
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Linear

Hydric soil rating: No

Rock outcrop

Percent of map unit: 5 percent

Hydric soil rating: No

Hollis, very stony

Percent of map unit: 5 percent

Landform: Ridges, hills

Landform position (two-dimensional): Backslope, shoulder, summit

Landform position (three-dimensional): Crest, side slope, nose slope

Down-slope shape: Convex

Across-slope shape: Linear, convex

Hydric soil rating: No

Leicester, very stony

Percent of map unit: 5 percent

Landform: Drainageways, depressions

Down-slope shape: Linear

Across-slope shape: Concave

Hydric soil rating: Yes

Data Source Information

Soil Survey Area: State of Connecticut

Survey Area Data: Version 19, Sep 13, 2019

Appendix - SCS Soils Groups

ELEVATION>7500	C	DRAINED, SANDY	LARIAT	B	LAUGENOUR, DRAINED	B	LEAKSVILLE	D
LAINAND	B	SUBSTRATUM	LARIC	D	LOAMY SUBSTRATUM	C	LEAL	B
LAIRD	B	LANDAVASO	LARIM	B	LAUGHLIN	C	LEALANDIC	D
LAIRDSVILLE	D	LANDCO	LARIMER	B	LAUGHLIN	D	LEANNA	D
LAJARA	D	LANDER	LARIOSCAMP	D	LAUMAIA	B	LEANTO	D
LAJITAS	D	LANDES	LARKIN	B	LAURAMIE	B	LEAPS	C
LAKASH	B	LANDES	LARKSON	C	LAUREL	D	LEATHAM	C
LAKASKIA	D	LANDES	LARMINE	D	LAUREL	C	LEATHERBARK, STONY	C
LAKE	A	LANDINGHAM	LAROQUE	B	LAURELWOOD	B	LEATHERMAN	D
CLAYEY SURFACE	C	LANDLOW	LAROSE	D	LAUREN	B	LEATHERWOOD	B
LAKE CHARLES	D	LANDLOW	LAROSS	B	CEMENTED	C	LEAVENWORTH	C
LAKE CREEK	C	LANDMAN	LARPENTEUR	B	SUBSTRATUM	C	LEAVERS	B
LAKE JANEE	B	LANDO	LARRUPIN	B	LAURENTZEN	B	LEAVITT	B
LAKEFIELD	B	LANDUSKY	LARRY	D	LARISTEN	B	CLAY SUBSTRATUM	D
LAKEHELEN	C	LANE	LARRY	C	LAVA FLOWS	D	WET	C
LAKEHURST	A	LANESBORO	LARRY	C	STONY	A	WET	C
LAKELAND	A	LANEVILLE	DRAINED	C	STONY	A	LEAVITTVILLE	B
LAKEMONT	D	LANEXA	STONY	C	LAVACREEK	B	LEBAM	B
LAKEPARK	B/D	LANEY	LARSON	D	LAVACREEK	C	LEBANON	C
LAKEPORT	B	LANFAIR	LARTON	A	LAVALLEE	B	LEBEAU	D
LAKESHORE	D	LANG, CLAYEY	LARUE	A	LAVATE	B	LEBEC	B
LAKESIDE, DRAINED	B	SUBSTRATUM	LARUSH	B	SANDY SUBSTRATUM	C	LEBO	B
LAKESOL	B	LANGELLAIN	LARUSH	C	SANDY SUBSTRATUM	C	LEBRON	D
LAKETON	C	LANGER	LARVIE	D	LAVEAGA	C	LEBSACK	C
LAKEVIEW	C	LANGFORD	LAS	C	LAVEAGA	D	LECK KILL, DEEP	C
LAKEWIN	B	LANGHEI	LAS	D	LAVEEN	B	LECKMAN	B
LAKEWOOD	A	LANGLADE	CLAYEY SUBSTRATUM	D	LAVELDO, HARDPAN	D	LECOMA	B
LAKI	B	LANGLESS	SALINE	D	SUBSTRATUM	C	LECRAG	D
LAKIN	A	LANGLOIS	LAS ANIMAS	C	LAVELGA	B	LEDFORD	B
LAKOA	B	LANGOLA	LAS ANIMAS	D	LAVENDER	B	LEDGFORK	A
LAKOMA	D	LANGRELL	CHANNELED	D	LAVENTANA	B	LEDMOUNT	D
LAKOTA	D	LANGSLET	FREQUENTLY	D	COOL	C	LEDOW	B
LAKRIDGE	C	LANGSPRING	FLOODED	D	LAVERRIN	C	LEDRU	D
LALAAU	A	LANGSTON	POORLY DRAINED	D	LAVEY	D	LEDWITH	B/D
LALINDA	B	LANGTRY	LAS FLORES	D	LAVIC	B	LEE	D
LALLIE	D	LANIER	LAS LUCAS	B	LAVINA	D	LEEBENCH	C
LALOS	B	LANIGER	LAS POSAS	C	LAWAI	B	LEEBENCH	D
LAM	D	LANIP	LAS VEGAS	D	LAWEN	B	COLD	D
LAMA	C	LANKBUSH	LAS VEGAS	C	LAWET	B/D	GRAVELLY	D
LAMANGA	C	LANKIN	LASA	A	LAWLER	B	SUBSTRATUM	D
LAMAR	B	LANKTREE	LASALLE	D	LAWNDALE	B	LEEDS	C
LAMARSH	C	LANOAK	LASAUSES	D	LAWNES	D	LEEFIELD	C
LAMARTINE	C	LANONA	LASCO	B	LAWNWOOD	B/D	LEEKO	C
LAMATH, DRAINED	D	LANQUE	LASERE	C	DEPRESSIONAL	D	COOL	B
LAMAWA	B	LANSDALE	LASH	B	LAWRENCE	C	WARM	B
LAMBERT	B	LANSDOWNE	LASIL	D	LAWRENCEVILLE	C	LEELANAU	A
LAMBETH	B	LANSING	LASKA	B	LAWRIE	B	LEEMONT	D
LAMBMAN	D	LANTERN	LASSEL	C	LAWSHE	D	LEEPER	D
COOL	C	LANTIS	LASSEN	D	LAWSON	C	LEERAY	D
LAMBRING	B	LANTON	LASSITER	B	LAWTHER	D	LEESBURG	B
LAMEDEER	B	LOW PRECIPITATION	LASTANCE	B	LAWTON	C	LEESVILLE	B
LAMESHUR	A	LANTONIA	LASVAR	C	LAWYER	B	LEETONIA	C
LAMINE	D	LANTRY	LATAH	D	LAWYER	C	LEEVAN	C
LAMINGTON	D	LANTZ	DRAINED	C	BEDROCK	C	LEFOR	B
LAMKIN	B	LANVER	HIGH RAINFALL;	C	SUBSTRATUM	B	LEGALL	B
LAMO	C	LOAMY	DRAINED	C	LAX	C	LEGAULT	D
LAMOILLE	B	LANYON	LATAHCO	C	LAXAL	C	LEGGETT	C
LAMOINE	D	LAOLAO	WET	D	LAXTON	C	LEGLER	B
LAMONDI	B	LAONA, VERY STONY	LATANIER	D	LAYCOCK	B	LEGORE	B
LAMONI	C	LAP	LATCH	A	LAYOINT	C	LEHEW	C
LAMONT	B	LAPARITA	LATENE	B	LAYTON	A	LEHIGH	C
LAMONTA	D	LAPDUN	LATES	C	DRY	B	LEHMANS, COBBLY	D
LAMOOSE	D	LAPED	LATEX	C	LAYVIEW	D	LEHR	B
LAMOTTE	B	LAPEER	LATHAM	D	LAZAN	D	LEICESTER	C
LAMOURE	D	LAPHAM	LATHER	D	LAZBUDDIE	D	LEIDL	C
LAMOURE	C	LAPINE	LATHROP	B	LAZEAR	D	LEIGHCAN	B
SALINE	C	LAPLATTA	LATIGO	B	LE BAR	B	LEILEHUA	B
SANDY SUBSTRATUM	C	LAPOINT	LATIMER	D	LE SUEUR	B	LEISY	B
SOMEWHAT POORLY	D	LAPON	LATINA	D	LEA	C	LEITER	C
DRAINED	C	LAPORTE	LATIUM	D	LEADER	B	LELA	D
LAMPASAS	D	LAPOSA	LATOM	D	LEADORE	B	LELAND	D
LAMPHER	B	LAPPANS	LATONIA	B	LEADPOINT	C	LEMAH	A
LAMPSHIRE	D	LAPWAI	LATOUCHE	D	LEADVALE	C	LEMBO	C
LAMSON	B/D	LARABEE	LATOUR	B	LEADVILLE	B	LEMCAYE	B
LANADA	C	LARAND	LATOURELL	B	LEAF	D	LEMCO	C
LANARK	B	LARCHMOUNT	LATTAS	D	LEAFRIVER	A/D	LEMERT	D
LANCASTER	B	LARCHPOINT	LATTY	D	LEAFU	C	LEMETA	D
LANCE	B	LARDELL	LAUBY	B	LEAGUE	D	LEMHI	D
LAND	C	LAREDO	LAUDERDALE	D	LEAGUEVILLE	B/D	LEMING	C
DRAINED	D	LARES	LAUDERHILL	B/D	LEAHY	C	LEMITAR	D
DRAINED	B	LARGO, FLOODED	LAUFER	D	LEAKEY	D	LEMM	B

WEISBURG	C	WESO	B	WHEELON	D	WHOLAN	B	COBBLY	C
WEISER	B	WESPAC	C	WHEELRIDGE	B	WHOMEE	D	WILLOWBROOK	C
WEISHAUP	D	ALKALI	D	WHERRY	A	WHORLED	C	WILLOWDALE	B
WEISSENFELS	C	WESSEL	C	WHETROCK	D	WHY	B	WILLOWEMOC	C
WEITAS	B	WESTBEND	B	WHETSOON	C	WIBAUX	B	WILLOWMAN	B
WEITCHPEC	C	WESTBROOK	D	WHETSTONE	C	WICHITA	C	WILLOWS,ALKALI	D
WEITCHPEC	D	WESTBURY	C	WHICHMAN	C	WICHUP	D	WILLWOOD	A
BEDROCK		WESTBUTTE	C	WHIDBEY	B	WICKAHONEY	D	WILLYNAT	B
SUBSTRATUM	B	WESTCAMP,MODERATELY		WHILPHANG	C	WICKENBURG	D	WILMA	C
WEKIVA	D	WET	C	WHIPPANY	D	WICKERSHAM	B	GRAVELLY	B
WEKODA	D	WESTCREEK	B	WHIPPLE	C	WICKETT	C	STONY	B
WELAKA	A	WESTE	C	WHIPPLE	D	WICKHAM	B	WILMER	C
WELBY	B	WESTERVILLE	B	WHIPSTOCK	B	WICKIUP	C	WILMER	B
WELCH	D	WESTFAN	B	WHIRLO	C	WICKSBURG	B	WILMINGTON	D
DRAINED	C	WESTFORK	D	WHISK	B	WICKWARE	B	WILMONT	B
GRAVELLY		WESTGATE	C	WHISKEY	D	WICUP	C	WILMONTON	B
SUBSTRATUM;		WESTGUARD	B	WHISKEYCREEK	B	WIDEMAN	A	WILPAR	C
DRAINED	C	WESTHAVEN	B	WHISKEYDICK	C	WIDEN	C	WILPOINT	D
RARELY FLOODED;		ALKALI; WET	C	WHISKEYLAKE	C	WIDTSON	B	WILSALL	D
DRAINED	B	SALINE-SODIC	C	WHISPERING	C	WIEHL	C	WILSHIRE	A
WELCHLAND	B	WESTINDIAN	C	WHISTLE	C	WIELAND	C	WILSON	D
WELCOME	B	WESTLAKE	D	WHITAKER	B	WIERGATE	D	WILSONGULCH	B
WELD	C	THIN SURFACE	C	WHITAKER	B	WIFFO	B	WILSONVILLE	D
WELDA	C	WESTLAND	B/D	WHITAKER	C	WIFTON	B	WILSOR	B
WELEETKA	B	WESTMORE	C	WHITE HOUSE	B	WIGGLER	D	WILST	C
WELLER	C	WESTMORELAND	B	GRAVELLY	C	WIGGLETON	B	WILST	B
WELLIE	A	WESTOLA	B	WHITE STORE	D	WIGTON	A	WILT	B
WELLINGTON	C	WESTON	D	WHITE SWAN	D	WIKIEUP	D	WILTON	B
WELLINGTON	D	WESTOVER	B	WHITE EARTH	D	WILAH	B	WIMPER	B
WELLMAN	B	WESTPHALIA	B	WHITEBIRD	C	WILBANKS	D	WIMPEY	C
WELLS	B	WESTPLAIN	D	WHITECAP	D	WILBRAHAM	C	WINADA	C
WELLSBENCH	B	WESTPORT	A	WHITECLOUD	D	WILBUR	B	WINADA	B
WELLSBORO	C	THIN SURFACE	B	WHITECOW	B	WILBURTON	B	WINBERRY	C
WELLSCREEK	B	WESTRACO	D	WHITECROSS	B	WILCO	C	WINBLOW	C
WELLSDAM	C	WESTSHORE	D	WHITEDEER	D	WILCOX	D	WINCHESTER	A
WELLED	C	WESTSIDE	C	WHITEFACE	B	WILCOXSON	C	WINCHUCK	C
WELLSFAR	B	WESTSUM	D	WHITEFIELD	D	WILDALE	C	WIND RIVER	B
WELLSFORD	D	WESTVACO	C	WHITEFISH	D	WILDCAT	D	WINDCOAT	D
WELLSTON	B	WESTVIEW	B	WHITEFORD	B	WILDER	B	WINDEGO	B
WELLSVILLE	B	WESTVILLE	B	WHITEHALL	B	WILDERNESS	C	WINDER	B/D
WELLTON	B	WESTWEGO	D	WHITEHILLS	B	WILDGEN	B	WINDER	C/D
WELLOY	C	WESWIND	C	WHITEHORN	C	WILDHILL	C	DEPRESSIONAL	D
WELRING	D	WESWOOD	B	WHITEHORSE	D	WILDHORSE	A	WINDHAM	B
WELSUM	D	WETA	D	WHITEKNOB	B	WILDMESA	C	WINDHAM	C
WELTER	D	WETBETH	C	WHITELAKE	B	WILDORS	C	WINDICREEK	A
WEMPLE	B	WETHERILL	B	WHITEMAN	B	WILDROSE	C	WINDLASS	C
WENAS	D	WETHERSFIELD	C	WHITEOAK	D	WILDWOOD	D	WINDMILL	B
DRAINED	C	WETHEY	C	WHITEPEAK	B	WILE	C	ACID	C
WENATCHEE	C	DRAINED	A	WHITEPINE	D	WILEY	B	WINDRY	D
GRAVELLY	B	WETMORE	D	WHITERIVER	D	WILHITE	C/D	WINDSOR	A
NONSTONY	B	WETOPA	C	WHITEROCK	C	WILHOIT	B	WINDTHORST	C
WENDANE	C	WETSAND	D	WHITESBORO	D	WILKES	C	WINDWHISTLE	C
DRAINED	B	WETSAW	C	WHITESBURG	C	WILKESON	B	WARM	B
WENDELL	C	WETTERDON	B	WHITESIDE	C	WILKINS	D	WINDY	B
WENDOVER	D	WETTERHORN	C	WHITELAKE	B	WILL	B/D	WINDYGAP	B
WENDTE	D	WETZEL	D	WHITESTONE	D	WILLABY	C	WINDYHOLLOW	C
WENGLER	A	WEVERTON	B	WHITETHORN	B	WILLACY	B	WINDYPOINT	B
WENONA,MODERATELY		WEWELA	B	WHITEWATER	B	WILLAKENZIE	C	WINE DALE	D
WET	C	WEWOKA	C	WHITEWOLF	B	WILLAMAR	B	WINEG	B
WENONAH	B	WEYANOKE	C	WHITEWOLF	D	WILLAMETTE	B	WINEMA	C
WENOTA	D	WEYERS	C/D	WHITEWOOD	A	WET	C	WINETTI	B
WENTWORTH	B	WEYMOUTH	B	WHITING	C	WILLANCH	D	WINEVADA	B
WEOGUFKA	C	WHAKANA	B	WHITING	C/D	WILLAPA	C	WINEVADA	C
WEOTT	D	WHALAN	B	WHITING	B/D	WILLARD	B	WINFALL	B
WEPO	C	WHALESHEAD	B	WHITING	C	WILLDIN	C	WINFIELD	B
WERELD	B	WHALEY	D	WHITING	C	WILLETTTE	A/D	WING	D
WERITO	C	WHARTON	C	WHITING	D	WILLHILL	C	WINGATE	B
WERLOG,COOL	C	WHATCOM	C	WHITING	C	WILLHO	D	WINGDALE	D
MODERATELY WELL		WHATELY	D	WHITING	D	WILLIAMS	B	WINGER	B/D
DRAINED	B	WHEATBELT	D	WHITING	B	WILLIAMS	B	WINGINA	B
STRONGLY SALINE	B	WHEATLEY	A/D	WHITING	B	WILLIAMS	B	WINGINAW	D
WERNER	D	WHEATON	B	WHITING	C	WILLIAMS	C	WINGROCK	B
WERNOCK	B	WHEATRIDGE	B	WHITING	C	WILLIAMS	C	WINGVILLE	D
WERNOCK	C	WHEATVILLE	B	WHITING	B	WILLIAMS	C	WINIFRED	C
WESCONNETT	D	WHEATWOOD	B	WHITING	B	WILLIAMS	B/D	WINK	C
WESDY	C	WHEELER	B	WHITING	D	WILLIS	C	WINKEL	D
WESDY	B	WHEELERPEK	D	WHITING	C/D	WILLIS	D	WINKLEMAN	C
WESFIL	D	WHEELERVILLE	B	WHITING	B	WILLISTON	C	WET	D
WESIX	D	WHEELING	C	WHITING	D	WILLOCK	B	WINKLER	B
WESKA	D	WHEELING	B	WHITING	C	WILLOSIPPI	C	WINKLO	C
WESLEY	B	FLOODED	B	WHOBREY	C	WILLOW CREEK	B	WINLER	D

89

NOAA Atlas 14, Volume 10, Version 3 HARTFORD
BRAINARD FLD
Station ID: 06-3451



Location name: Hartford, Connecticut, USA*
Latitude: 41.7333°, Longitude: -72.65°
Elevation:
Elevation (station metadata): 20 ft**



* source: ESRI Maps
** source: USGS

POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps & aeriels](#)

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.331 (0.265-0.413)	0.404 (0.322-0.504)	0.522 (0.415-0.655)	0.620 (0.490-0.782)	0.755 (0.575-1.00)	0.857 (0.637-1.16)	0.963 (0.693-1.36)	1.08 (0.734-1.57)	1.25 (0.815-1.89)	1.39 (0.882-2.15)
10-min	0.469 (0.375-0.585)	0.572 (0.457-0.714)	0.740 (0.589-0.928)	0.879 (0.695-1.11)	1.07 (0.815-1.42)	1.21 (0.904-1.65)	1.37 (0.982-1.93)	1.53 (1.04-2.23)	1.78 (1.15-2.68)	1.97 (1.25-3.04)
15-min	0.552 (0.441-0.688)	0.673 (0.537-0.840)	0.870 (0.692-1.09)	1.03 (0.818-1.30)	1.26 (0.959-1.67)	1.43 (1.06-1.94)	1.61 (1.16-2.27)	1.81 (1.23-2.62)	2.09 (1.36-3.15)	2.32 (1.47-3.58)
30-min	0.742 (0.593-0.925)	0.904 (0.722-1.13)	1.17 (0.931-1.47)	1.39 (1.10-1.75)	1.69 (1.29-2.24)	1.92 (1.43-2.61)	2.16 (1.56-3.06)	2.43 (1.65-3.53)	2.82 (1.83-4.24)	3.13 (1.98-4.82)
60-min	0.931 (0.744-1.16)	1.14 (0.907-1.42)	1.47 (1.17-1.84)	1.75 (1.38-2.20)	2.13 (1.62-2.82)	2.42 (1.80-3.28)	2.72 (1.96-3.84)	3.06 (2.07-4.43)	3.54 (2.30-5.34)	3.93 (2.49-6.07)
2-hr	1.22 (0.979-1.51)	1.48 (1.19-1.83)	1.90 (1.52-2.36)	2.25 (1.79-2.82)	2.73 (2.10-3.61)	3.09 (2.32-4.19)	3.48 (2.53-4.92)	3.93 (2.67-5.67)	4.60 (3.00-6.90)	5.17 (3.28-7.92)
3-hr	1.41 (1.14-1.73)	1.70 (1.37-2.10)	2.19 (1.76-2.71)	2.59 (2.07-3.23)	3.14 (2.42-4.14)	3.56 (2.68-4.80)	4.00 (2.92-5.65)	4.53 (3.09-6.51)	5.34 (3.48-7.97)	6.02 (3.83-9.19)
6-hr	1.75 (1.43-2.15)	2.13 (1.73-2.61)	2.75 (2.22-3.38)	3.25 (2.61-4.04)	3.96 (3.07-5.18)	4.47 (3.40-6.02)	5.04 (3.71-7.09)	5.73 (3.92-8.18)	6.79 (4.44-10.1)	7.70 (4.91-11.7)
12-hr	2.12 (1.73-2.58)	2.60 (2.12-3.17)	3.38 (2.75-4.13)	4.02 (3.25-4.95)	4.91 (3.83-6.39)	5.57 (4.25-7.44)	6.28 (4.66-8.80)	7.16 (4.92-10.2)	8.53 (5.60-12.6)	9.70 (6.21-14.6)
24-hr	2.47 (2.03-2.99)	3.07 (2.63-3.72)	4.05 (3.32-4.93)	4.87 (3.96-5.96)	5.99 (4.71-7.78)	6.82 (5.25-9.09)	7.73 (5.78-10.8)	8.88 (6.12-12.5)	10.7 (7.06-15.7)	12.3 (7.91-18.4)
2-day	2.81 (2.33-3.37)	3.55 (2.94-4.27)	4.77 (3.93-5.76)	5.77 (4.73-7.02)	7.16 (5.68-9.27)	8.17 (6.35-10.9)	9.30 (7.05-13.1)	10.8 (7.48-15.2)	13.3 (8.80-19.4)	15.6 (10.0-23.1)
3-day	3.05 (2.54-3.65)	3.87 (3.22-4.64)	5.21 (4.31-6.27)	6.32 (5.20-7.65)	7.85 (6.25-10.1)	8.95 (6.99-11.9)	10.2 (7.78-14.4)	11.9 (8.24-16.6)	14.7 (9.74-21.4)	17.3 (11.1-25.6)
4-day	3.27 (2.73-3.90)	4.14 (3.45-4.94)	5.56 (4.61-6.66)	6.73 (5.55-8.13)	8.36 (6.67-10.8)	9.53 (7.46-12.6)	10.9 (8.29-15.2)	12.7 (8.78-17.8)	15.7 (10.4-22.7)	18.4 (11.9-27.1)
7-day	3.83 (3.22-4.55)	4.80 (4.02-5.70)	6.37 (5.31-7.60)	7.68 (6.36-9.21)	9.48 (7.59-12.1)	10.8 (8.46-14.2)	12.2 (9.36-17.0)	14.2 (9.89-19.7)	17.4 (11.6-25.1)	20.3 (13.1-29.8)
10-day	4.42 (3.72-5.23)	5.43 (4.57-6.43)	7.09 (5.93-8.42)	8.46 (7.03-10.1)	10.3 (8.30-13.1)	11.7 (9.20-15.3)	13.3 (10.1-18.2)	15.3 (10.7-21.1)	18.5 (12.3-26.5)	21.3 (13.8-31.2)
20-day	6.36 (5.39-7.47)	7.43 (6.29-8.73)	9.17 (7.73-10.8)	10.6 (8.88-12.6)	12.6 (10.1-15.8)	14.1 (11.1-18.1)	15.7 (11.9-21.1)	17.6 (12.4-24.1)	20.6 (13.8-29.2)	23.1 (15.0-33.6)
30-day	8.04 (6.84-9.40)	9.14 (7.76-10.7)	10.9 (9.24-12.8)	12.4 (10.4-14.7)	14.5 (11.6-17.9)	16.0 (12.5-20.3)	17.6 (13.3-23.3)	19.4 (13.7-26.4)	22.1 (14.8-31.2)	24.3 (15.8-35.1)
45-day	10.2 (8.67-11.8)	11.3 (9.63-13.2)	13.1 (11.2-15.4)	14.7 (12.4-17.3)	16.8 (13.6-20.6)	18.4 (14.5-23.2)	20.1 (15.1-26.2)	21.8 (15.4-29.5)	24.1 (16.3-33.9)	25.9 (16.9-37.3)
60-day	11.9 (10.2-13.9)	13.1 (11.2-15.2)	15.0 (12.8-17.6)	16.6 (14.1-19.5)	18.8 (15.2-23.0)	20.6 (16.1-25.6)	22.2 (16.6-28.7)	23.9 (17.0-32.1)	25.9 (17.5-36.3)	27.4 (17.9-39.4)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical

DURATION (min)	DURATION (hr)	RAINFALL INTENSITY (in/hr)					
		2 Yr	5 Yr	10 Yr	25 Yr	50 Yr	100 Yr
5	0.08	4.6	5.5	6.0	6.7	7.3	7.8
6	0.10	4.4	5.2	5.8	6.5	7.0	7.5
7	0.12	4.2	5.0	5.5	6.2	6.8	7.2
8	0.13	4.0	4.8	5.3	6.0	6.5	7.0
9	0.15	3.8	4.6	5.1	5.7	6.2	6.7
10	0.17	3.6	4.3	4.8	5.5	6.0	6.5
11	0.18	3.4	4.2	4.7	5.3	5.8	6.3
12	0.20	3.3	4.0	4.5	5.1	5.6	6.1
13	0.22	3.1	3.8	4.3	5.0	5.4	5.9
14	0.23	3.0	3.7	4.2	4.8	5.3	5.7
15	0.25	2.8	3.5	4.0	4.6	5.1	5.5
16	0.27	2.8	3.5	3.9	4.5	5.0	5.4
17	0.28	2.7	3.4	3.8	4.4	4.9	5.4
18	0.30	2.7	3.3	3.8	4.4	4.8	5.3
19	0.32	2.6	3.2	3.7	4.3	4.7	5.2
20	0.33	2.5	3.2	3.6	4.2	4.6	5.1
21	0.35	2.5	3.1	3.5	4.1	4.5	5.0
22	0.37	2.4	3.0	3.4	4.0	4.4	4.9
23	0.38	2.3	2.9	3.4	3.9	4.3	4.8
24	0.40	2.3	2.9	3.3	3.8	4.2	4.7
25	0.42	2.2	2.8	3.2	3.7	4.2	4.6
26	0.43	2.2	2.7	3.1	3.7	4.1	4.5
27	0.45	2.1	2.7	3.0	3.6	4.0	4.4
28	0.47	2.0	2.6	3.0	3.5	3.9	4.3
29	0.48	2.0	2.5	2.9	3.4	3.8	4.2
30	0.50	1.9	2.4	2.8	3.3	3.7	4.1

Rainfall Intensity/Duration/Frequency Relationship for Connecticut (English Units)
Table B-2.1

a1

		RAINFALL INTENSITY (in/hr)					
DURATION	DURATION	2 Yr	5 Yr	10 Yr	25 Yr	50 Yr	100 Yr
31	0.52	1.9	2.4	2.8	3.3	3.6	4.0
32	0.53	1.9	2.4	2.7	3.2	3.6	4.0
33	0.55	1.8	2.4	2.7	3.2	3.6	3.9
34	0.57	1.8	2.3	2.7	3.2	3.5	3.9
35	0.58	1.8	2.3	2.6	3.1	3.5	3.8
36	0.60	1.8	2.3	2.6	3.1	3.4	3.8
37	0.62	1.7	2.2	2.6	3.0	3.4	3.7
38	0.63	1.7	2.2	2.5	3.0	3.4	3.7
39	0.65	1.7	2.2	2.5	3.0	3.3	3.7
40	0.67	1.7	2.1	2.5	2.9	3.3	3.6
41	0.68	1.6	2.1	2.4	2.9	3.2	3.6
42	0.70	1.6	2.1	2.4	2.8	3.2	3.5
43	0.72	1.6	2.1	2.4	2.8	3.1	3.5
44	0.73	1.6	2.0	2.3	2.8	3.1	3.4
45	0.75	1.5	2.0	2.3	2.7	3.1	3.4
46	0.77	1.5	2.0	2.3	2.7	3.0	3.3
47	0.78	1.5	1.9	2.2	2.6	3.0	3.3
48	0.80	1.5	1.9	2.2	2.6	2.9	3.2
49	0.82	1.5	1.9	2.2	2.6	2.9	3.2
50	0.83	1.4	1.8	2.1	2.5	2.8	3.2
51	0.85	1.4	1.8	2.1	2.5	2.8	3.1
52	0.87	1.4	1.8	2.1	2.5	2.8	3.1
53	0.88	1.4	1.8	2.0	2.4	2.7	3.0
54	0.90	1.3	1.7	2.0	2.4	2.7	3.0
55	0.92	1.3	1.7	2.0	2.3	2.6	2.9
56	0.93	1.3	1.7	1.9	2.3	2.6	2.9
57	0.95	1.3	1.6	1.9	2.3	2.5	2.8
58	0.97	1.2	1.6	1.9	2.2	2.5	2.8
59	0.98	1.2	1.6	1.8	2.2	2.5	2.7
60	1.00	1.2	1.5	1.8	2.1	2.4	2.7

Rainfall Intensity/Duration/Frequency Relationship for Connecticut (English Units)
Table B-2.1 continued





CHART 35

12"

PIPE FLOW CHART
12-INCH DIAMETER

92

Chart 12



EXAMPLE

D = 36 inches (3.0 feet)
Q = 66 cfs


	HW/D	HW (feet)
(1)	1.8	5.4
(2)	2.1	6.3
(3)	2.2	6.6

^aD in feet

HW/D	ENTRANCE TYPE
(1)	Headwall
(2)	Mitered to conform to slope
(3)	Projecting

To use scale (2) or (3) project horizontally to scale (1), then use straight inclined line through D and Q scales, or reverse as illustrated.

HEADWATER DEPTH FOR C. M. PIPE CULVERT WITH INLET CONTROL





DUTTON ASSOCIATES, LLC
 LAND SURVEYORS AND CIVIL ENGINEERS
 67 EASTERN BOULEVARD
 GLASTONBURY, CONNECTICUT 06033
 TEL: 860-633-9401 FAX: 860-633-8951
 EMAIL: JMD@DUTTONASSOCIATESLLC.COM

JOHN R. MARTUCCI, P.E. #19494

THIS DOCUMENT IS AN INSTRUMENT OF PROFESSIONAL SERVICE AND SHALL NOT BE USED IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN THAT SPECIFICALLY STATED HEREIN. THE APPROVED WRITTEN CONSENT OF DUTTON ASSOCIATES, LLC, ANY UNAUTHORIZED USE, REUSE, MODIFICATION OR CONVERSION OF THIS DOCUMENT IS NOT ALLOWED AND IF SUCH OCCURS, THE OFFENDER PROCEEDS TO THE FULL EXTENT OF THE LAW.
 © 2019 - DUTTON ASSOCIATES, LLC

DRAINAGE AREA PLAN - EXISTING CONDITIONS
 DETENTION POND ROUTING
 CASELLA SUBDIVISION
 KNOLLWOOD DRIVE
 PREPARED FOR:
THE ESTATE OF JON CASELLA
 GLASTONBURY, CONNECTICUT

REVISIONS:
DATE: 03/16/2020
SCALE: 1" = 40'
SHEET 1 of 3
A-03-098-DA
FILE: 03098-SUBDIVISION 2020-DA.DWG



DUTTON ASSOCIATES, LLC
LAND SURVEYORS AND CIVIL ENGINEERS
67 EASTERN BOULEVARD
GLASTONBURY, CONNECTICUT 06033
TEL: 860-633-9401 FAX: 860-633-8951
EMAIL: JMD@DUTTONASSOCIATESLLC.COM

JOHN R. MARTUCCI, P.E. #19494

THIS DOCUMENT IS AN INSTRUMENT OF PROFESSIONAL SERVICE AND SHALL NOT BE USED IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS CREATED WITHOUT THE WRITTEN CONSENT OF DUTTON ASSOCIATES, LLC. ANY UNAUTHORIZED USE, REUSE, MODIFICATION OR REPRODUCTION OF THIS DOCUMENT IS NOT ALLOWED AND IF SUCH OCCURS, THE OFFENDER IS SUBJECT TO THE FULL EXTENT OF THE LAW. © 2019 - DUTTON ASSOCIATES, LLC

DRAINAGE AREA PLAN - PROPOSED CONDITIONS
DETENTION POND ROUTING
CASELLA SUBDIVISION
KNOLLWOOD DRIVE
PREPARED FOR
THE ESTATE OF JON CASELLA
GLASTONBURY, CONNECTICUT

REVISIONS:




DATE: 03/16/2020

SCALE: 1" = 40'

SHEET 2 of 3

A-03-098-DA

FILE: 03098-SUBDIVISION 2020-DA.DWG



DUTTON ASSOCIATES, LLC
LAND SURVEYORS AND CIVIL ENGINEERS
67 EASTERN BOULEVARD
GLASTONBURY, CONNECTICUT 06033
TEL: 860-633-9401 FAX: 860-633-8951
EMAIL: JMD@DUTTONASSOCIATESLLC.COM

JOHN R. MARTUCCI, P.E. #19494

THIS DOCUMENT IS AN INSTRUMENT OF PROFESSIONAL SERVICE AND SHALL NOT BE USED IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN THAT SPECIFICALLY SET FORTH HEREIN. THE JURISDICTION OF DUTTON ASSOCIATES, LLC, ANY UNAUTHORIZED USE, REUSE, MODIFICATION OR REPRODUCTION OF THIS DOCUMENT IS NOT ALLOWED AND IF SUCH OCCURS, THE OFFENDER PROCEEDS TO THE FULL EXTENT OF THE LAW.
© 2019 - DUTTON ASSOCIATES, LLC

DRAINAGE AREA PLAN - PROPOSED CONDITIONS
AREA TO INLETS - STORM SEWER DESIGN
CASELLA SUBDIVISION
KNOLLWOOD DRIVE
PREPARED FOR
THE ESTATE OF JON CASELLA
GLASTONBURY, CONNECTICUT

REVISIONS:

DATE: 03/16/2020
SCALE: 1" = 40'
SHEET 3 of 3
A-03-098-DA
FILE: 03098-SUBDIVISION 2020-DA.DWG