



S2510, LLC	TOWN CENTER ZONE
PROJECT/APPLICANT	ZONE
#2520 MAIN STREET	
PROJECT ADDRESS	
SECTION 12.9	
SPECIAL PERMIT SECTION	TP2 CHAIRMAN
DATE SPECIAL PERMIT APP'D	DIRECTOR OF COMMUNITY DEVELOPMENT
FILE NO.	

**ZONING INFORMATION**  
 ZONE: TOWN CENTER ZONE  
 AREA = 67,069 S.F. = 1.539 AC.

**SETBACK REQUIREMENTS**

	REQUIRED	PROVIDED #2510	PROVIDED #2520
FRONT YARD:	20'	29.8'	144.9'
REAR YARD:	20'	176'	58.1'
SIDE YARD:	8'	10.4'	8.3'

**LOT COVERAGE**


BUILDING COVERAGE = 15,457 S.F. 23.1%  
 PAVEMENT COVERAGE = 33,643 S.F. 50.1%  
 OPEN SPACE = 17,969 S.F. 26.8% (15% MIN.)  
 67,069 S.F. 100.0%  
 F.A.R. = 15,300 S.F./67,069 S.F. = 0.228

**PARKING TABLE**

#2510 MAIN STREET  
 EXISTING BANK:  
 5,500 S.F. 1ST. FL. X 80% X 1/200 = 22 SPACES  
 1,200 S.F. 2ND. FL. X 80% X 1/200 = 5 SPACES  
 TOTAL BANK = 27 SPACES (REQ.)


#2520 MAIN STREET  
 EXIST RETAIL/MEDICAL/OFFICE USE: 5,103 S.F. X 80% X 1/150 = 27.2 SPACES (REQ.)  
 PROP. 3,497 S.F. RESTAURANT 56 SEATS X 1 SPACE/3 SEATS = 18.7 SPACES (REQ.)  
 TOTAL SITE = 73 SPACES (REQ.)  
 PARKING PROVIDED = 73 SPACES (3 H.C.)

**SITE LOCATION MAP**  
 SCALE: 1"=1,000'



**LEGEND**

EXISTING SPOT ELEVATION	48X38
EXIST. LIGHT POLE	LP
APPROX. LOC. EXIST. SANITARY LATERAL	S



EXISTING BUILDING LOCATED IN FIELD AS SHOWN ON 2-29-16

REFERENCE MADE TO MAP TITLED:  
 "RECORD DRAWING #2520 MAIN STREET PREPARED FOR SCHWARTZ REAL ESTATE GLASTONBURY, CONN." BY MEGSON, HEAGLE & FRIEND C.E. & L.S. GLASTONBURY, CONN. DATE: 3-2-16 MAP NO. 6-15-1RD

"SITE PLAN MODIFICATION - CHANGE OF USE #2520 MAIN STREET PREPARED FOR SCHWARTZ REAL ESTATE GLASTONBURY, CONN." BY MEGSON, HEAGLE & FRIEND, C.E. & L.S., LLC GLASTONBURY, CT. DATE: 1-11-17 REV. 2-13-17 SCALE: 1"=20' MAP NO. 6-15-1CH

I HEREBY DECLARE TO THE BEST OF MY KNOWLEDGE AND BELIEF THAT THIS PLAN IS SUBSTANTIALLY CORRECT.

**MEGSON, HEAGLE & FRIEND**  
 CIVIL ENGINEERS & LAND SURVEYORS, LLC  
 61 RANKIN ROAD  
 GLASTONBURY, CONN. 06033  
 PHONE (860)-659-0587

**PROPOSED RESTAURANT & PATIO #2520 MAIN STREET**  
 PREPARED FOR  
**SCHWARTZ REAL ESTATE**  
 GLASTONBURY, CONN.

CK. BY: JLH  
 DRW. BY: JHS  
 DATE: 6-8-21  
 SCALE: 1"=20'  
 SHEET 1 OF 1  
 MAP NO. 6-15-1PA2

P:\2015\Proj\0615\dwg\BASE\0615-1PA2.dwg 3/2/2016 2:32:06 PM EST

REV. 6-21-21 PATIO LAYOUT  
 REV. 6-9-21