

TOWN OF GLASTONBURY

BID #GL-2010-10

**Glastonbury High School
Emergency Power System
GLASTONBURY, CT 06033**

ADDENDUM #2

Dated: 11/13/2009

Bid due date 11/17/2009

11:00 a.m.

Please be advised that the following addendum has been provided to all bidders:

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated October, 2009. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

This Addendum consists of two (2) pages. Numbering is sequential from Addendum #1.

QUESTION AND ANSWERS

5. Question: Why the reference to aluminum conductors on sketch E102.1 in addendum #1?
Answer: The existing feeders for the gym circuit are aluminum. Aluminum conductors will be provided to match existing conditions for this location only.
6. Question: Verify number of conductors in 2 ½" conduit in bid #2.
Answer: There are 5 conductors in each 2 ½" conduit.
7. Question: Verify number of conductors in 2 ½" conduit in bid #4.
Answer: There are 5 conductors in each 2 ½" conduit.

CHANGES/CLARIFICATIONS

- 8. Specification 16612 E 5 – Change the dba rating of the sound attenuated enclosure from 70 dba to be 73 – 78 dba.
- 9. Add: Specification 16612 E 9 “Contractor shall provide diesel fuel in each sub base to fill tanks.”
- 10. Add to Drawing E-101 General Notes #9: Contractor shall provide watt meter for feeder of panel 1EMP2 in MDF electrical room equal to E-mon D-mon 208200 KIT. Meter shall be mounted on wall adjacent to panel. Provide 20 amp, three pole, circuit breaker for meter in panel 1EMP2. This work is part of Base Bid #1.
- 11. Add to Drawing E-102 General Notes #1: Contractor shall provide watt meter for gym feeder in south side electrical room equal to E-mon D-mon 4801600 KIT. Meter shall be mounted on wall adjacent to new pull section. Provide 20 amp, three pole, circuit breaker for meter in main switchgear. This work is part of Base Bid #3.
- 12. Add to Drawing E-102 General Notes #2: Contractor shall provide watt meter for gym feeder in south side electrical room equal to E-mon D-mon 4801600 KIT. Meter shall be mounted on wall adjacent to new pull section. Provide 20 amp, three pole, circuit breaker for meter in main switchgear. This work is part of Base Bid #4.
- 13. Add to Drawing E-103 General Notes #1: Contractor shall provide watt meter for feeder of panel 2EMP1 in south side electrical room equal to E-mon D-mon 480400 KIT. Meter shall be mounted on wall adjacent to panel 2EMP1. Provide 20 amp, three pole, circuit breaker for meter 2EMP1. This work is part of Base Bid #2.

END OF ADDENDUM NO. 2

BID DUE DATE REMAINS UNCHANGED

**Please confirm receipt of this addendum via fax by 11/13/09 by 4:00 PM to:
Kathy Hughey @ (860) 652-7590 (fax)**

Company Name: _____

Name of Person Responding: _____

Authorized Signature: _____

Title: _____

Date: _____

Kathy Hughey’s Phone (860) 652-7588