

LOCATION MAP

SCALE: 1"=1000'

GENERAL LANDSCAPING, LLC	PLANNED COMMERCE/GW-1
PROJECT/APPLICANT	ZONE
121 KREIGER LANE	
PROJECT ADDRESS	
SPECIAL PERMIT SECTION	TPZ CHAIRMAN
DATE SPECIAL PERMIT APP'D	DIRECTOR OF COMMUNITY DEVELOPMENT
DATE SI LOIAL I LINNIT ALL D	DIRECTOR OF COMMISSION DEVELOR WEIGHT
NOTE: ALL SHEETS OF THIS PLAN SET	FILE NO.

HORIZONTAL DATUM REFERS TO NAD83

SCALE: 1"=40' MAP NO. 94-84-1

WARNING: THESE PLANS NOT TO BE USED FOR LOCATION OF UNDERGROUND UTILITIES — CALL BEFORE YOU DIG 1-800-922-4455 TWO WORKING DAYS BEFORE YOU DIG.

REFERENCE MADE TO MAP TITLED: ""RECORD DRAWING" SITE DEVELOPMENT & TOPOGRAPHIC MAP OAK STREET INDUSTRIAL SUBDIVISION PREPARED FOR MGM ASSOCIATES GLASTONBURY, CONN." BY MEGSON & HEAGLE C.E. & L.S. GLASTONBURY, CONN. DATE: 2-7-86 REV. 10-26-88 SCALE: 1"=40' MAP NO. 94-84-1A

"PROPOSED EASEMENT BRUCE J. BEMER PREPARED FOR EDWARD J. & JANIS I. PRELI GLASTONBURY, CONN." BY MEGSON & HEAGLE C.E. & L.S. GLASTONBURY. CONN. DATE: 6-22-88 REV. 10-3-88 SCALE: 1"=40' MAP NO. 331-87-3


"SUBDIVISION PLAN OAK STREET INDUSTRIAL SUBDIVISION PREPARED FOR MGM ASSOCIATES GLASTONBURY, CONN." BY MEGSON & HEAGLE C.E. & L.S. GLASTONBURY. CONN. DATE: 2-7-86 REV. 8-5-86

THIS MAP IS NOT VALID IF MODIFIED IN ANY WAY AND/OR DOES NOT BEAR THE EMBOSSED SEAL OF THE UNDERSIGNED.

TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON. THIS SURVEY WAS PREPARED PURSUANT TO THE REGULATIONS OF CONNECTICUT STATE AGENCIES SECTION 20-300b-1 THROUGH 20-300b-20 AND THE "STANDARDS AND SUGGESTED METHODS AND PROCEDURES FOR SURVEYS AND MAPS IN THE THE STATE OF CONNECTICUT" AS ADOPTED BY THE CONNECTICUT ASSOCIATION OF LAND

SURVEYORS, INC. ON AUGUST 29, 2019. TYPE OF SURVEY: ZONING LOCATION SURVEY BOUNDARY DETERMINATION CATEGORY: RESURVEY CLASS OF ACCURACY: A-2

L.S. # 14201



ZONING INFORMATION
ZONE: PLANNED COMMERCE/GW-1 AREA = 0.92 AC.

<u>LEGEND</u>

EXIST. IRON PIN PROP. IRON PIN EXIST. CHD MONUMENT EXISTING EDGE OF PAVEMENT EXIST. 6" BITUMINOUS CURB

■ MON.

EXISTING DRAINAGE EASEMENT

CK. BY: MWF

MAP NO.131-20-1BDY

DRW. BY: TCJ DATE: 10-4-21 SCALE: 1"=20' SHEET 1 OF 6

MEGSON, I

THE CONTRACTOR SHALL NOTIFY THE TOWN OF GLASTONBURY ENGINEERING DIVISION 24 HOURS PRIOP TO BEGINNING ANY STORM DRAINAGE, SANITARY SEWER INSTALLATION, ROADWAY PREPARATION, PAVING, SIDEWALK, CURBING, OR ANY EXCAVATION IN THE TOWN RIGHT—OF—WAY TO SCHEDULE INSPECTIONS. THE DIVISION CAN BE REACHED BETWEEN 8:00 AM—4:30 PM MONDAY THRU FRIDAY AT (860)652—7735.

HORIZONTAL DATUM REFERS TO NAD83 VERTICAL DATUM REFERS TO NGVD88

ALL CONSTRUCTION METHODS TO CONFORM TO CONN. DOT FORM 818 AND/OR THE TOWN STANDARD SPECIFICATION

NO BITUMINOUS CURBING IS PROPOSED ON THIS SITE EXISTING ELEVATIONS FROM ACTUAL FIELD SURVEY

NOTES;

GENERAL LANDSCAPING, LLC

SPECIAL PERMIT SECTION

PROJECT/APPLICANT

PROJECT ADDRESS

PLANNED COMMERCE/GW-1

TPZ CHAIRMAN

NOTE: ALL SHEETS OF THIS PLAN SET ARE LOCATED IN THE OFFICE OF COMMUNITY DEVELOPMENT FILE NO.

DATE SPECIAL PERMIT APP'D DIRECTOR OF COMMUNITY DEVELOPMENT

TEST PIT 1 DATE: 9-15-21 MATERIAL: 0.0 - 108" RED FINE SAND MOTTLING: NONE GROUNDWATER: NONE

SOILS DATA

N/F WILLIAM CONSTANTINE FLARED END-FL94.45

BENCHMARK T.F.

CATCH BASIN ELEV 97.63

PROP CB#1 TF=98.10 FL=95.00

--- CONCRETE BLOCK ---L'ANDSCAPE MATERIALI STORAGE BINS

12" CHDPE

FL=92.00 197.30 61.31 -14'-15" STORM @ 1.0% PROP. STORM MH TF=97.30 FL=91.86 96 FL 24" RCP "S"=91.48

EXIST. CB. TF=97.54 FL=94.24

- PROP_OUTLET_STRUCTURE TF=96.50

FL 15" RCP "N"=91.36 FL 15" RCP "N"=91.41

FL 30" RCP "E"=91.06

FL 30" RCP "W"=91.06

TELE. COMM. BOX (TO BE RELOCATED)

EXIST DRAINAGE

EXIST. CB. TF=96.11 FL=92.77(N) FL=92.27(S)

- EASEMENT IN FAVOR OF 121 KREIGER LANE

EXIST DRAINAGE — EASEMENT IN FAVOR OF 129 KREIGER LANE

GRAPHIC SCALE

(IN FEET) 1 inch = 20 ft. MS4 PERMIT INFORMATION PRE-DEVELOPMENT POST-DEVELOPMENT NET CHANGE (+ OR -)

IMPERVIOUS AREA DIRECTLY CONNECTED IMPERVIOUS AREA TOWN OF GLASTONBURY 0.00 AC 0.000 AC 0.64 AC 0.015 AC 0.015 AC

> PARKING TABLE PROPOSED STORAGE AREA = 12,928 S.F.

> > 1 SPACE/2500 S.F. REQUIRED

12,928/2500 = 5.1 SPACES REQUIRED 15 SPACES PROVIDED (1 H.C. VAN SPACE)

40,073 S.F. (0.920) AC. 150.0 FT. LOT FRONTAGE 150 FT FRONT YARD SETBACK 50 FT N/A SIDE YARD SETBACK 25 FT N/A REAR YARD SETBACK 25 FT OPEN SPACE 30% (12,022 S.F.) 30.2% (12,103 S.F.)

PROPOSED USE: LANDSCAPE MATERIAL STORAGE & EMPLOYEE PARKING ZONING TABLE PLANNED COMMERCE REQUIRED/ALLOWED PROPOSED/PROVIDED

ZONING INFORMATION

ZONE: PLANNED COMMERCE/GW-1 AREA = 0.92 AC.

<u>LEGEND</u> PROP. CONTOUR EXIST. 4" GAS MAIN EXIST. 12" WATER MAIN EXIST. 8" SANITARY SEWER EXIST. CONTOUR MINOR EXIST. CONTOUR MAJOR EXISTING LIMIT OF CLEARING .PROPOSED LIMIT OF CLEARING .~~~~~~~ EXISTING EDGE OF PAVEMENT EXIST. 6" BITUMINOUS CURB PROPOSED HANDICAPPED SIGN PROP. SPOT ELEVATIONS ----UD----PROPOSED UNDERDRAIN

PROPOSED CATCH BASIN

CK. BY: MWF DRW. BY: TCJ DATE: 10-4-21 SCALE:

1"=20'

SHEET 2 OF 6 MAP NO. 131-20-1SP

0

MEGSON, CIVIL ENGINEE

WARNING: THESE PLANS NOT TO BE USED FOR LOCATION OF UNDERGROUND UTILITIES — CALL BEFORE YOU DIG 1-800-922-4455 TWO WORKING DAYS BEFORE YOU DIG.

GENERAL

WARNING: THESE PLANS NOT TO BE USED FOR LOCATION OF UNDERGROUND UTILITIES - CALL BEFORE YOU DIG 1-800-922-4455 TWO WORKING DAYS

THESE GUIDELINES SHALL APPLY TO ALL WORK CONSISTING OF ANY AND ALL TEMPORARY AND/OR PERMANENT MEASURES TO CONTROL WATER GENERAL: POLLUTION AND SOIL EROSION AS MAY BE REQUIRED, DURING THE CONSTRUCTION OF THE PROJECT. CONSTRUCTION METHODS, IN GENERAL, SHALL BE IN ACCORDANCE WITH THE PROVISIONS SET FORTH IN THE ?GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL ? (2002) BY THE STATE OF CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION.

IN GENERAL, ALL CONSTRUCTION ACTIVITIES SHALL PROCEED IN SUCH A MANNERT (A.SPONDITTE ANY WETLANDS, WATERCOURSE, WATERBODY, AND CONDUIT CARRYING WATER, ETC. THE CONTRACTOR SHALL LIMIT, INSOFAR AS POSSIBLE, THE SURFACE AREA OF EARTH MATERIALS EXPOSED BY CONSTRUCTION METHODS. AND IMMEDIATELY PROVIDE PERMANENT AND TEMPORARY POLLUTION CONTROL MEASURES TO PREVENT CONTAMINATION OF ADJACENT WETLANDS, WATERCOURSES AND WATERBODIES, AND TO PREVENT, INSOFAR AS POSSIBLE, EROSION ON

THE POINT OF ACCESS TO THE SITE SHALL BE WELL DEFINED.

AN APRON OF 2? TRAP ROCK AT A MINIMUM DEPTH OF 6 INCHES AND 50 FEET IN LENGTH SHALL BE INSTALLED AND MAINTAINED TO THE SITE. ALL VEHICULAR ACTIVITIES SHALL BE SERVED VIA THIS LOCATION.

THE TRAP ROCK IS TO BE REPLACED WHEN SILTED IN TO THE EXTENT THAT IT IS NO LONGER EFFECTIVE FOR ANTI-TRACKING. GOALS OF THE E&SCP

- REDUCE MOVEMENT OF SOIL FROM EXPOSED SURFACES UTILIZING TEMPORARY MULCH.
- SLOW RUNOFF VELOCITIES AND TRAP SEDIMENTS WITH SEDIMENT BARRIERS UTILIZING SILT FENCE AND/OR HAY BALES.
- CONTAIN OFF SITE TRACKING OF SEDIMENTS FROM TIRES WITH ANTI-TRACKING PADS. DIRECT ALL SURFACE WATER FROM DISTURBED AREA TO TEMPORARY SEDIMENT TRAP.
- WINTER STABILIZATION MEASURES SHALL BE PLANNED IN ADVANCE OF THE END OF THE GROWING SEASON TO ALLOW FOR ADEQUATE EROSION AND SEDIMENTATION CONTROL FOR THE WINTER MONTHS.

PROJECT DESCRIPTION THIS PROJECT CONSISTS OF THE DEVELOPMENT OF A NEW PAVED PARKING LOT. 15 PARKING SPACES ARE PROPOSED AS WELL AS BULK STORAGE AREAS. THE LOT WILL DRAIN TO A CATCH BASIN IN THE MIDDLE OF THE LOT AND ALSO WA SHEET FLOW TO THE PROPOSED STORMWATER MANAGEMENT BASIN ON THE SOUTH SIDE OF THE PARCEL. THE RUNOFF COLLECTED IN THE CATCHBASIN WILL BE DIRECTED TO THE STORMWATER

MANAGEMENT BASIN. THIS BASIN IS SIZED TO RETAIN & INFILTRATE THE WATER QUALITY VOLUME. SHORT TERM. THIS BASIN WILL ALSO PROVIDE 1. SIGNIFICANT EROSION AND SEDIMENTATION CONTROL DURING CONSTRUCTION AS A TEMPORARY SEDIMENT TRAP.

THIS SITE WILL HAVE A DISTURBED AREA OF APPROXIMATELY 0.9 ACRES FOR CONSTRUCTION OF THE PARKING LOT AND STORMWATER MANAGEMENT BASIN. THE TOTAL IMPERVIOUS COVER WILD. 694E ACRES.

AVERAGE RUNOFF COEFFICIENT AFTER CONSTRUCTION 05/2

SITE SPECIFIC EROSION AND SEDIMENTATION ISSUES 1. PREVENT SEDIMENT INTO THE EXISTING STORM DRAINAGE SYSTEM ON KREIGER LANE.

- 2. PREVENT CLOGGING OF COARSE AGGREGATE INFILTRATION BED IN BOTTOM OF STORMWATER MANAGEMENT BASIN
- 3. PREVENT TRACKING OF SEDIMENTS ONTO KREIGER LANE
- DUST CONTROL

THE ENTIRE CONSTRUCTION IS EXPECTED TO TAKE APPROXIMATELY 3 - 4 MONTHS. THE INITIAL PHASE OF CONSTRUCTION SHALL CONSIST OF CONSTRUCTING THE STORMWATER MANAGEMENT BASIN TO PROVIDE A TEMPORARY SEDIMENT TRAP. THE BOTTOM COARSE AGGREGATE INFILTRATION LAYER SHOULD NOT BE INSTALLED AT THIS TIME TO AVOID CLOGGING AND REDUCTION OF FUTURE INFILTRATION RATE.

CONSTRUCTION SEQUENCE

- CLEARING AND GRUBBING
- 2. INSTALL CONSTRUCTION ENTRANCE
- ROUGH GRADE STORMWATER MANAGEMENT BASIN TO BE USED AS A TEMPORARY SEDIMENT TRAP (DO NOT INSTALL COURSE GRADE AGGREGATES IN BOTTOM)
- 5. INSTALL CATCH BASIN OUTLET STRUCTURE & STORM PIPE
- SITE GRADING
- 7. INSTALLATION OF RECLAIMED ASPHALT PAVEMENT
- 8. INSTALLATION OF LANDSCAPE MATERIALS
- TOPSOILING AND SEEDING SHOULDERS
- 10. CLEAN OUT ANY ACCUMULATED SEDIMENTS IN STORMWATER MANAGEMENT BASIN 🗶 11. INSTALL UNDERDRAINS, CRUSHED STONE AND COARSE AGGREGATE IN BOTTOM OF STORMWATER MANAGEMENT BASIN
- 12. FINISH GRADE BASIN
- 13. TOPSOILING AND SEEDING OF BASIN AREA

LAND GRADING

- THE RESHAPING OF THE GROUND SURFACE BY EXCAVATION AND FILLING OR A COMBINATION OF BOTH, TO OBTAIN PLANNED GRADES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING BASIC CRITERIA:
- A) THE CUT FACE OF EARTH EXCAVATION SHALL NOT BE STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL (2:1).
- B) THE PERMANENT EXPOSED FACES OF FILLS SHALL NOT BE STEEPER THAN TWO HORIZONTAL
- C) THE CUT FACE OF ROCK EXCAVATION SHALL NOT BE STEEPER THAN ONE HORIZONTAL TO
- D) NO FILL SHOULD BE PLACED WHERE IT WILL SLIDE, OR WASH UPON THE PREMISES OF ANOTHER OWNER OR UPON ADJACENT WETLANDS, WATERCOURSE OR WATERBODY.
- E) INSTALLATION OF SEDIMENT AND EROSION CONTROLS SUCH AS HAY BALES AND SILT FENCES SHALL BE ESTABLISHED PRIOR TO COMMENCING LAND DISTURBANCE ACTIVITIES. ALL SEDIMENT AND EROSION CONTROL STRUCTURES MUST BE MONITORED AND MAINTAINED BY THE CONTRACTOR UNTIL THE SOIL SURFACE IS STABILIZED
- F) IF NECESSARY, LATERAL WATER DIVERSIONS SHALL BE INSTALLED ACROSS THE GRADED ROADWAY TO PREVENT DOWNSLOPE OUTWASH AND EROSION.
- G) HAY BALES SHALL BE STAKED AND SILT FENCES SHALL BE PROPERLY SECURED. SEDIMENT WILL BE REMOVED FROM ALL CATCHMENTS AS NECESSARY.
- H) PRIOR TO ANY REGRADING, STONE APRON SHALL BE PLACED BY THE ENTRANCE TO THI WORK AREA IN ORDER TO REDUCE MUD AND OTHER SEDIMENTS FROM LEAVING THE SITE
- PROVISIONS SHOULD BE MADE TO CONDUCT SURFACE WATER SAFELY TO STORM DRAINS, TO PREVENT SURFACE RUNOFF FROM DAMAGING CUT FACES AND FILL SLOPES.
- J) EXCAVATIONS SHOULD NOT BE MADE SO CLOSE TO PROPERTY LINES AS TO ENDANGER ADJOINING PROPERTY WITHOUT PROTECTING SUCH PROPERTY FROM EROSION, SLIDING, SETTLING OR CRACKING.

EROSION CHECKS

GENERAL

1. TEMPORARY PERVIOUS BARRIERS USING BALES OF HAY OR STRAW, HELD IN PLACE WITH STAKES DRIVEN THROUGH THE BALES AND INTO THE GROUND, OR SEDIMENT FILTER FABRIC FASTENED TO A FENCE POST AND BURIED INTO THE GROUND, SHALL BE INSTALLED AND MAINTAINED AS REQUIRED TO CHECK EROSION AND REDUCE SEDIMENTATION. STRAW SHALL BE USED RATHER THAN HAY BALES TO PREVENT INTRODUCTION OF INVASIVE PLANT SPECIES TO THE SENSITIVE WETLAND AREAS.

- 1. BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES.
- 2. EACH BALE SHALL BE EMBEDDED INTO THE SOIL A MINIMUM OF FOUR (4") INCHES.
- 3. BALES SHALL BE SECURELY ANCHORED IN PLACE BY WOOD STAKES OR REINFORCEMENT BARS DRIVEN THROUGH THE BALES AND INTO THE GROUND. THE FIRST STAKE IN EACH BALE SHALL BE ANGLED TOWARD THE PREVIOUSLY LAID BALE TO FORCE BALES TOGETHER.
- 4. FILTER FABRIC SHALL BE SECURELY FASTENED AT THE TOP OF A THREE (3') FOOT HIGH FENCE AND BURIED A MINIMUM OF FOUR (4") INCHES INTO THE SOIL. SEAMS BETWEEN SECTIONS OF FILTER FABRIC SHALL OVERLAP A MINIMUM OF TWO (2') FEET.
- INSTALLATION AND MAINTENANCE:
- 1. BALED HAY EROSION BARRIERS SHALL BE INSTALLED AT ALL STORM SEWER INLETS.
- 2. BALED HAY EROSION BARRIERS AND SEDIMENT FILTER FENCES SHALL BE INSTALLED AT THE LOCATIONS INDICATED ON THE PLAN AND IN ADDITIONAL AREAS AS MAY BE DEEMED
- 3. ALL EROSION CHECKS SHALL BE MAINTAINED UNTIL ADJACENT AREAS ARE STABILIZED.
- 4. INSPECTION SHALL BE FREQUENT (AT MINIMUM MONTHLY AND BEFORE AND AFTER HEAVY RAIN) AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
- 5. EROSION CHECKS SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULNESS SO AS NOT TO BLOCK OR IMPEDE STORMWATER FLOW OR DRAINAGE.

ALL WINDBLOWN SEDIMENTS SHALL BE CONTROLLED AT ALL TIMES. THE SITE CONTRACTOR IS RESPONSIBLE FOR APPLYING DUST CONTROL AS OFTEN AS NEEDED TO PREVENT ANY WINDBLOWN SEDIMENTS FROM LEAVING THE SITE. PREDETERMINED TRAFFIC ROUTES FOR ALL TRAFFIC SHALL BE ESTABLISHED BY THE SITE CONTRACTOR TO STABILIZED ROUTES. TEMPORARY AND PERMANENT MULCHING AND TEMPORARY AND PERMANENT VEGETATIVE COVER SHALL BE USED TO MINIMIZE THE NEED FOR DUST CONTROL. MECHANICAL SWEEPERS SHALL BE USED ON ALL PAVED SURFACES TO PREVENT DUST BUILD UP DURING THE COURSE OF SITE WORK.

- 1. WATER IS ACCEPTABLE AND MUST BE APPLIED OFTEN IN HOT, DRY WEATHER. CALCIUM CHLORIDE IS NOT ACCEPTABLE.
- 2. CRUSHED STONE OR COARSE GRAVEL CAN ALSO BE USED.

TEMPORARY VEGETATIVE COVER

TEMPORARY VEGETATIVE COVER SHALL BE ESTABLISHED ON ALL UNPROTECTED AREAS THAT PRODUCE SEDIMENT, AREAS WHERE FINAL GRADING HAS BEEN COMPLETED AND AREAS WHERE THE ESTIMATED PERIOD OF BARE SOIL EXPOSURE IS LESS THAN 12 MONTHS.

- . INSTALL REQUIRED SURFACE WATER CONTROL MEASURES.
- 2. REMOVE LOOSE ROCK, STONE, AND CONSTRUCTION DEBRIS FROM AREA
- . APPLY LIME ACCORDING TO SOIL TEST.
- 4. APPLY FERTILIZER ACCORDING TO SOIL TEST. SLOW RELEASE AND LOW/NO PHOSPHORUS FERTILIZERS SHALL BE USED.
- 5. UNLESS HYDROSEEDED, WORK IN LIME AND FERTILIZER TO A DEPTH OF FOUR (4") INCHES USING A DISK OR ANY SUITABLE EQUIPMENT.
- 6. TILLAGE SHOULD ACHIEVE A REASONABLY UNIFORM, LOOSE SEEDBED. WORK ON CONTOUR IF SITE IS SLOPING.

ESTABLISHMENT:

- 1. USE ANNUAL RYEGRASS AT A RATE OF 40 LBS/AC. OR SUITABLE EQUIVALENT AS SPECIFIED IN THE "GUIDELINES".
- 2. SEEDING TO BE DONE FROM APRIL 1ST TO JUNE 15 OR AUGUST 1ST TO OCTOBER 1ST. WINTER STABILIZATION PLANTINGS TO BE NO LATER THAN OCTOBER 1ST. THIS INCLUDES
- 3. APPLY SEED UNIFORMLY ACCORDING TO THE RATE INDICATED BY BROADCASTING, DRILLING, OR HYDRAULIC APPLICATION.
- 4. UNLESS HYDROSEEDED, COVER RYEGRASS SEEDS WITH NOT MORE THAN 1/4 INCH OF SOIL WITH SUITABLE EQUIPMENT. COVER SUDANGRASS AND SMALL GRAINS WITH 1/2 INCH SOIL.
- 5. MULCH IMMEDIATELY AFTER SEEDING, IF REQUIRED, ACCORDING TO THE GUIDELINES IN THE "GUIDELINES"

PERMANENT VEGETATIVE COVER

GENERAL:

 PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED AS VARIOUS SECTIONS OF THE PROJECT ARE COMPLETED IN ORDER TO STABILIZE THE SOIL, REDUCE DOWNSTREAM DAMAGE FROM SEDIMENT AND RUNOFF AND TO ENHANCE THE AESTHETIC NATURE OF THE SITE. IT WILL BE APPLIED TO ALL CONSTRUCTION AREAS SUBJECT TO EROSION WHERE FINAL GRADING HAS BEEN COMPLETED AND A PERMANENT COVER IS NEEDED.

- 1. INSTALL REQUIRED SURFACE WATER CONTROL MEASURES.
- 2. REMOVE LOOSE ROCK, STONE AND CONSTRUCTION DEBRIS FROM AREA.
- 3. PERFORM ALL PLANTING OPERATIONS PARALLEL TO THE CONTOURS OF THE SLOPE
- 4. APPLY TOPSOIL AS INDICATED ELSEWHERE HEREIN.

DROUGHTY SITES

TALL FESCUE

CREEPING RED FESCUE

5. APPLY FERTILIZER ACCORDING TO SOIL TEST. USE ONLY SLOW RELEASE AND LOW/NO PHOSPHORUS FERTILIZERS.

ESTABLISHMENT:

- 1. SMOOTH AND FIRM SEEDBED WITH CULTIPACKER OR OTHER SIMILAR EQUIPMENT PRIOR TO SEEDING (EXCEPT WHEN HYDROSEEDING).
- 2. SELECT ADAPTED SEED MIXTURE AS FOLLOWS. NOTE RATES AND THE SEEDING DATES.

SUNNY TO PARTIALLY	SUNNY SITE	<u>S_</u>	
KENTUCKY BLUEGRASS CREEPING RED FESCUE PERENNIAL RYEGRASS		20 20 05	0.50 0.50 0.10
	TOTAL	45	1.10
SHADY SITES			
CREEPING RED FESCUE PERENNIAL RYEGRASS	•	50 05	1.00 0.10
	TOTAL	55	1.10

	TOT	AL	60	1.50
3.	FINAL SEEDING SHALL TAKE PLACE			
	RUNS A DISTINCT CHANCE OF FA	ILURE DUE	TO ADVERSE WEA	ATHER. ANY AREAS THAT ARE
	DISTURBED BETWEEN OCTOBER 19	T AND AP	RIL 1ST SHALL BE	STABILIZED BY
	NON-VEGETATIVE MEANS SUCH A	S HEAVY N	JULCHING WITH A	BINDER OR JUTE MATTING
	WHICH WILL HAVE TO BE REMOVE	D BEFORE	FINAL SEEDING A	ND THEN REPLACED AFTER

- 4. APPLY SEED UNIFORMLY ACCORDING TO RATE INDICATED, BY BROADCASTING, DRILLING,
- 5. COVER GRASS AND LEGUME SEEDS WITH NOT MORE THAN 1/4 INCH OF SOIL WITH SUITABLE EQUIPMENT (EXCEPT WHEN HYDROSEEDING).

6. MULCH IMMEDIATELY AFTER SEEDING, IF REQUIRED, ACCORDING TO THE GUIDELINES IN


7. USE PROPER INOCULANT ON ALL LEGUME SEEDINGS, USE FOUR (4) TIMES NORMAL RATE WHEN HYDROSEEDING.

TOPSOILING

APPLICATION:

- TOPSOIL SHALL BE SPREAD OVER ALL EXPOSED AREAS IN ORDER TO PROVIDE A SOIL MEDIUM HAVING FAVORABLE CHARACTERISTICS FOR THE ESTABLISHMENT, GROWTH AND MAINTENANCE OF VEGETATION.
- 2. REMOVE ALL LARGE STONES, TREE LIMBS, ROOTS, AND CONSTRUCTION DEBRIS.
- 3. APPLY LIME ACCORDING TO SOIL TEST OR AT THE RATE OF TWO (2) TONS PER ACRE.
- 1. TOPSOIL SHOULD HAVE PHYSICAL, CHEMICAL AND BIOLOGICAL CHARACTERISTICS FAVORABLE TO THE GROWTH OF PLANTS.
- TOPSOIL SHOULD HAVE A SANDY OR LOAMY TEXTURE.
- 3. AN ORGANIC MATTER CONTENT BETWEEN 6 & 20 PERCENT IS HIGHLY DESIRABLE. AVOID LIGHT COLORED LOWER SUBSOIL MATERIAL.

AVOID SPREADING WHEN TOPSOIL IS WET OR FROZEN. 2. SPREAD TOPSOIL UNIFORMLY TO A DEPTH OF AT LEAST SIX (6") INCHES.



STORMWATER MAINTENANCE PROGRAM

(TYPE "C-L" SHOWN)

SECTION A-A

— GRAVEL FILL

STONE OR PEA

1. PERFORATIONS TO BE PLACED UP OR

2. HOLES ARE TO BE 1/2" DIA. OR 5/8" DIA.

5. ALL UNDERDRAIN TO BE OUTLETTED DIRECTLY INTO A CATCH BASIN.THE TOP OF THE

6. INCLUDE CLEANOUTS AT SPACING NOT TO EXCEED 150 FEET.

UNDERDRAIN PIPE IS TO MATCH THE TOP OF THE

SLOTTED REINFORCED CONC. PIPE (SRCP) CAN BE USED AS A COMBINED STORM AND UNDERDRAIN SYSTEM.

DOWN AS SPECIFIED BY THE ENGINFER

3. PIPE SHALL BE MIN. 6" DIA.

2555555

STANDARD UNDERDRAIN

-UTILITY MARKING TAPE

OVERLAP ON TOP

' MIN. PVC UNDERDRAIN

- GEOTEXTILE (SUBSURFACE DRAINAGE CLASS A) WITH FULL

___ PROCESSED AGGREGATE 4" IN EARTH 12"____ BASE IF TRENCH BOTTOM MIN. IN ROCK IS UNSUITABLE

EXCEEDS 10' CATCH BASIN WILL BE CLASSED AS

L", OVER 10' DEEP

AROUND PIPE

SQUARE KNOCKOUT FOR PIPE, MIN. 6" CLEAR

" TYPICAL, SEE NOTE 5

── 6" THICK BASE OF ¾"-CRUSHED STONE.

MAINTENANCE OF STORMWATER MANAGEMENT BASIN

- WEED (3-5" LAYER OF MULCH WILL LIMIT WEEDS)

- WHERE PLANTS ARE TOO CROWDED, DIVIDE AND

- CUT AND REMOVE DEAD STALKS AND SEED HEADS FROM

<u>ANNUAL</u>

PREVIOUS SEASON.

SPRING AND SUMMER

CUT BACK DEAD STALKS

- REMOVE STICKS AND DEBRIS

- PRUNE SHRUBS IF NECESSARY

MOVE PLANTS TO DIFFERENT AREA

- REMOVE WEEDS AND DISEASED PLANTS

- REMOVE EXCESS TREE LEAVES FROM GARDEN

REQUIRED

REDUCE

- REPLENISH MULCH TO 3-5" LAYER

All paved surfaces and landscaped areas are to be maintained free of litter and ion debrie. Litter and debrie are to be removed (hand picked) from ped areae, and parking areae. This cleaning service will be perfor

The excepting program is intended to militarie codiment accumulation from canding parking areas during the winter months. By far, most of the cand applied remains on or adjacent to the paved curioses. Accumulated fell follage is nnother annually recurring material that can negatively affect the eleminator system. These materials will be removed twice each year, once in November and once in April. Should more frequent europings be required, the program will

C. Disposel of Sediment and Debrie

FLOW LINE

SCALE : NONE

CHECKED BY: SMB

APPROVED BY: DAP

LAST REVISED: 9/1/2016

VARIES

THE TOP OF PIPE.

CHECKED BY: SMB

APPROVED BY: DAP

LAST REVISED: 9/1/2016

possi of debris and sediment removed from any of the structures must be in nce with all applicable local, state and federal regulations. On-elle Record of sediment and debris shall not coour.

FOR DETAILS OF FRAMES AND GRATES, SEE CONNDOT STANDARD DETAIL SHEET HW-507_08.

1. ALL CATCH BASINS SHALL CONFORM TO CONNDOT STANDARD DETAIL SHEETS HW-507_1 AND HW-507_04 EXCEPT AS OTHERWISE NOTED ON THIS DETAIL. DOUBLE GRATE CATCH BASINS SHALL CONFORM TO CONNDOT STANDARD SHEETS HW-507_05 AND HW-507_06.

PRECAST CATCH BASIN TOPS MUST BE PROPERLY ALIGNED AS SHOWN AND SHALL CONFORM TO CONNDOT STANDARD DETAIL SHEETS HW-507_07. CAPE COD CATC BASIN TOPS SHALL HAVE AN OPEN THROAT.

4. WHEN TYPE 'C' CATCH BASINS ARE CONSTRUCTED IN PAVEMENT, THE NORMAL GUTTER OF THE ROADWAY SHALL BE VARIED TO PROVIDE AN ADDITIONAL 2—INCH DEPRESSE GUTTER AT THE CATCH BASIN.

5. WALL THICKNESS TO BE 12 INCHES WHEN HEIGHT O STRUCTURE EXCEEDS 10 FEET FROM TOP OF FRAME TO BOTTOM OF BASE. THICKER WALLS APPLY ONLY TO

6. PRECAST RISER SECTIONS SHALL <u>NEVER</u> HAVE CORNER PIPE ENTRIES. WHEN PIPE ALIGNMENT CANNOT E CHANGED, A ROUND STRUCTURE SHALL BE USED PER CONNDOT DETAIL HW-507_04.

7. CATCH BASINS LEFT ABOVE THE FINISHED GUTTER GRADE FOR THE WINTER MUST BE PROPERLY SHIMMED FOR PLOWING AS SHOWN IN PLATE 4.

ENDS OF PIPE SHALL BE SAWCUT FLUSH WITH INSID

MORTAR MIX SHALL NOT CONTAIN LIME.

10. IF CONCRETE MASONRY UNITS ARE USED THE FOLLOWING ADDITIONAL REQUIREMENTS SHALL BE MET:

MAXIMUM CORBEL SHALL NOT EXCEED 2 INCHES;

WHERE NECESSARY, BLOCKS MAY BE CUT OR

WHERE NECESSART, BLOCKS MAT BE CUT OR
CONCRETE BRICK USED (NO RED BRICK PERMITTED);
 CORNERS SHALL BE SQUARE, COURSES LEVEL, AND
JOINTS PROPERLY STAGGERED;
 VOIDS IN EXTERIOR WALLS SHALL BE GROUTED, AND
CORDELS SHALL BE WEDGED.

TOWN OF GLASTONBURY
DEPARTMENT OF PHYSICAL SERVICES
ENGINEERING DIVISION

CATCH BASIN

COMPACTED IN

12"(MAX.)LAYERS

OR SUITÁBLE NATIVE

BY THE ENGINEER.

BACKFILL AS APPROVED

BEDDING MATERIAL

STORM SEWER TRENCH

TOWN OF GLASTONBURY
DEPARTMENT OF PHYSICAL SERVICES

TRENCH FOR STORM DRAIN

AND UNDER DRAIN

UTILITY MARKING TAPE

CORBELS SHALL BE WEDGED.

TYPICAL WIDTHS FOR

EXCAVATION &

OF ELLIPTICAL PIPE

FOR PIPE 30"& OVER

ALL STORM DRAIN INSTALLED WITHIN TOWN RIGHT-OF-WAY

SHALL BE CONCRETE PIPE. ALL CONCRETE PIPE SHALL BE MINIMUM CLASS IV UNLESS OTHERWISE SPECIFIED.

OF WHICH PASSES 3/8" SIEVE AND <10% PASSING NO. 200 SIEVE.

SUBSTITUTED FOR PIPE BEDDING, AND BACKFILLED TO 12" ABOVE


USE WATERTICHT RUBBER GASKETS IN ALL PIPE JOINTS.
PIPE BEDDING MATERIALS SHALL BE SAND OR SANDY SOIL, ALL

. WHEN GROUND WATER IS ENCOUNTERED, 3/4" STONE SHALL BE


& FOR HORIZ. ELLIPTICAL PIPE

I.D.+2' FOR PIPE UNDER 30", I.D.+3'

PORTION OF STRUCTURE BELOW 10' DEEP.




<u>TYPICAL PARKING SPACE DETAIL</u>



HANDICAPPED

PARKING SIGN

VAN ACCESSIBLE PARKING SPACE DETAIL



SECTION "A"-"A

GENERAL LANDSCAPING, LLC	PLANNED COMMERCE/GW-1
PROJECT/APPLICANT	ZONE
233 EASTERN BOULEVARD	
PROJECT ADDRESS	
SPECIAL PERMIT SECTION	TPZ CHAIRMAN
DATE SPECIAL PERMIT APP'D	DIRECTOR OF COMMUNITY DEVELOPMENT
NOTE: ALL SHEETS OF THIS PLAN S	SET ARE LOCATED IN THE OFFICE OF COMMUNITY DEVELOPMENT
NOTE. ALL SHEETS OF THIS FEAR	FILE NO.

NOT TO SCALE 8" RECLAIMED ASPHALT PAVEMENT PAVEMENT DETAIL NOT TO SCALE

ENT			
	-		

PING \mathbf{C} AND 0

DRW. BY: 10-4-21 1"=20'

SCALE: SHEET 3 OF 6 MAP NO. 131-20-1N

SOILS DATA

TEST PIT 1
DATE: 9-15-21
MATERIAL:
0.0 - 108" RED FINE SAND
MOTTLING: NONE
GROUNDWATER: NONE

GENERAL LANDSCAPING, LLC	PLANNED COMMERCE/GW-1
PROJECT/APPLICANT	ZONE
121 KREIGER LANE	
PROJECT ADDRESS	
SPECIAL PERMIT SECTION	TPZ CHAIRMAN
DATE SPECIAL PERMIT APP'D	DIRECTOR OF COMMUNITY DEVELOPMENT
NOTE: ALL SHEETS OF THIS PLAN SET	ARE LOCATED IN THE OFFICE OF COMMUNITY DEVELOPMENT FILE NO.


TS - TEMPORARY SEDIMENT BASIN TO BE USED DURING CONSTRUCTION TO COLLECT RUNOFF. BOTTOM AGGREGATES SHALL NOT BE INSTALLED UNTIL SITE IS STABILIZED TO AVOID CLOGGING OF AGGREGATE

PROPOSED SPOT ELEVATIONS DENOTE BOTTOM OF CURB WHERE CURBING IS PROPOSED

ALL CONTRUCTION METHODS TO CONFORM TO CONN. DOT FORM 818 AND/OR THE TOWN STANDARD SPECIFICATION HORIZONTAL DATUM REFERS TO NAD83 VERTICAL DATUM REFERS TO NGVD88

THE CONTRACTOR SHALL NOTIFY THE TOWN OF GLASTONBURY ENGINEERING DIVISION 24 HOURS PRIOP TO BEGINNING ANY STORM DRAINAGE, SANITARY SEWER INSTALLATION, ROADWAY PREPARATION, PAVING, SIDEWALK, CURBING, OR ANY EXCAVATION IN THE TOWN RIGHT-OF-WAY TO SCHEDULE INSPECTIONS. THE DIVISION CAN BE REACHED BETWEEN 8:00 AM-4:30 PM MONDAY THRU FRIDAY AT (860)652-7735.

WARNING: THESE PLANS NOT TO BE USED FOR LOCATION OF UNDERGROUND UTILITIES — CALL BEFORE YOU DIG 1-800-922-4455 TWO WORKING DAYS BEFORE YOU DIG.



1 inch = 20 ft.

CONTACT NAME: JEFF PELL (860) 209-0751


& FRIEND SURVEYORS, LLC

MEGSON, CIVIL ENGINEE

CK. BY: MWF DRW. BY: TCJ DATE: 10-4-21 1"=20'

SCALE: SHEET 4 OF 6

MAP NO. 131-20-1ES



andscaping LLC Gene

| General Landscapir

THIS MAP IS NOT VALID IF MODIFIED IN ANY WAY AND/OR BEAR THE EMBOSSED SEAL OF THE UNDERSIGNED I HEREBY DECLARE TO THE BEST OF MY KNOWLEDGE BELIEF THAT THIS PLAN IS SUBSTANTIALLY CORRECT. MEGSON, HEAGLE & FRIEND
CIVIL ENGINEERS & LAND SURVEYORS, LLC
81 RANKIN ROAD
GLASTONBURY, CONN. 06033
PHONE (860)-659-0587 PLANNED COMMERCE/GW-1
ZONE GENERAL LANDSCAPING, LLC
PROJECT/APPLICANT 121 KREIGER LANE PROJECT ADDRESS SPECIAL PERMIT SECTION TPZ CHAIRMAN DATE SPECIAL PERMIT APP'D DIRECTOR OF COMMUNITY DEVELOPMENT NOTE: ALL SHEETS OF THIS PLAN SET ARE LOCATED IN THE OFFICE OF COMMUNITY DEVELOPMENT FILE NO. CK. BY: MWF DRW. BY: TCJ DATE: 10-4-21 SCALE: 1"=20' SHEET 6 OF 6

MAP NO.131-20-1BDY