

ZONING DATA

Filed pursuant to C.G.S. § 8-30g

ZONE:	PBD / RR / *GW-1	PROPOSED
LOT AREA	60,000 SF	±104,554 SF - 2.40 AC.
LOT FRONTAGE	200 FT	238.75 FT (HEBRON AVE.)
		359.21 FT (MANCHESTER RD.)
FRONT YARD	75 FT	76 FT
SIDE YARD	25 FT	25.5 FT
REAR YARD	25 FT	99 FT
LOT COVERAGE	20% (MAX.)	14,366 SF (13.74% PROPOSED)
OPEN SPACE (MIN.)	2 X COVERAGE	
	= 28,732 SF (27.48% MIN.)	53,493 SF (51.17% PROPOSED)
IMPERVIOUS COVERAGE		51,051 SF (48.83%)
BLDG. HEIGHT (MAX.)	35 FT	58 FT (SECT. 2.6)
BLDG. STORIES (MAX.)	2.5 STORIES	5 STORIES
RESIDENTIAL DENSITY		30.8 UNITS / ACRE

*PARCEL IS LOCATED IN GROUNDWATER PROTECTION ZONE 1

PARKING CALCULATIONS

REQUIRED PER PDB / RR 1 SPACE PER RESIDENTIAL UNIT

74 UNITS x 1 SPACE / UNIT = 74 SPACES

4 HANDICAPPED

81 STANDARD

<u>PROPOSED</u>

TOTAL:


RESIDENTIAL:

74 SPACES

85 SPACES

PARKING RATIO = 81 SPACES / 74 UNITS = 1.09 SPACES PER UNIT+ 4 HC SPACES

MANCHESTER/HEBRON AVE LLC PROJECT/APPLICANT 1199 MANCHESTER RD. GLASTONBURY, CONN. PROJECT ADDRESS TPZ CHAIRMAN DATE APPROVED DIRECTOR OF COMMUNITY DEVELOPMENT FILE NO.



SCALE: 1"=1,000'

1199 MANCHESTER ROAD PREPARED FOR MANCHESTER/HEBRON AVE LLC GLASTONBURY, CONN.

INDEX TO SHEETS

COVER SHEET

SITE LAYOUT PLAN

SHEET C-1

SURVEY PLANS

TOPOGRAPHIC MAP - EXISTING CONDITIONS SURVEY

A-2 BOUNDARY SURVEY


SHEET SV-1


SHEET SP-1


SITE PLANS


SITE GRADING	SHEET SP-2
UTILITY PLAN	SHEET SP-3
OFFSITE SANITARY SEWER	SHEET SP-4
EROSION & SEDIMENTATION CONTROL PLAN	SHEET SP-5
LANDSCAPING PLAN	SHEET SP-6
ACCESS MANAGEMENT PLAN	SHEET SP-7
SITE ILLUMINATION PLAN	SHEET SP-8
GENERAL NOTES & DETAILS	SHEETS SP-9 THRU SP-11


DATE: 11-08-21 SCALE: SHOWN MAP NO. 21-002-10














& SEDIMENTATION CONTROL 1199 MANCHESTER ROAD


EROSION


MANCHESTER/HEBRON AVE GLASTONBURY, CONNECTICUT

SP-5

DATE: 11-08-21 SCALE: 1"=30' SHEET MAP NO. 21-002-1ES

PLanting Specifications Symbol Code Scientific Name/ COMMON NAME PREESS PREES	WENTS X3 WENTS X3 OUY: PROP.	SNET 201 CONC. TRAFFIC BOX
EXIST TWO BUIL	SING SED DIMESTER PAD DIMESTER	TOHN ALEXOPOULOS TANDSCAPE A DOCUMENT OF THE MARKET OF
CC CONCRETE CURB WIS SPAN POLE WAST ARM EDGE OF PAVEMENT EDGE OF PAVEMENT EDGE OF GRAVEL/LANDSCAPE EDGE OF PAVEMENT EDGE OF GRAVEL/LANDSCAPE CORB STEEL GUARD RAIL UNDERGROUND BRAINAGE LINE UNDERGROUND SEWER UNE OVERHEAD WISE UNDERGROUND SEWER UNE OVERHEAD WISE UNDERGROUND ELECTRIC LINE UNDERGROUND GAS LINE OVERHEAD WISE UNDERGROUND GAS LINE OVERHEAD WISE UNDERGROUND GAS LINE OVERHEAD WAST UNDERGROUND WASTER LINE UNDERGROUND TELEPHONE LINE UNDERGROUND WASTER LINE UNDERGROUND WASTER LINE UNDERGROUND WASTER LINE UNDERGROUND TELEPHONE LINE WASTER MANHOLE EASEMENT LINE W	Chember Fig. PRASER FIR PROCED TO STATE TO THE PROPERTY OF T	TO MRO MRO SPECIAL BERNIN AVE LIC LANDSCAPE PLAN WANCHESTER/HEBRON AVE ITC BORD WANCHESTER ROAD PREPARED FOR WANCHESTER ROAD PREPARED FOR WANCHESTER PROAD PREPARED FOR WANCHESTER PROAD PROBLET ADDRESS FILE NO. SPECIAL PERMIT SECTION TPZ CHAIRMAN
CB CAICH BASIN DMH DRAIN MANHOLE SMH SEWER MANHOLE OHW OVERHEAD LINE MW MONITORING WELL RIM= RIM ELEVATION INV= INVERT ELEVATION FLEV. ELEVATION TYP. TYPICAL WQU WATER QUALITY UNIT GM GAS METER HAND HOLE WALK GATE FIRE HYDRANT FIRE HYDRANT FIRE HYDRANT OGAS GATE STREET SIGN LIGHT POLE UTILITY POLE WOU WATER QUALITY UNIT MONITORING WELL MW MONITORING WELL WON MONITORING WELL	UP#3486 / DMH-Rim=375-34 Inv.A=370.7 Inv.B=370.9	GRAPHIC SCALE One of the second permit app'd director of community development REV: 1-3-22 3-25-22 DATE: 11-08-2 SCALE: 1"=30' SHEET SP-6 MAP NO.





MANCHESTER/HEBRON AVE LLC
PROJECT/APPLICANT

1199 MANCHESTER RD. GLASTONBURY, CONN.
PROJECT ADDRESS


TPZ CHAIRMAN

DATE APPROVED

DIRECTOR OF COMMUNITY DEVELOPMENT

FILE NO.

WARNING THESE PLANS NOT TO BE USED FOR LOCATION OF UNDERGROUND UTILITIES — CALL BEFORE YOU DIG 1—800—922—4455 TWO WORKING DAYS BEFORE YOU DIG.



MNO ZOEV ZOEV


DATE: 11-08-21


SCALE: 1"=30'

SHEET SP-8


MAP NO. 21-002-1L

SITE 1199






LIGHT POLE DETAIL NOT TO SCALE



TYPICAL WALL MOUNT FIXTURE NOT TO SCALE




GARDCO S 64L - 900 mAMP LED SHOEBOX POLE TYPICAL LIGHT POLE FIXTURE NOT TO SCALE

NBURY, CONN.	
NBOKT, COMM.	
TPZ CHAIRMAN	_
DIRECTOR OF COMMUNITY DEVELOPMENT	
FILE NO.	
	DIRECTOR OF COMMUNITY DEVELOPMENT

DETAILS ROAD

GENERAL NOTES & 1199 MANCHESTE


DATE: 11-08-21 SCALE: SHOWN SHEET SP-9MAP NO. 21-002-1N




DIVERSION STORM WATER MANHOLE DETAIL

STM MH 117

NOT TO SCALE




DIVERSION STORM WATER MANHOLE DETAIL
STM MH 120



DIVERSION STORM WATER MANHOLE DETAIL


STM MH 118


NOT TO SCALE



STORM MANHOLE DETAIL


NO SCALE







STORM TRENCH DETAIL

NOT TO SCALE







PROJECT/APPLICANT	
1199 MANCHESTER RD. GL	ASTONBURY, CONN.
PROJECT ADDRESS	
	TPZ CHAIRMAN
	TPZ CHAIRMAN

REV. 3-05-22 TOWN COMMENTS

DATE: 11-08-21

SCALE: SHOWN

SHEET SP-10

MAP NO. 21-002-1CA

NOTES & DETAILS 1199 MANCHESTER ROAD

WENTWORTH CIVIL

ENGINEERS LLC
177 WEST TOWN ST.
LEBANON, CT 06249
TEL. (860) 642-7255
EANY (860) 642-7255
EANY (860) 643-7255

GENERAL NOTES

NOTE: THE CONTRACTOR SHALL NOTIFY THE TOWN OF GLASTONBURY ENGINEERING DIVISION 24 HOURS PRIOR TO BEGINNING ANY STORM DRAINAGE, SANITARY SEWER INSTALLATION, ROADWAY PREPARATION, PAVING, SIDEWALK, CURBING OR ANY EXCAVATION IN THE TOWN RIGHT OF WAY TO SCHEDULE INSPECTIONS. THE DIVISION CAN BE REACHED BETWEEN 8:00-4:30 PM MONDAY THROUGH FRIDAY AT (860) 652-7735.

THE LOCATION OF ALL EXISTING UTILITIES IS APPROXIMATE. THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THE LOCATION OF EXISTING UTILITIES IN THE FIELD PRIOR TO CONSTRUCTION. TOWN MAY REQUIRE CHANGES TO THE PLAN TO ADDRESS PROBLEMS THAT MAY RESULT IN THE

HEALTHY AND MATURE TREES TO BE PRESERVED WHERE POSSIBLE WITH USE OF HIGH VISIBILITY CONSTRUCTION FENCE DURING CONSTRUCTION.

REPLACE STAKED HAYBALES EVERY 60 DAYS.

NO CERTIFICATE OF OCCUPANCY SHALL BE ISSUED PRIOR TO ADEQUATE SITE / LOT STABILIZATION. THIS MEANS THAT THE BUILDING LOT SHALL BE LOAMED, SEEDED AND MULCHED WITH STRAW PRIOR TO ISSUANCE OF A C.O. (IF SEASON DOES NOT PERMIT SEEDING. THEN THE LOT MUST BE STABILIZED WITH STRAW OR EROSION CONTROL NETTING TO PREVENT EROSION.) PROPERLY INSTALLED E & S CONTROLS MUST BE IN PLACE TO CONTROL ANY E&S PROBLEMS. THE BUILDER / OWNER IS RESPONSIBLE FOR ALL STABILIZATION REQUIREMENTS.

AN INSPECTION BY THE ENVIRONMENTAL PLANNING STAFF WILL BE REQUIRED PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY. THIS INSPECTION EVALUATES COMPLIANCE TO THE APPROVED PLOT PLAN AND THE PERMANENT STABILIZATION REQUIREMENT.. PROVIDE AMPLE TIME OR NOTICE TO ALLOW FOR THIS INSPECTION NONCE STABILIZATION MEASURES ARE

IN EVENT OF BLASTING BEING REQUIRED FOR CONSTRUCTION, PRE AND POST BLAST SURVEYS SHALL BE CONDUCTED FOR NEARBY PROPERTIES.


TREE STUMPS AND BLASTED ROCK MATERIAL SHALL NOT BE BURIED ONSITE.

ALL APPLICABLE CONDITIONS OF APPROVAL THAT ARE RELEVANT TO DEVELOPMENT OF THE SUBJECT LOT.


THE USE AND LOCATION OF TEMPORARY FUEL TANKS FOR CONSTRUCTION PURPOSES MUST BE APPROVED BY THE FIRE MARSHAL'S OFFICE.

THE DEVELOPER SHALL INFORM ALL CONTRACTORS THAT THE DISPOSAL OF CONSTRUCTION DEBRIS BY OPEN BURNING IS NOT PERMITTED. THIS INCLUDES ANY VEGETATION THAT MIGHT BE CLEARED AS PART OF THIS PROPOSAL.

PORTABLE TOILETS SHALL BE POSITIONED AT A MINIMUM OF TEN FEET FROM THE BUILDING WHILE UNDER CONSTRUCTION.



Source: U.S. Department of Agriculture, Soil Conservation Service, Storrs, Connecticut PLACEMENT AND CONSTRUCTION OF A STRAW BALE BARRIER NOT TO SCALE



Source: U.S. Department of Agriculture, Soil Conservation Service, Storrs, Connecticut PLACEMENT AND CONSTRUCTION

OF A SYNTHETIC FILTER BARRIER NOT TO SCALE

<u>GENERAL</u>

THESE GUIDELINES SHALL APPLY TO ALL WORK CONSISTING OF ANY AND ALL TEMPORARY AND/OR PERMANENT MEASURES TO CONTROL WATER POLLUTION AND SOIL EROSION AS MAY BE REQUIRED, DURING THE CONSTRUCTION OF THE PROJECT.

IN GENERAL, ALL CONSTRUCTION ACTIVITIES SHALL PROCEED IN SUCH A MANNER SO AS NOT TO POLLUTE ANY WETLANDS, WATERCOURSE, WATERBODY, AND CONDUIT CARRYING WATER, ETC. THE CONTRACTOR SHALL LIMIT, INSOFAR AS POSSIBLE, THE SURFACE AREA OF EARTH MATERIALS EXPOSED BY CONSTRUCTION METHODS, AND IMMEDIATELY PROVIDE PERMANENT AND TEMPORARY POLLUTION CONTROL MEASURES TO PREVENT CONTAMINATION OF ADJACENT WETLANDS, WATERCOURSES AND WATERBODIES, AND TO PREVENT, INSOFAR AS POSSIBLE, FROSION ON THE SITE.

CONSTRUCTION METHODS, IN GENERAL, SHALL BE IN ACCORDANCE WITH THE PROVISIONS SET FORTH IN THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE STATE OF CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION AND TOWN OF

LAND GRADING

GENERAL:

THE RESHAPING OF THE GROUND SURFACE BY EXCAVATION AND FILLING OR A COMBINATION OF BOTH, TO OBTAIN PLANNED GRADES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING BASIC CRITERIA:

- A) NO FILL SHOULD BE PLACED WHERE IT WILL SLIDE, OR WASH UPON THE PREMISES OF ANOTHER OWNER OR UPON ADJACENT WETLANDS, WATERCOURSE OR WATERBODY.
- B) INSTALLATION OF SEDIMENT AND EROSION CONTROLS SUCH AS HAY BALES AND SILT FENCES SHALL BE ESTABLISHED PRIOR TO COMMENCING LAND DISTURBANCE ACTIVITIES. ALL SEDIMENT AND EROSION CONTROL STRUCTURES MUST BE MONITORED AND MAINTAINED

BY THE CONTRACTOR UNTIL THE SOIL SURFACE IS STABILIZED.

WILL BE REMOVED FROM ALL CATCHMENTS AS NECESSARY

- C) HAY BALES SHALL BE STAKED AND SILT FENCES SHALL BE PROPERLY SECURED. SEDIMENT
- D) PRIOR TO ANY REGRADING, STONE APRON SHALL BE PLACED BY THE ENTRANCE TO THE WORK AREA IN ORDER TO REDUCE MUD AND OTHER SEDIMENTS FROM LEAVING THE SITE. EXCAVATIONS SHOULD NOT BE MADE SO CLOSE TO PROPERTY LINES AS TO ENDANGER ADJOINING PROPERTY WITHOUT PROTECTING SUCH PROPERTY FROM EROSION, SLIDING, SETTLING OR CRACKING.

TOPSOILING

- 1. TOPSOIL SHALL BE SPREAD OVER ALL EXPOSED AREAS IN ORDER TO PROVIDE A SOIL MEDIUM HAVING FAVORABLE CHARACTERISTICS FOR THE ESTABLISHMENT, GROWTH AND MAINTENANCE OF VEGETATION.
- 2. REMOVE ALL LARGE STONES, TREE LIMBS, ROOTS, AND CONSTRUCTION DEBRIS.
- 3. APPLY LIME ACCORDING TO SOIL TEST OR AT THE RATE OF TWO (2) TONS PER ACRE.
- 1. TOPSOIL SHOULD HAVE PHYSICAL, CHEMICAL AND BIOLOGICAL CHARACTERISTICS FAVORABLE TO THE GROWTH OF PLANTS.
- 2. TOPSOIL SHOULD HAVE A SANDY OR LOAMY TEXTURE.
- 3. AN ORGANIC MATTER CONTENT OF OVER TWO (2%) PERCENT IS HIGHLY DESIRABLE. AVOID LIGHT COLORED LOWER SUBSOIL MATERIAL.
- 1. AVOID SPREADING WHEN TOPSOIL IS WET OR FROZEN. 2. SPREAD TOPSOIL UNIFORMLY TO A DEPTH OF AT LEAST FOUR (6") INCHES.

EROSION CHECKS

TEMPORARY PERVIOUS BARRIERS USING BALES OF HAY OR STRAW, HELD IN PLACE WITH STAKES DRIVEN THROUGH THE BALES AND INTO THE GROUND, OR SEDIMENT FILTER FABRIC FASTENED TO A FENCE POST AND BURIED INTO THE GROUND, SHALL BE INSTALLED AND MAINTAINED AS REQUIRED TO CHECK EROSION AND REDUCE SEDIMENTATION.

TEMPORARY AND/OR PERMANENT VEGETATIVE COVER

- PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED AS VARIOUS SECTIONS OF THE PROJECT ARE COMPLETED IN ORDER TO STABILIZE THE SOIL, REDUCE DOWNSTREAM DAMAGE FROM SEDIMENT AND RUNOFF AND TO ENHANCE THE AESTHETIC NATURE OF THE SITE. IT WILL BE APPLIED TO ALL CONSTRUCTION AREAS SUBJECT TO EROSION WHERE FINAL GRADING HAS BEEN COMPLETED AND A PERMANENT COVER IS NEEDED.
- SITE PREPARATION:
- 1. INSTALL REQUIRED SURFACE WATER CONTROL MEASURES. 2. REMOVE LOOSE ROCK, STONE AND CONSTRUCTION DEBRIS FROM AREA.
- 3. PERFORM ALL PLANTING OPERATIONS PARALLEL TO THE CONTOURS OF THE SLOPE. 4. APPLY TOPSOIL AS INDICATED ELSEWHERE HEREIN.
- 5. APPLY FERTILIZER ACCORDING TO SOIL TEST OR:

SUNNY TO PARTIALLY SUNNY SITES

WORK DEEPLY IN SOIL, BEFORE SEEDING, 300 LBS OF 10-10-10 FERTILIZER PER ACRE 7 LBS PER 1,000 SQUARE FEET); THEN SIX (6) TO EIGHT (8) WEEKS LATER APPLY ON THE SURFACE AN ADDITIONAL 300 LBS OF 10-10-10 FERTILIZER PER ACRE.

WORK DEEPLY IN SOIL, BEFORE SEEDING, 600 LBS OF 10-10-10 FERTILIZER PER ACRE (14 LBS PER 1,000 SQUARE FEET). **ESTABLISHMENT:**

- 1. SMOOTH AND FIRM SEEDBED WITH CULTIPACKER OR OTHER SIMILAR EQUIPMENT PRIOR TO SEEDING (EXCEPT WHEN HYDROSEEDING)
- 2. SELECT ADAPTED SEED MIXTURE AS FOLLOWS. NOTE RATES AND THE SEEDING DATES.


LBS./ACRE

KENTUCKY BLUEGRASS CREEPING RED FESCUE PERENNIAL RYEGRASS


0.10 ____ TOTAL

LBS./1000 S.F.

- 3. FINAL SEEDING SHALL TAKE PLACE PRIOR TO OCTOBER 1ST AS SEEDING AFTER THIS DATE RUNS A DISTINCT CHANCE OF FAILURE DUE TO ADVERSE WEATHER. ANY AREAS THAT ARE DISTURBED BETWEEN OCTOBER 1ST AND APRIL 1ST SHALL BE STABILIZED BY NON-VEGETATIVE MEANS SUCH AS HEAVY MULCHING WITH A BINDER OR JUTE MATTING WHICH WILL HAVE TO BE REMOVED BEFORE FINAL SEEDING AND THEN REPLACED AFTER
- 4. APPLY SEED UNIFORMLY ACCORDING TO RATE INDICATED, BY BROADCASTING, DRILLING, OR HYDRAULIC APPLICATION.
- 5. COVER GRASS AND LEGUME SEEDS WITH NOT MORE THAN 1/4 INCH OF SOIL WITH SUITABLE EQUIPMENT (EXCEPT WHEN HYDROSEEDING).
- 6. MULCH IMMEDIATELY AFTER SEEDING, IF REQUIRED, ACCORDING TO THE GUIDELINES.
- 7. USE PROPER INOCULANT ON ALL LEGUME SEEDINGS, USE FOUR (4) TIMES NORMAL RATE WHEN HYDROSEEDING.



|Silt Sack - Type B





CATCH BASIN SILT SACK DETAIL NOT TO SCALE

EROSION & SEDIMENTATION CONTROL RESPONSIBLE PARTY: RICHARD P. HAYES, JR. 1471 PLEASANT VALLEY RD.

1199 MANCHESTER ROAD CONSTRUCTION SEQUENCING NARRATIVE

THIS PROJECT CONSISTS OF CONSTRUCTING A NEW ±71.830 SF 5 STORY RESIDENTIAL BUILDING ON A VACANT WOODED LOT. PROPOSED SITE ACTIVITIES INCLUDE CONSTRUCTION OF A NEW BUILDING, PAVED PARKING AREA AND ACCESS DRIVE, OFFSITE SANITARY SEWER, WATER, STORM DRAINAGE SYSTEM INCLUDING UNDERGROUND DETENTION CHAMBERS AND UNDERGROUND UTILITIES. 2.3 ACRES OF SITE DISTURBANCE IS PROPOSED.

EROSION CONTROLS FOR SITE CONSTRUCTION:

MANCHESTER, CT 06042

(860) 646-0131

LOT DISTURBANCE WILL BE KEPT TO A MINIMUM. SILT FENCING OR STAKED HAYBALES TO BE PLACED BELOW ANY DISTURBED AREAS AND INSPECTED REGULARLY. SILTFENCE AND CONSTRUCTION ENTRANCE TO BE INSTALLED PRIOR TO ANY SITE DISTURBANCE ACTIVITIES. ROUGH GRADE SITE AND STABILIZE IMMEDIATELY WITH HEAVY MULCH AND/OR TEMPORARY VEGETATIVE COVER. INSPECT AND INSTALL ADDITIONAL SILTFENCE / HAYBALES AS NEEDED. INSPECT ALL E&S CONTROLS REGULARLY (WEEKLY AND AFTER RAIN EVENTS OF 1/2" OR GREATER). LONG TERM STOCKPILES ARE TO BE SEEDED IN ADDITION TO BEING RINGED WITH SILTFENCE. REMOVE ALL EROSION CONTROL MEASURES AT END OF CONSTRUCTION ONCE ENTIRE SITE IS VEGETATED AND STABILIZED.

MASS GRADING ACTIVITIES, FOUNDATION AND RETAINING WALL CONSTRUCTION WILL BE PERFORMED AS OUTLINED IN REPORT PREPARED BY WELTI GEOTECHNICAL, P.C. AND DATED 1/20/22 (AS REVISED). DURING THE INITIAL PORTION OF CONSTRUCTION EXCESS MATERIAL WILL BE HAULED OFF SITE TO PREPARE THE BUILDING AND PARKING AREA PAD. SITE ACCESS SHOULD BEGIN AT THE HEBRON AVENUE CONSTRUCTION ENTRANCE AND PROCEED TO THE SOUTH AND EAST TO CREATE A FLAT TERRACE IN THIS AREA. AS EXCAVATION PROCEEDS, MATERIAL WILL BE EXCAVATED FROM THE SOUTHERLY PORTION OF THE SITE IN 10 TO 15 FOOT VERTICAL STEPS AND STABILIZED WITH VEGETATION AT EACH STEP. MATERIAL WILL BE PUSHED TO THE NORTHERLY TERRACE FOR LOADING ONTO TRUCKS. SEDIMENTATION TRAPS WILL BE INSTALLED ALONG WITH DIVERSION SWALES TO CREATE A BOWL SHAPED EXCAVATION DURING THE MASS GRADING PHASE OF OPERATION. BY USING THIS APPROACH, THE SITE CAN DRAIN STORM WATER RUNOFF TO THE INTERIOR DURING ROUGH GRADING WHICH WILL INFILTRATE INTO THE GROUND AND NOT DISCHARGE OFFSITE. THE PROPOSED CUTS TO THE WEST AND SOUTH OF THE PROPOSED BUILDING WILL HAVE A SLOPES OF 2:1 DURING CONSTRUCTION. 1.5:1 TEMPORARY SLOPES WILL BE APPROPRIATELY STABILIZED BEHIND THE FOUNDATION WALL AND RETAINING WALLS FOR THE SHORT TIME DURING CONSTRUCTION AND WILL ULTIMATELY BE BACKFILLED BEHIND THE WALLS FOR FINAL GRADING AFTER THE BUILDING FOUNDATION AND RETAINING WALLS ARE CONSTRUCTED.

SITE CONSTRUCTION SEQUENCING AS FOLLOWS:

- 1. INSTALLATION OF CONSTRUCTION ENTRANCE 2. CLEARING AND GRUBBING AREAS NOT ALREADY CLEARED. INSTALLATION OF REMAINING E&S MEASURES
- 4. ROUGH GRADE SITE. INSTALL WATER DIVERSION BARS AND SEDIMENT TRAP. REMOVE EXCESS MATERIAL OFFSITE BEGIN RETAINING WALL CONSTRUCTION. INSTALLATION OF FOUNDATION - COMMENCE BUILDING CONSTRUCTION
- GRADE ACCESS DRIVES AND PARKING AREAS TO SUBGRADE INSTALL STORM DRAINAGE INFRASTRUCTURE, WATER, ROOF DRAINS, SITE LIGHTING AND
- UNDERGROUND UTILITIES. INSTALL ONSITE AND OFFSITE SANITARY SEWER. 8. INSTALL BANK RUN AND PROCESSED GRAVEL AND SIDEWALKS INSTALL BITUMINOUS ASPHALT BASE COARSE AND CURBING.
- 10. FINE GRADE SITE, LOAM, SEED & FERTILIZE DISTURBED AREAS 11. INSTALL DUMPSTER SCREENING AND FINISH COARSE BITUMINOUS ASPHALT
- 12. LANDSCAPE SITE 13. REMOVE EROSION CONTROLS

STRIPPING TOPSOIL

CONSTRUCTION ENTRANCE TO BE INSTALLED PRIOR TO ANY SITE DISTURBANCE ACTIVITIES. REMAININGING E&S MEASURES TO BE INSTALLED AFTER CLEARING IS COMPLETED. IT IS EXPECTED THIS ACTIVITY WILL TAKE LESS THAN 18 MONTHS TO COMPLETE.

POST CONSTRUCTION STORMWATER RUNOFF MANAGEMENT PLAN

RESPONSIBLE PARTY: RICHARD P. HAYES, JR. 1471 PLEASANT VALLEY RD. MANCHESTER, CT 06042 (860) 646-0131

STORMWATER MAINTENANCE PLAN


-THE RESPONSIBLE PARTY SHALL MAINTAIN UP TO DATE INSPECTION LOGS AND MAINTENANCE

DRIVEWAY / PARKING AREAS / SIDEWALKS -KEEP WINTER SANDING TO A MINIMUM. MINIMIZE USE OF SALT ON PROPERTY AS SODIUM CAN BREAK DOWN SOIL STRUCTURE AND MINIMIZE INFILTRATION CAPABILITIES IN INFILTRATION AREAS. -SWEEP / REMOVE SAND FROM DRIVEWAY, PARKING AREAS & ADJACENT VEGETATED AREAS

PERMITTED SOLID WASTE FACILITY. - REMOVE LEAVES FROM PAVEMENT AND DRAINAGE INLETS ROUTINELY UNTIL FINAL LEAF FALL AND PRIOR TO SNOWFALL.

ANNUALLY (SPRING) BY APRIL 30th . SWEEPINGS ARE TO BE DISPOSED OF OFFSITE AT A

- CLEAN CATCH BASIN INLET GRATES AND VACUUM CATCH BASIN SUMPS ANNUALLY.
- UNDERGROUND DETENTION CHAMBERS AND HYDRODYNAMIC SEPARATOR
 -INSPECT FOR SEDIMENT ACCUMULATION TWICE PER YEAR. VACUUM ACCUMULATED SEDIMENTS FROM SEPARATOR, MANHOLES, HEADERS AND CHAMBERS WHEN SEDIMENT EXCEEDS 6" IN DEPTH. SEDIMENTS ARE TO BE DISPOSED OF OFFSITE AT A PERMITTED SOLID WASTE FACILITY.




List of Common Placement/Installation Mistakes to Avoid

- Ensure the ends are properly secured.
- Install a sufficient number of staples to hold the blanket in place.
- Overlap the blanket to ensure water that flows on top of the blanket and is unable to flow under the

EROSION CONTROL BLANKET DETAIL

NOT TO SCALE



FILE NO.

DATE: 11-08-21 SCALE: SHEET

S-RO,

DE STI

SH SH

N 199

CHESTER, GLASTONBUR

M

WORTH (
VGINEERS

77 WEST TOWN ST
FRANON, CT 06249

SP-11

SHOWN

MAP NO. 21-002-1CA