

ZONING DATA

ZONE:	PBD / RR / *GW-1	PROPOSED		
LOT AREA	60,000 SF	±104,554 SF - 2.40 AC.		
LOT FRONTAGE	200 FT	238.75 FT (HEBRON AVE.)		
		359.21 FT (MANCHESTER RD.)		
FRONT YARD	75 FT	76 FT		
SIDE YARD	25 FT	25.5 FT		
REAR YARD	25 FT	99 FT		
LOT COVERAGE	20% (MAX.)	14,366 SF (13.74% PROPOSED)		
OPEN SPACE (MIN.)	2 X COVERAGE			
	= 28,732 SF (27.48% MIN.)	53,493 SF (51.17% PROPOSED)		
IMPERVIOUS COVERAGE		51,051 SF (48.83%)		
BLDG. HEIGHT (MAX.)	35 FT	58 FT (SECT. 2.6)		
BLDG. STORIES (MAX.)	2.5 STORIES	5 STORIES		
RESIDENTIAL DENSITY		30.8 UNITS / ACRE		

*PARCEL IS LOCATED IN GROUNDWATER PROTECTION ZONE 1

TOTAL:

PARKING CALCULATIONS

REQUIRED PER PDB / RR 1 SPACE PER RESIDENTIAL UNIT RESIDENTIAL:

<u>PROPOSED</u> *4 HANDICAPPED*


81 STANDARD

85 SPACES

74 SPACES

74 UNITS x 1 SPACE / UNIT = 74 SPACES

MANCHESTER/HEBRON AVE LLC PROJECT/APPLICANT 1199 MANCHESTER RD. GLASTONBURY, CONN. PROJECT ADDRESS TPZ CHAIRMAN DATE APPROVED DIRECTOR OF COMMUNITY DEVELOPMENT FILE NO.



SCALE: 1"=1,000'

1199 MANCHESTER ROAD PREPARED FOR MANCHESTER/HEBRON AVE LLC GLASTONBURY, CONN.

INDEX TO SHEETS

COVER SHEET

SHEET C-1

SURVEY PLANS

A-2 BOUNDARY SURVEY TOPOGRAPHIC MAP - EXISTING CONDITIONS SURVEY

SHEET SV-1

SITE PLANS

SITE LAYOUT PLAN SHEET SP-1

SITE GRADING SHEET SP-2 UTILITY PLAN

SHEET SP-3 OFFSITE SANITARY SEWER SHEET SP-4

EROSION & SEDIMENTATION CONTROL PLAN SHEETS SP-5 THRU SP-7


LANDSCAPING PLAN SHEET SP-8 ACCESS MANAGEMENT PLAN SHEET SP-9


SITE ILLUMINATION PLAN SHEET SP-10


GENERAL NOTES & DETAILS SHEETS SP-11 THRU SP-13


DATE: 11-08-21 SCALE: SHOWN


MAP NO. 21-002-1C











EROSION & SEDIMENTATION CONTROL RESPONSIBLE PARTY: RICHARD P. HAYES, JR. 1471 PLEASANT VALLEY RD. MANCHESTER, CT 06042 (860) 646-0131 1199 MANCHESTER ROAD CONSTRUCTION SEQUENCING NARRATIVE - PHASE I Rim= 348.82 EROSION CONTROLS FOR SITE CONSTRUCTION: Inv. A=345.1 Inv.B=344.6 LOT DISTURBANCE WILL BE KEPT TO A MINIMUM. SILT FENCING OR STAKED HAYBALES TO BE PLACED BELOW ANY DISTURBED AREAS AND INSPECTED REGULARLY. SILTFENCE AND CONSTRUCTION ENTRANCE TO BE INSTALLED PRIOR TO ANY SITE DISTURBANCE INSPECT AND INSTALL ADDITIONAL SILTFENCE / HAYBALES AS NEEDED. INSPECT ALL E&S CONTROLS REGULARLY (WEEKLY AND AFTER RAIN EVENTS OF 1/2" OR GREATER). LONG TERM STOCKPILES ARE TO BE SEEDED IN ADDITION TO BEING RINGED WITH SILTFENCE. REMOVE ALL EROSION CONTROL MEASURES AT END OF CONSTRUCTION ONCE ENTIRE SITE IS VEGETATED AND Inv.A=345.8 Inv.B=345.9 MASS GRADING ACTIVITIES WILL BE PERFORMED AS OUTLINED IN REPORT PREPARED BY WELTI GEOTECHNICAL, P.C. AND DATED 1/20/22 (AS REVISED). DURING THE INITIAL PORTION OF ON CATCH BASINEY SILT SACK CONSTRUCTION EXCESS MATERIAL WILL BE HAULED OFF SITE TO PREPARE THE BUILDING AND PARKING AREA PAD. SITE ACCESS SHOULD BEGIN AT THE HEBRON AVENUE CONSTRUCTION ENTRANCE AND PROCEED TO THE SOUTH AND EAST TO CREATE A FLAT TERRACE IN THE NORTHEAST CORNER OF THE SITE FOR LOADING OF TRUCKS. EXCAVATION WILL PROCEED SOUTHERLY AND WESTERLY IN 15 TO 20 FOOT STEPS IN A TOP DOWN MANNER. MATERIAL WILL Inv.=347.0 BE PUSHED TO THE NORTHEAST FOR LOADING ONTO TRUCKS. SEDIMENTATION TRAPS WILL BE INSTALLED ALONG WITH DIVERSION SWALES TO ENTRAP SEDIMENT ONSITE. THE EXCAVATION WILL PROCEED IN A MANNER TO CREATE A BOWL SHAPE DURING THE MASS GRADING PHASE OF OPERATION. BY USING THIS APPROACH, THE SITE CAN DRAIN STORM WATER RUNOFF TO THE INTERIOR DURING ROUGH GRADING WHICH WILL INFILTRATE INTO THE GROUND AND NOT DISCHARGE OFFSITE. THE PROPOSED CUTS TO THE WEST AND SOUTH OF THE PROPOSED BUILDING WILL HAVE A SLOPES OF 2:1 DURING CONSTRUCTION. 1.5:1 TEMPORARY SLOPES WILL BE UTILIZED DURING THE INITIAL EXCAVATION PROCESS IN THE NORTHEAST CORNER OF SILT SACK 201 (TYP.) SITE CONSTRUCTION SEQUENCING AS FOLLOWS: PRESERVE SOIL INTEGRITY OF UNDERGROUND DETENTION AREA SILT TRAP INSTALLATION OF CONSTRUCTION ENTRANCES TOM ELEV. = 350.0 SHAH PROPERTIES LLC AND RAIN GARDEN DURING
CONSTRUCTION. AVOID
COMPACTION, OVER EXCAVATION
OR FILLING DURING CONSTRUCTION CLEAR ENTIRE SITE
 INSTALL ADDITIONAL E&S MEASURES CLEAR AND GRUB MAJORITY OF SITE — DO NOT STUMP AND GRUB AREAS SHOWN AT NORTHWEST CORNER AND SOUTHEAST CORNER ALONG ROAD FRONTAGE. ASSESSOR #: J5-2920-50086 2088 HEBRON AVENUE • STRIP TOPSOIL AND STOCKPILE AT NORTHWEST CORNER OF SITE AS SHOWN. SEED AND MULCH TO ALLOW TEMPORARY VEGETATION TO ESTABLISH. RING STOCKPILE WITH SILT FENCE OR HAY BALES BEGIN EXCAVATION OF LOADING AREA IN NORTHEAST CORNER OF SITE. INSTALL WATER DIVERSION BAR AND SEDIMENT TRAP. REMOVE EXCESS MATERIAL OFFSITE. TRUCK TRAFFIC TO ENTER AT HEBRON AVENUE CONSTRUCTION ENTRANCE AND EXIT ONTO MANCHESTER. 2:1 SLOPE WEST AND SOUTH OF BUILDING TO BE COVERED WITH ERÖSTON CONTROL BLANKET AFTER TOPSOIL AND SEEDING. CONTINUE INSTALLATION AND MAINTENANCE OF ADDITIONAL E&S MEASURES EXCAVATION TO PROCEED IN A TOP DOWN MANNER TO ELEVATION 385. EXCAVATION TO CONTINUALLY TO PROCEED IN A BOWL SHAPED MANNER WITH A BERM IN PLACE AROUND PERIMETER AT A MINIMUM ELEVATION OF 388.5. BERM TO BE IN PLACE AT THE END OF EVERY WORK DAY AND PRIOR TO AND DURING MAJOR RAIN EVENTS. BEGIN SHAPING 2:1 SLOPE FROM ELEVATION ±406 TO 385. TOPSOIL, FINAL GRADE, SEED, MULCH AND INSTALL EROSION CONTROL BLANKET. THIS SLOPE TO BE COMPLETELY ESTABLISHED PRIOR TO PROCEEDING TO NEXT PHASE OF EXCAVATION TWO-STORY BUILDING Rim=358.45 Inv=351.4 MAINTAIN TOP OF BERM = 360.0 (MINIMUM) DURING CONSTRUCTION DIVERSION LOADING AREA EXCAVATE TERRACE TO ELEVATION 385.0
BERM EXTERIOR TO ELEVATION 388.5 TO FORM BOWL SHAPED EXCAVATION. PROPOSED 36 CONSTRUCTION ENTRANCE Inv.A=353.4 Inv.B=353.1 CATCH BASIN SILT SACK (TYP.) 25' DRAINAGE EASEMENT Rim=361.92 Inv.A=355.1 Inv.B=356.3 Inv.C=356.1 BERM TOP/ OF WORK SLOPE AT END OF WORK DAY AND DURING MAJOR STORM EVENT\$ TO ELEVATION 388.5 TO MAINTAIN BOWL SHAPED EXCAVATION. Rim=402.36 Inv.A=397.1 380.8 To Bottom Of Chamber ROAD MANCHESTER/HEBRON AVE LLC PROJECT/APPLICANT PROPOSED CONSTRUCTION ENTRANCE 1199 MANCHESTER RD. GLASTONBURY, CONN. PROJECT ADDRESS Rim=370.88 Inv.A=367.3 Inv.B=367.3 TPZ CHAIRMAN DATE APPROVED DIRECTOR OF COMMUNITY DEVELOPMENT Rim=370.88 FILE NO. Inv.A=364.9 Inv.B=366.1 Inv.C=365.7 RESPONSIBLE PARTY: RICHARD P. HAYES, JR. 1471 PLEASANT VALLEY RD. MANCHESTER, CT 06042 (860) 646-0131 **LEGEND** DMH Rim=386.3 Inv.A=372.7 Inv.B=382.5 _____ EXISTING CONTOUR Rim=373.2 Inv.A=368.6 Inv.B=368.8 PROPOSED CONTOUR 170X2 EXISTING SPOT ELEVATION 172.9 PROPOSED SPOT ELEVATION PROPOSED LIMIT OF CLEARING STAKED HAYBALES / SILTFENCE

CONTROL & SEDIMENTATION 1199 MANCHESTER

ANCHESTER/HEBRON AVE GLASTONBURY, CONNECTICUT

EROSION

DATE: 11-08-21 SCALE: 1"=30'


SHEET SP-5MAP NO. 21-002-1ES

EROSION & SEDIMENTATION CONTROL RESPONSIBLE PARTY: RICHARD P. HAYES, JR. 1471 PLEASANT VALLEY RD. MANCHESTER, CT 06042 (860) 646-0131 1199 MANCHESTER ROAD CONSTRUCTION SEQUENCING NARRATIVE - PHASE II EROSION CONTROLS FOR SITE CONSTRUCTION: LOT DISTURBANCE WILL BE KEPT TO A MINIMUM. SILT FENCING OR STAKED HAYBALES TO BE PLACED BELOW ANY DISTURBED AREAS AND INSPECTED REGULARLY. SILTFENCE AND CONSTRUCTION ENTRANCE TO BE INSTALLED PRIOR TO ANY SITE DISTURBANCE INSPECT AND INSTALL ADDITIONAL SILTFENCE / HAYBALES AS NEEDED. INSPECT ALL E&S CONTROLS REGULARLY (WEEKLY AND AFTER RAIN EVENTS OF 1/2" OR GREATER). LONG TERM STOCKPILES ARE TO BE SEEDED IN ADDITION TO BEING RINGED WITH SILTFENCE. REMOVE ALL EROSION CONTROL MEASURES AT END OF CONSTRUCTION ONCE ENTIRE SITE IS VEGETATED AND MASS GRADING ACTIVITIES WILL BE PERFORMED AS OUTLINED IN REPORT PREPARED BY WELTI GEOTECHNICAL, P.C. AND DATED 1/20/22 (AS REVISED). DURING THE INITIAL PORTION OF CONSTRUCTION EXCESS MATERIAL WILL BE HAULED OFF SITE TO PREPARE THE BUILDING AND PARKING AREA PAD. TRUCK ACCESS WAY IS TO BE EXCAVATED AND SHAPED TO THE SOUTHEAST CORNER AS SHOWN. INSTALL NEW CONSTRUCTION ENTRANCE AT SOUTHEAST CORNER OF PROPERTY TO ALLOW TRUCKS TO EXIT ONTO MANCHESTER ROAD AT THIS LOCATION. ABANDON AND REMOVE PHASE I CONSTRUCTION ENTRANCE ON MANCHESTER ROAD AND STABILIZE WITH LOAM, SEED AND MULCH. THE NEXT STEP OF EXCAVATION WILL PROCEED SOUTHERLY AND WESTERLY IN A SECOND 10 TO 15 FOOT STEP IN A TOP DOWN MANNER.

MATERIAL WILL BE PUSHED AND EXCAVATED WORKING FROM EAST TO WEST FOR LOADING ONTO TRUCKS. SEDIMENTATION TRAPS WILL BE INSTALLED ALONG WITH DIVERSION SWALES TO ENTRAP SEDIMENT ONSITE. THE EXCAVATION WILL PROCEED IN A MANNER TO CREATE A BOWL SHAPE DURING THE MASS GRADING PHASE OF OPERATION. BY USING THIS APPROACH, THE SITE CAN DRAIN STORM WATER RUNOFF TO THE INTERIOR DURING ROUGH GRADING WHICH WILL INFILTRATE INTO THE GROUND AND NOT DISCHARGE OFFSITE. THE PROPOSED CUTS TO THE WEST AND SOUTH OF THE PROPOSED BUILDING WILL HAVE A SLOPES OF 2:1 DURING CONSTRUCTION. 1.5:1 TEMPORARY SLOPES WILL BE UTILIZED DURING THE INITIAL EXCAVATION PROCESS IN THE EASTERLY PORTION OF THE SITE. SITE CONSTRUCTION SEQUENCING AS FOLLOWS: INSTALL / MAINTAIN CONSTRUCTION ENTRANCES AND ADDITIONAL E&S MEASURES
 CLEAR AND GRUB SOUTHEAST CORNER OF SITE ALONG MANCHESTER ROAD — DO NOT STUMP AND GRUB AREA SHOWN AT NORTHWEST CORNER CORNER ALONG ROAD FRONTAGE. BEGIN EXCAVATION OF TRUCK ACCESS ROAD FROM NORTHEAST CORNER TO SOUTHEAST CORNER OF SITE. INSTALL NEW CONSTRUCTION ENTRANCE AT SOUTHEAST CORNER TO ALLOW TRUCKS TO EXIT ONTO MANCHESTER ROAD. CONTINUE INSTALLATION AND MAINTENANCE OF ADDITIONAL E&S MEASURES ABANDON AND REMOVE CONSTRUCTION ENTRANCE AT NORTHEAST CORNER OF SITE ONTO MANCHESTER ROAD. LOAM, SEED AND MULCH AREA TO STABILIZE AND INSTALL ADDITIONAL E&S MEASURES AS REQUIRED.

• SECOND STEP PHASE OF EXCAVATION TO PROCEED IN A TOP DOWN MANNER TO ELEVATION 373 WORKING EAST TO WEST. EXCAVATION TO CONTINUALLY PROCEED IN A BOWL SHAPED MANNER WITH A BERM IN PLACE AROUND PERIMETER AT A MINIMUM ELEVATION OF 375.5. BERM TO BE IN PLACE AT THE END OF EVERY WORK DAY AND PRIOR TO AND DURING MAJOR RAIN EVENTS.

BEGIN SHAPING 2:1 SLOPE FROM ELEVATION ±385 TO 373. SHAPE IN AND FINAL GRADE REVERSE BENCH AS SHOWN. TOPSOIL, FINAL GRADE, SEED, MULCH AND INSTALL EROSION CONTROL BLANKET. INSTALL TEMPORARY MODIFIED RIP RAP SWALE FROM LOW POINT OF REVERSE BENCH TO ELEVATION 373 AS SHOWN. RIP RAP TO STAY IN PLACE UNTIL PIPE AND CATCH BASINS INSTALLED TO COLLECT RUNOFF AT THIS POINT. THIS SLOPE TO BE COMPLETELY ESTABLISHED PRIOR TO PROCEEDING TO NEXT PHASE OF EXCAVATION



ANCHESTER /HEBRON GLASTONBURY, CONNECT

& SEDIMENTATION 1199 MANCHESTER

EROSION

DATE: 11-08-21

MAP NO. 21-002-1ES

1"=30'

SP-6

SCALE:

SHEET


& SEDIMENTATION 1199 MANCHESTER

ANCHESTER/HEBRON AVE GLASTONBURY, CONNECTICUT EROSION

DATE: 11-08-21 SCALE: 1"=30' SHEET SP-7MAP NO. 21-002-1ES

SY	′MB□L	SCIENTIFIC/ COMMON NAME	ITMAUQ	TY SIZE F	POLLINATOR	≀ NATI
TREES: DECIDUOUS (4	ACER X FREEMANII 'JEFFERSRED'/ AUTUMN BLAZE MAPLE	8	3 - 3 1/2" CA	ALIPER	N
220120200	+REDM	ACER RUBRUM 'COLUMNARE'/ COLUMNAR RED MAPLE	4	3 - 3 1/2" C	ALIPER	N
		AMELANCHIER CANADENSIS/ SHADBLOW, SERVICEBERRY	5	3 - 3 1/2" CA	ALIPER P	N
	(k)D)	CORNUS KOUSA/ KOUSA DOGWOOD	1	3 - 3 1/2" CA	ALIPER P	
		STEWARTIA KOREANA/ STEWARTIA	3	5 - 6′	Р	
TREES: WARDEN EVERGREEN	ABIES FRASERI/ FRASER FIR	22	5 - 6′		N	
	JUNIPERUS VIRGINIANA/ RED CEDAR	4	5 - 6′		N	
SHRUBS:	CLETHRA ALNIFOLIA 'HUMMINGBIRD'/ SUMMERSWEET CLETHRA	19	18 - 21"	Р	N	
	HYDRANGEA ANDMYLA PETIDLARIS/ CLIMING HYDRANGEA	3	5 GAL.	Р		
	①	ILEX GLABRA 'SHAMROCK'/ SHAMROCK HOLLY	19	3 - 4'	Р	N
	Sept.	ILEX VERTICILLATA 'RED SPRITE'/ WINTERBERRY	6	18 - 21"	Р	N
	Entraga	ILEX VERTICILLATA 'WINTER RED'/ WINTER RED WINTERBERRY	17	18 - 21"	Р	N
		JUNIPERUS CHINENSIS PF. PLUMOSA/ COMPACT JUNIPER	19	24'-36"		
		JUNIPERUS COMMUNIS 'GOLD CONE'/ GOLD CONE JUNIPER	12	24'-36"		N
	(BAY)	MYRICA PENNYSYLVANICUM/ BAYBERRY	13	24'-36"	Р	N
	POT	POTENTILLA FRUTICOSA 'ABBOTSWOOD'/ ABBOTSWOOD POTENTILL	.A 4	18 - 21"	Р	N
(POT	POTENTILLA FRUTICOSA 'BELLA SOL'/ BELLA SOL POTENTILLA	8	18 - 21"	Р	N
	(POT)	POTENTILLA FRUTICOSA 'GOLD DROP'/ GOLD DROP POTENTILLA	4	18 - 21"	Р	N
	(DE)	RHDDDDENDRON 'DELAWARE VAL. WH.'/ DEL.VALLEY WH. AZALEA	6	24'-36"	Р	
		RHUS ARDMATICA 'GRD-LDW'/ FRAGRANT SUMAC	35	24'-36"		N
PLANTS: S:P	ROSA 'KNOCKOUT'/ KNOCKOUT SHRUB ROSE	11	24'-36"	Р		
	SPIRAEA BUMALDA 'ANTHONY WATERER'/ SPIREA	12	24′-36″	Р		
HERBACEOUS (S)	(c)	CALAMAGROSTIS KARL FOERSTER/ FEATHER REED GRASS	27	2 Gal.		
		SEDUM 'BRILLIANT'/ SEDUM	26	1 Gal.	Р	

NOTE: SLOPES ARE SEEDED WITH CONSERVATION MIX WITH POLLINATORS --HART SEED CO. WETHERSFIELD, CT NOTE: ALL PLANT BEDS TO BE MULCHED WITH SHREDDED BARK TO A MAXIMUM DEPTH OF 3"





CONCRETE CURB

BITUMINOUS BERM

BITUMINOUS CURB

UTILITY POLE

CONC. CONCRETE

UP

RCP

PVC

CPP

CLF

CB

GM

CMP

EDGE OF PAVEMENT

VERTICAL GRANITE CURB

BITUMINOUS PAVEMENT

REINFORCED CONCRETE PIPE

POLYVINYLCHLORIDE PIPE

CORRUGATED METAL PIPE

CORRUGATED PLASTIC PIPE

CHAIN-LINK FENCE

MONITORING WELL

CATCH BASIN

DMH DRAIN MANHOLE

SMH SEWER MANHOLE

OHW OVERHEAD LINE

RIM= RIM ELEVATION


ELEV. ELEVATION

INV= INVERT ELEVATION

TYP. TYPICAL WQU WATER QUALITY UNIT

GAS METER

HAND HOLE



O UTILITY POLE

GUY POLE


GUY WIRE

BOLLARD/POSTBORING

MW • MONITORING WELL

⇔ → UTILITY POLE W/LIGHT

E — G — T — — — — — — — — — — — — — — — —	EDGE OF PAVEMENT EDGE OF GRAVEL/LANDSCAPE CURB STEEL GUARD RAIL CHAIN LINK FENCE UNDERGROUND DRAINAGE LINE UNDERGROUND SEWER LINE OVERHEAD WIRE UNDERGROUND ELECTRIC LINE UNDERGROUND GAS LINE UNDERGROUND WATER LINE UNDERGROUND WATER LINE UNDERGROUND TELEPHONE LINE PROPERTY LINE EASEMENT LINE STATE HIGHWAY LINE
٥	PROP. PARKING SPACE SUBTOTAL
3	PROP. ACCESSIBLE PARKING SPACE




MANCHESTER/HEBRON AVE LLC
PROJECT/APPLICANT ZONE

1199 MANCHESTER RD. GLASTONBURY, CONN.
PROJECT ADDRESS
FILE NO.

TPZ CHAIRMAN

DIRECTOR OF COMMUNITY DEVELOPMENT




REV: 1-3-22 3-25-22 6-2-22 DATE: 11-08-21


1199

 SCALE:
 1"=30"

 SHEET
 SP-8

MAP NO.





DIMENSIONS

AMERICAN ELECTRIC LIGHTING AUTOBAHN ATBO SERIES LED FULL CUTOFF POLE FIXTURE TYPICAL LIGHT POLE FIXTURE NOT TO SCALE

1199 MANCHESTER RD. GLASTONBURY, CONN. TPZ CHAIRMAN DIRECTOR OF COMMUNITY DEVELOPMENT FILE NO.


> WARNING THESE PLANS NOT TO BE USED FOR LOCATION OF UNDERGROUND UTILITIES — CALL BEFORE YOU DIG 1-800-922-4455 TWO WORKING DAYS BEFORE YOU DIG.


GRAPHIC SCALE (IN FEET) 1 inch = 30 ft.

DATE: 11-08-21 SCALE: 1"=30'

SITE 1199

SHEET SP-10 뿐₩MAP NO. 21-002-1LF





CHESTER/HEBRON AVE GLASTONBURY, CONNECTICUT DETAILS ESTER ROAD NOTES & L

NTWORTH CIVII ENGINEERS LLC

DATE: 11-08-21 SCALE: SHEET

SHOWN SP-12 ~ MAP NO. 21-002-1CA

GENERAL NOTES

NOTE: THE CONTRACTOR SHALL NOTIFY THE TOWN OF GLASTONBURY ENGINEERING DIVISION 24 HOURS PRIOR TO BEGINNING ANY STORM DRAINAGE, SANITARY SEWER INSTALLATION, ROADWAY PREPARATION, PAVING, SIDEWALK, CURBING OR ANY EXCAVATION IN THE TOWN RIGHT OF WAY TO SCHEDULE INSPECTIONS. THE DIVISION CAN BE REACHED BETWEEN 8:00-4:30 PM MONDAY THROUGH FRIDAY AT (860) 652-7735.

THE LOCATION OF ALL EXISTING UTILITIES IS APPROXIMATE. THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THE LOCATION OF EXISTING UTILITIES IN THE FIELD PRIOR TO CONSTRUCTION. TOWN MAY REQUIRE CHANGES TO THE PLAN TO ADDRESS PROBLEMS THAT MAY RESULT IN THE

HEALTHY AND MATURE TREES TO BE PRESERVED WHERE POSSIBLE WITH USE OF HIGH VISIBILITY CONSTRUCTION FENCE DURING CONSTRUCTION.

REPLACE STAKED HAYBALES EVERY 60 DAYS.

NO CERTIFICATE OF OCCUPANCY SHALL BE ISSUED PRIOR TO ADEQUATE SITE / LOT STABILIZATION. THIS MEANS THAT THE BUILDING LOT SHALL BE LOAMED, SEEDED AND MULCHED WITH STRAW PRIOR TO ISSUANCE OF A C.O. (IF SEASON DOES NOT PERMIT SEEDING. THEN THE LOT MUST BE STABILIZED WITH STRAW OR EROSION CONTROL NETTING TO PREVENT EROSION.) PROPERLY INSTALLED E & S CONTROLS MUST BE IN PLACE TO CONTROL ANY E&S PROBLEMS. THE BUILDER / OWNER IS RESPONSIBLE FOR ALL STABILIZATION REQUIREMENTS.

AN INSPECTION BY THE ENVIRONMENTAL PLANNING STAFF WILL BE REQUIRED PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY. THIS INSPECTION EVALUATES COMPLIANCE TO THE APPROVED PLOT PLAN AND THE PERMANENT STABILIZATION REQUIREMENT. PROVIDE AMPLE TIME OR NOTICE TO ALLOW FOR THIS INSPECTION NONCE STABILIZATION MEASURES ARE

IN EVENT OF BLASTING BEING REQUIRED FOR CONSTRUCTION, PRE AND POST BLAST SURVEYS SHALL BE CONDUCTED FOR NEARBY PROPERTIES.


TREE STUMPS AND BLASTED ROCK MATERIAL SHALL NOT BE BURIED ONSITE.

ALL APPLICABLE CONDITIONS OF APPROVAL THAT ARE RELEVANT TO DEVELOPMENT OF THE SUBJECT LOT.


THE USE AND LOCATION OF TEMPORARY FUEL TANKS FOR CONSTRUCTION PURPOSES MUST BE APPROVED BY THE FIRE MARSHAL'S OFFICE.

THE DEVELOPER SHALL INFORM ALL CONTRACTORS THAT THE DISPOSAL OF CONSTRUCTION DEBRIS BY OPEN BURNING IS NOT PERMITTED. THIS INCLUDES ANY VEGETATION THAT MIGHT BE CLEARED AS PART OF THIS PROPOSAL.

PORTABLE TOILETS SHALL BE POSITIONED AT A MINIMUM OF TEN FEET FROM THE BUILDING WHILE UNDER CONSTRUCTION.



Source: U.S. Department of Agriculture, Soil Conservation Service, Storrs, Connecticut PLACEMENT AND CONSTRUCTION OF A STRAW BALE BARRIER NOT TO SCALE



Source: U.S. Department of Agriculture, Soil Conservation Service, Storrs, Connecticut PLACEMENT AND CONSTRUCTION

OF A SYNTHETIC FILTER BARRIER NOT TO SCALE

<u>GENERAL</u>

THESE GUIDELINES SHALL APPLY TO ALL WORK CONSISTING OF ANY AND ALL TEMPORARY AND/OR PERMANENT MEASURES TO CONTROL WATER POLLUTION AND SOIL EROSION AS MAY BE REQUIRED, DURING THE CONSTRUCTION OF THE PROJECT.

IN GENERAL, ALL CONSTRUCTION ACTIVITIES SHALL PROCEED IN SUCH A MANNER SO AS NOT TO POLLUTE ANY WETLANDS, WATERCOURSE, WATERBODY, AND CONDUIT CARRYING WATER, ETC. THE CONTRACTOR SHALL LIMIT, INSOFAR AS POSSIBLE, THE SURFACE AREA OF EARTH MATERIALS EXPOSED BY CONSTRUCTION METHODS, AND IMMEDIATELY PROVIDE PERMANENT AND TEMPORARY POLLUTION CONTROL MEASURES TO PREVENT CONTAMINATION OF ADJACENT WETLANDS, WATERCOURSES AND WATERBODIES, AND TO PREVENT, INSOFAR AS POSSIBLE, EROSION ON THE SITE.

CONSTRUCTION METHODS, IN GENERAL, SHALL BE IN ACCORDANCE WITH THE PROVISIONS SET FORTH IN THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE STATE OF CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION AND TOWN OF

LAND GRADING

GENERAL:

THE RESHAPING OF THE GROUND SURFACE BY EXCAVATION AND FILLING OR A COMBINATION OF BOTH, TO OBTAIN PLANNED GRADES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING BASIC CRITERIA:

- A) NO FILL SHOULD BE PLACED WHERE IT WILL SLIDE, OR WASH UPON THE PREMISES OF ANOTHER OWNER OR UPON ADJACENT WETLANDS, WATERCOURSE OR WATERBODY.
- B) INSTALLATION OF SEDIMENT AND EROSION CONTROLS SUCH AS HAY BALES AND SILT FENCES SHALL BE ESTABLISHED PRIOR TO COMMENCING LAND DISTURBANCE ACTIVITIES. ALL SEDIMENT AND EROSION CONTROL STRUCTURES MUST BE MONITORED AND MAINTAINED

BY THE CONTRACTOR UNTIL THE SOIL SURFACE IS STABILIZED.

- C) HAY BALES SHALL BE STAKED AND SILT FENCES SHALL BE PROPERLY SECURED. SEDIMENT WILL BE REMOVED FROM ALL CATCHMENTS AS NECESSARY.
- D) PRIOR TO ANY REGRADING, STONE APRON SHALL BE PLACED BY THE ENTRANCE TO THE WORK AREA IN ORDER TO REDUCE MUD AND OTHER SEDIMENTS FROM LEAVING THE SITE. EXCAVATIONS SHOULD NOT BE MADE SO CLOSE TO PROPERTY LINES AS TO ENDANGER ADJOINING PROPERTY WITHOUT PROTECTING SUCH PROPERTY FROM EROSION, SLIDING, SETTLING OR CRACKING.

<u>TOPSOILING</u>

- 1. TOPSOIL SHALL BE SPREAD OVER ALL EXPOSED AREAS IN ORDER TO PROVIDE A SOIL MEDIUM HAVING FAVORABLE CHARACTERISTICS FOR THE ESTABLISHMENT, GROWTH AND MAINTENANCE OF VEGETATION.
- 2. REMOVE ALL LARGE STONES, TREE LIMBS, ROOTS, AND CONSTRUCTION DEBRIS.
- 3. APPLY LIME ACCORDING TO SOIL TEST OR AT THE RATE OF TWO (2) TONS PER ACRE.
- 1. TOPSOIL SHOULD HAVE PHYSICAL, CHEMICAL AND BIOLOGICAL CHARACTERISTICS FAVORABLE TO THE GROWTH OF PLANTS.
- 2. TOPSOIL SHOULD HAVE A SANDY OR LOAMY TEXTURE.
- 3. AN ORGANIC MATTER CONTENT OF OVER TWO (2%) PERCENT IS HIGHLY DESIRABLE. AVOID LIGHT COLORED LOWER SUBSOIL MATERIAL.
- 1. AVOID SPREADING WHEN TOPSOIL IS WET OR FROZEN. 2. SPREAD TOPSOIL UNIFORMLY TO A DEPTH OF AT LEAST FOUR (6") INCHES.

EROSION CHECKS

TEMPORARY PERVIOUS BARRIERS USING BALES OF HAY OR STRAW, HELD IN PLACE WITH STAKES DRIVEN THROUGH THE BALES AND INTO THE GROUND, OR SEDIMENT FILTER FABRIC FASTENED TO A FENCE POST AND BURIED INTO THE GROUND, SHALL BE INSTALLED AND MAINTAINED AS REQUIRED TO CHECK EROSION AND REDUCE SEDIMENTATION.

TEMPORARY AND/OR PERMANENT VEGETATIVE COVER

- PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED AS VARIOUS SECTIONS OF THE PROJECT ARE COMPLETED IN ORDER TO STABILIZE THE SOIL, REDUCE DOWNSTREAM DAMAGE FROM SEDIMENT AND RUNOFF AND TO ENHANCE THE AESTHETIC NATURE OF THE SITE. IT WILL BE APPLIED TO ALL CONSTRUCTION AREAS SUBJECT TO EROSION WHERE FINAL GRADING HAS BEEN COMPLETED AND A PERMANENT COVER IS NEEDED.
- SITE PREPARATION:
- 1. INSTALL REQUIRED SURFACE WATER CONTROL MEASURES.
- 2. REMOVE LOOSE ROCK, STONE AND CONSTRUCTION DEBRIS FROM AREA.
- 3. PERFORM ALL PLANTING OPERATIONS PARALLEL TO THE CONTOURS OF THE SLOPE. 4. APPLY TOPSOIL AS INDICATED ELSEWHERE HEREIN.
- 5. APPLY FERTILIZER ACCORDING TO SOIL TEST OR:

SUNNY TO PARTIALLY SUNNY SITES

- SPRING SEEDING: WORK DEEPLY IN SOIL, BEFORE SEEDING, 300 LBS OF 10-10-10 FERTILIZER PER ACRE 7 LBS PER 1,000 SQUARE FEET); THEN SIX (6) TO EIGHT (8) WEEKS LATER APPLY ON THE SURFACE AN ADDITIONAL 300 LBS OF 10-10-10 FERTILIZER PER ACRE.


- FALL SEEDING: WORK DEEPLY IN SOIL, BEFORE SEEDING, 600 LBS OF 10-10-10 FERTILIZER PER ACRE (14 LBS PER 1,000 SQUARE FEET). ESTABLISHMENT:

- 1. SMOOTH AND FIRM SEEDBED WITH CULTIPACKER OR OTHER SIMILAR EQUIPMENT PRIOR TO SEEDING (EXCEPT WHEN HYDROSEEDING).
- 2. SELECT ADAPTED SEED MIXTURE AS FOLLOWS. NOTE RATES AND THE SEEDING DATES. LBS./ACRE LBS./1000 S.F.


KENTUCKY BLUEGRASS CREEPING RED FESCUE PERENNIAL RYEGRASS

0.10 ____

- TOTAL 3. FINAL SEEDING SHALL TAKE PLACE PRIOR TO OCTOBER 1ST AS SEEDING AFTER THIS DATE RUNS A DISTINCT CHANCE OF FAILURE DUE TO ADVERSE WEATHER. ANY AREAS THAT ARE DISTURBED BETWEEN OCTOBER 1ST AND APRIL 1ST SHALL BE STABILIZED BY NON-VEGETATIVE MEANS SUCH AS HEAVY MULCHING WITH A BINDER OR JUTE MATTING WHICH WILL HAVE TO BE REMOVED BEFORE FINAL SEEDING AND THEN REPLACED AFTER
- 4. APPLY SEED UNIFORMLY ACCORDING TO RATE INDICATED, BY BROADCASTING, DRILLING,
- OR HYDRAULIC APPLICATION. 5. COVER GRASS AND LEGUME SEEDS WITH NOT MORE THAN 1/4 INCH OF SOIL WITH SUITABLE EQUIPMENT (EXCEPT WHEN HYDROSEEDING).
- 6. MULCH IMMEDIATELY AFTER SEEDING, IF REQUIRED, ACCORDING TO THE GUIDELINES.
- 7. USE PROPER INOCULANT ON ALL LEGUME SEEDINGS, USE FOUR (4) TIMES NORMAL RATE WHEN HYDROSEEDING.



Silt Sack - Type B






CATCH BASIN SILT SACK DETAIL NOT TO SCALE

ENDS ANCHORED **EDGES OVERLAPPED** STAPLES ATTACHED PER MANUFACTURE RECOMMENDATION **ENDS ANCHORED** IN TRENCH

List of Common Placement/Installation Mistakes to Avoid


- Ensure the ends are properly secured.
- Install a sufficient number of staples to hold the blanket in place.
- Overlap the blanket to ensure water that flows on top of the blanket and is unable to flow under the blanket.

EROSION CONTROL BLANKET DETAIL NOT TO SCALE



SOIL NAILING DETAIL - DURING EXCAVATION

NOT TO SCALE NOTE: SOIL NAILING PROCEDURES TO BE OVERSEEN BY WELTI GEOTECHNICAL, P.C.



BUILDING WALL

SOIL NAILING DETAIL - BUILDING WALL INSTALLATION / BACKFILL

NOT TO SCALE NOTE: SOIL NAILING PROCEDURES TO BE OVERSEEN BY WELTI GEOTECHNICAL, P.C.

MANCHESTER/HEBRON AVE LLC PROJECT/APPLICANT 1199 MANCHESTER RD. GLASTONBURY, CONN. PROJECT ADDRESS TPZ CHAIRMAN DATE APPROVED DIRECTOR OF COMMUNITY DEVELOPMENT FILE NO.

DATE: 11-08-21 SHOWN CALE: SP-13 SHEET MAP NO. 21-002-1CA

NOTES

WORTH (
VGINEERS

WEST TOWN ST