

**TOWN OF GLASTONBURY
BID NO. GL-2010-50 REBID
EARLE PARK FOOTBRIDGE REPLACEMENT**

**ADDENDUM NO. 1
JUNE 4, 2010**

The attention of bidders submitting proposals for the above-referenced project is called to the following Addendum to the specifications. The items set forth herein, whether of omission, addition, substitution or other change, are all to be included in and form a part of the proposed Contract Documents for the work. Bidders shall acknowledge this Addendum in the Bid Proposal by inserting its number on Page BP-1.

Make the following modifications to the Contract Documents:

ITEM 1: SECTION 500.0 HANDLING WATER:

Replace the first paragraph of section 500.2 Construction Methods with the following:

“The Contractor shall investigate and verify existing stream conditions, and evaluate the need for, and the type of protection and facilities required. All facilities shall be in accordance with the local Inland Wetlands Permit, Army Corps of Engineers permit, Department of Environmental Protection Water Quality Certification, and any other applicable permits. Before commencing construction, the Contractor shall furnish the Engineer with details of the plan and the methods he proposes to use for handling water and accomplishing the work. If temporary cofferdams placed in the watercourse are required based on the Contractor’s proposed work methods, they shall be capable of conveying the required temporary design discharge of 4.7 cubic feet per second without overtopping. The Engineer will review the Contractor’s proposed water handling plan for consistency with this requirement. The furnishing of such plans and methods shall not relieve the Contractor of any of his responsibility for the safety of the work, effectiveness of the temporary protective structures and temporary dewatering facilities, and for the successful completion of the project.”

QUESTIONS AND ANSWERS

- Q1-1: Construction note number 4 on sheet 1 of 2 of the site plans describes the need for the contractor to remove all loose brush and timber from the area of the abandoned beaver dam. Please clarify the work involved.
- A1-1: The Contractor will not be required to perform this task. This work will be performed by the Town in the future.
- Q2-1: What materials can be disposed of at the Town’s Bulky Waste facility?
- A2-1: Brush, stumps, and excess excavated earth materials from this project can be disposed at the Town Bulky Waste facility at no cost to the contractor.

Q3-1: Is a Town building permit required for this project?
A3-1: No, a Town building permit is not required.

**Please confirm receipt of this addendum via fax by 6/7/2010 by 10:00 A.M. to
Kathy Hughey @ (860) 652-7590 (fax)**

Company Name: _____

Name of Person Responding: _____

Authorized Signature: _____

Title: _____

Date: _____

END OF ADDENDUM NO. 1