## TOWN OF GLASTONBURY ENGINEERING DEPARTMENT PROPOSED STORM DRAINAGE IMPROVEMENTS PW-9278

located at

# TRYON STREET & DUG ROAD GLASTONBURY, CONNECTICUT


## SHEET INDEX

SHEET NO.	DESCRIPTION	REV. No.	
1	TITLE SHEET	4	
2	PROPOSED STORM DRAINAGE IMPROVEMENTS PLAN & PROFILE — PHASE 1 TRYON STREET OUTFALL	2	
3	PROPOSED STORM DRAINAGE IMPROVEMENTS PLAN & PROFILE — PHASE 2 TRYON STREET OUTFALL	3	
4	EROSION & SEDIMENTATION CONTROL NOTES PHASE 1 & 2 TRYON STREET OUTFALL	3	
5,6	CONSTRUCTION DETAILS PHASE 1 & 2 TRYON STREET OUTFALL	3	
7,8	PROPOSED STORM DRAINAGE IMPROVEMENTS PLAN & PROFILE — PHASE 3 DUG ROAD SWALE	3	
9-11	PROPOSED STORM DRAINAGE IMPROVEMENTS CROSS SECTIONS — PHASE 3 DUG ROAD SWALE	2	NOT IN CONTRACT
12	DETAILS AND SPECIFICATIONS	3	CONTINACT

APPROVED RECOMMENDATION TO THE TOWN PLAN & ZONING COMMISSION

MOVED, that the Conservation Commission recommends to the Town Plan and Zoning Commission approval of a Section 4.11 (Flood Zone) Special Permit for the Town of Glustonbury's proposed storm drainage improvements along sections of Dug Road and leading westerly across Tryon Street and over land to the Connecticut River, in accordance with plans on file in the Office of Community Development, and in compliance with the following conditions

- 1. The plans for this project shall be revised to the satisfaction of the Environmental Planner to indicate: the locations and design details for water stops or anti-scepage collars within the backfilled trench between the river and upgradient wetlands; a specified seed mix containing native wetland plants, along with seeding rates and seedbed preparation and planting information; and the submitted maintenance plan for stormwater facilities.
- 2. Installation of soil crosion and sedimentation control and stabilization measures shall be the Permittee's responsibility. Once installed these measures shall then be inspected by the Environmental Planner prior to land disturbance activities. Afterwards it then shall be the Permittee's responsibility to inspect these control measures during, and immediately following, substantial storm events and maintain and/or replace the control measures, when needed, on a regular basis until the site is vegetatively stabilized. Hay bales shall be replaced every 60 days. The Environmental Planner is hereby authorized to require additional soil erosion and sediment controls and stabilization measures to address situations that arise on the site.
- 3. In the event of a forecasted flood of the Connecticut River or a forecasted heavy rain within the Dug Road watershed, contingency measures shall be undertaken, under consultation with the Environmental Planner, in order to cease prescribed construction operations and to temporarily stabilize critical areas.
- 4. Upon completion of the project, certification from the Town Engineer shall be required approved design, and that no available flood storage was lost within the 100-year Flood Zone. Such certification shall be provided to the Office of Community Development.



LOCATION MAP SCALE: 1"=1000' DECEMBER 2013 ISSUED FOR PHASE 1 CONSTRUCTION 3 OF 12 ADDED TEST PIT LOCATION/DATA 1/4/2013 ADD SED. STRUCTURE AT DUG RD & FILTER BERM AT OUTFALL #1 9/30/2013"

RICHARD J. JOHNSON TOWN MANAGER

DANIEL A. PENNINGTON TOWN ENGINEER/MANAGER OF PHYSICAL SERVICES

Town of Glastonbury 2155 MAIN STREET · P.O. BOX 6523 · GLASTONBURY, CONNECTICUT 06033-653

TOWN PLAN AND ZONING COMMISSION

SECTION 4.11 FLOOD ZONE SPECIAL PERMIT OWNER: RICHARD J JOHNSON TOWN OF GLASTONBURY 2155 MAIN STREET

> POST OFFICE BOX 6523 INTERSECTION OF TRYON

MOVED, that the Town Plan and Zoning Commission approve the application of the Town of Glastonbury for a Section 4.11 Special Permit (Flood Zone) for a new drainage system intersection of Tryon Street & Dug Road extending to a new outlet at rear of 306 Tryon Street -Rural Residence Zone & Flood Zone, in accordance with the following plans:

"TITLE SHEET FOR STORM DRAINAGE IMPROVEMENTS PHASE 1, 2 & 3 LOCATED AT TRYON STREET & DUG ROAD GLASTONBURY CONNECTICUT TOWN OF GLASTONBURY ENGINEERING SCALE: AS SHOWN DRAWN BY: C.F.S. 8/15/2012 CHECKED BY: S.M.B. 8/15/2012 APPROVED BY: D.A.P. 8/15/2012 SHEET NO. 1 OF 12 OLISP SUBMISSION - REVISIONS 10/30/2012 DEEP IWRD/COMMENTS - REVISIONS 1/4/2013 ADD SED. STRUCTURE AT DUG RD. & FILTER BERM AT OUTFALL #1 &

"PLAN & PROFILE DEPICTING PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 1 LOCATED BEHIND 306 TRYON STREET GLASTONBURY, CONNECTICUT TOWN OF GLASTONBURY ENGINEERING SCALE: AS SHOWN DRAWN BY: C.F.S. 8/15/2012 CHECKED BY: S.M.B. 8/15/2012 APPROVED BY: D.A.P. 8/15/2012 SHEET NO. 2 OF 12 ADJUSTED FLARED END G3 LOCATION/GRADING 10/30/2012" "PLAN & PROFILE DEPICTING PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 2 LOCATED AT 302 & 306 TRYON STREET GLASTONBURY, CONNECTICUT TOWN OF GLASTONBURY ENGINEERING SCALE: AS SHOWN DRAWN BY: C.F.S. 8/15/2012 CHECKED BY: S.M.B . 8/15/2012 APPROVED BY: D.A.P. 8/15/2012 SHEET NO.

EROSION CONTROL NOTES FOR PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 1 & 2 LOCATED AT 302 & 306 TRYON STREET GLASTONBURY. CONNECTICUT SCALE: AS SHOWN DRAWN BY: C.F.S. 8/15/2012 CHECKED BY: S.M.B. 8/15/2012 APPROVED BY: D.A.P. 8/15/2012 SHEET NO. 4 OF 12 ADD GRADING/ PLANTING PLAN 10/30/2012 ADD EROSION CONTROL MAT DETAIL 1/4/2013"

CONSTRUCTION DETAILS FOR PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 1 & 2 LOCATED AT 302 & 306 TRYON STREET GLASTONBURY, CONNECTICUT TOWN OF GLASTONBURY ENGINEERING SCALE: AS SHOWN DRAWN BY: C.F.S. 8/15/2012 CHECKED BY: S.M.B. 8/15/2012 APPROVED BY: D.A.I 8/15/2012 SHEET NO. 5 OF 12 MOD. SCOUR HOLE ADD SED. STRUCT. JUNCTION

"CONSTRUCTION DETAILS FOR PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 1 & 2 LOCATED AT 302 & 306 TRYON STREET GLASTONBURY, CONNECTICUT TOWN OF GLASTONBURY ENGINEERING SCALE: AS SHOWN DRAWN BY: C.F.S. 11/26/2012 CHECKED BY: S.M.B. 11/26/2012 APPROVED BY: D.A.P 11/26/2012 SHEET NO. 6 OF 12 ADDED INFILTRATOR DETAILS "SHEET 6" 1/4/2013 ADD SED. & DIVERSION STRUCTURE DETAILS 9/30/2013"

"PLAN & PROFILE DEPICTING PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 3 LOCATED ON DUG ROAD GLASTONBURY, CONNECTICUT TOWN OF GLASTONBURY ENGINEERING SCALE: AS SHOWN DRAWN BY: S. TROY 8/15/2012 CHECKED BY: S.M.B. 8/15/2012 APPROVED BY: D.A.P. 8/15/2012 SHEET NO. 7 OF 12 REV. SHEET NUMBER 1-4-2013"

"PLAN & PROFILE DEPICTING PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 3 LOCATED ON DUG ROAD GLASTONBURY, CONNECTICUT TOWN OF GLASTONBURY ENGINEERING SCALE: AS SHOWN DRAWN BY: S. TROY 8/15/2012 CHECKED BY: S.M.B. 8/15/2012 APPROVED BY: D.A.P. 8/15/2012 SHEET NO. 8 OF 12 REV. SHEET NUMBER, TP-DATA, BASIN DETAILS 1-4-2013 ADD DRIVEWAY CULVERT FOR LOT N7 9-30-2013"

"CONSTRUCTION DETAILS DEPICTING PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 3 LOCATED ON DUG ROAD GLASTONBURY, CONNECTICUT TOWN OF GLASTONBURY ENGINEERING SCALE: AS SHOWN DRAWN BY: S. TROY 8/15/2012 CHECKED BY: S.M.B. 8/15/2012 APPROVED BY: D.A.P. 8/15/2012 SHEET NO. 12 OF 12 REV. SHEET NUMBER, ADD DRYWELL, SPILLWAY DETAILS 1-4-2013 ADDED OUTLET STRUCTURE D-1 FOR DRIVEWAY CULVERT 9-

Page 2 of 2

and in compliance with the following: 1. Compliance with conditions as recommended by the Conservation Commission during its meeting of October 24, 2013.

APPROVED: TOWN PLAN AND ZONING COMMISSION NOVEMBER 19, 2013

Peter R. Carey, Building Official

LOCATIONS PRIOR TO CONSTRUCTION.

MEMORANDUM

Date: October 28, 2013

To: Town Plan & Zoning Commission

attached motion was approved by the Commission

From: John Rook, AICP, Planner

ALL UTILITY INFORMATION AND DATA SHOWN OR INDICATED IN THE CONTRACT DOCUMENTS ARE COMPLIED FROM MAPS AND DATA FURNISHED B OTHERS, ANY SUCH INFORMATION SHOULD NOT BE CONSTRUED AS ACCURATE OR COMPLETE AND THE CONTRACTOR SHALL VERIFY ALL

Recommendations to the Town Plan and Zoning Commission concerning a Section 4.11 (Flood

Zone) Special Permit – proposed Storm Drainage System from Dug Road and Tyron Street to the Connecticut River with new outfall (across properties of #302, 306 and ussessor's lot W-20

During its Regular Meeting of October 24, 2013, the Conservation Commission recommended to the

Town Plan and Zoning Commission approval of a Section 4.11 (flood zone) Special Permit for the

proposed Storm Drainage System from Dug Road and Tyron Street to the Connecticut River. The

Tryon Street) - Stephen Braun, Assistant Town Engineer

MANUAL REVISIONS TO THIS DOCUMENT ARE PROHIBITED ALL REVISIONS MUST BE PERFORMED ON CADD FILE:

 $H: \DWG\Streets\Tryon\ St\PW-9278\ Tryon\ St-Dug\ Rd\ Drainage\Tryon\ St\ -\ Dug\ Rd\ Drainage-2013-DUG-REV2.dwg$ 




ATE SPECIAL PERMIT APP'D DIRECTOR OF COMMUNITY DEVELOPMENT FILE NO. Certified to be substantially correct


DANIEL A. PENNINGTON P.E. Reg. No. 20101


	4.	ISSUED FOR CONSTRUCTION	12/10/2013
	3.	ADD SED. STRUCTURE AT DUG RD & FILTER BERM AT OUTFALL #1 & DETAILS FOR NEW STRUCTURES	9/30/2013
 	2.	DEEP IWRD/COMMENTS - REVISIONS	1/4/2013
	1.	OLISP SUBMISSION - REVISIONS	10/30/2012
PW-9278	NO.	DESCRIPTION	DATE

DRAWING ISSUE STATUS



CALE: AS SHOWN	DATE:			
RAWN BY: C.F.S.	8/15/2012			
HECKED BY: S.M.B. 8/15/2012				
PPROVED BY: D.A.P.	8/15/2012			
T. FILE:				
O NOT SCALE THIS DRAWING. USE THE				






TITLE SHEET STORM DRAINAGE IMPROVEMENTS PHASE 1, 2 & 3

located at TRYON STREET & DUG ROAD GLASTONBURY, CONNECTICUT OF <u>12</u>

SHEET NO



CONNECTICUT RIVER 100 YEAR FLOOD ELEV. = 26.3CONNECTICUT RIVER 10 YEAR FLOOD PHASE "2" CONSTRUCTION ELEV. = 20.0 BY OTHERS PHASE "1" CONSTRUCTION INSTALL CONCRETE ANTI-SEEP
COLLAR SEE DETAIL FES BK9 & BK10 DRAINAGE -MANHOLE G2 OUTLET STRUCTURE G1 OF SWALE PROPOSED STONE -FILTER BERM FLARED END G3-H T L ELEV.= 5.99 36" RCP Ø 0.5% 36" RCP @ 0.5% PROPOSED RIPRAP SCOUR HOLE DATUM ELEVO 0.00 MLW ELEV.= -0.48 17+50 15 + 5015 + 0019+00 18+50 18+00 17 + 0016+50 16+00 24+80 24+50 24+00 23 + 5023+00 22+50 22+00 21+50 21+00 20+50 20+00 19+50

TOWN OF GLASTONBURY RURAL RESIDENCE & FLOOD ZONE
PROJECT/APPLICANT ZONE #302. #306 & LOT W-20 TRYON STREET PROJECT ADDRESS TPZ CHAIRPERSON DATE SPECIAL PERMIT APP'D DIRECTOR OF COMMUNITY DEVELOPMENT FILE NO.

ELEVATIONS AND VERTICAL CONTROL IS BASED ON THE NORTH AMERICAN VERTICAL

WETLAND DATA DEPICTED HEREON WAS FLAGGED ON 8/15/2011 BY R. RICHARD SNARSKI REGISTERED SOIL SCIENTIST AND FIELD SURVEY CONDUCTED 8/19/2011.

THIS PLAN WAS COMPILED FROM OTHER MAPS, RECORD RESEARCH OR OTHER SOURCES OF INFORMATION. IT IS NOT TO BE CONSTRUED AS HAVING BEEN

OBTAINED AS THE RESULT OF A FIELD SURVEY, AND IS SUBJECT TO SUCH CHANGE

REPRODUCTIONS OF THIS PLAN ARE INVALID IF THEY DO NOT BEAR THE IMPRESSION

SEAL OF THE UNDERSIGNED LAND SURVEYOR AND/OR PROFESSIONAL ENGINEER.

REFERENCE FOR FLOOD WAY AND FLOOD ZONES IS MADE TO FLOOD INSURANCE

SECURITY EFFECTIVE DATE: SEPTEMBER 26, 2008 FEDERAL EMERGENCY

Wetlands delineated per requirements of CT Tidal Wetlands and Inland Wetlands Acts.

Date

RATE MAP ENTITLED: "NATIONAL FLOOD INSURANCE PROGRAM PANEL 0536F FIRM FLOOD INSURANCE RATE MAP HARTFORD COUNTY, CONNECTICUT (ALL JURISDICTIONS) PANEL 536 OF 675 MAP NUMBER 09003C0536F U.S. DEPARTMENT OF HOMELAND

ALL UTILITY INFORMATION AND DATA SHOWN OR INDICATED IN THE CONTRACT DOCUMENTS ARE COMPLIED FROM MAPS AND DATA FURNISHED BY OTHERS, ANY SUCH INFORMATION SHOULD NOT BE CONSTRUED AS ACCURATE OR COMPLETE AND THE CONTRACTOR SHALL VERIFY ALL LOCATIONS PRIOR TO CONSTRUCTION.

DATUM 1988 - (NAVD88).

MANAGEMENT AGENCY"

AS AN ACCURATE FIELD SURVEY MAY DISCLOSE.

Richard Snarski

Soil Scientist

MANUAL REVISIONS TO THIS DOCUMENT ARE PROHIBITED.

ALL REVISIONS MUST BE PERFORMED ON CADD FILE:

H: \DWG\Streets\Tryon St\PW-9278 Tryon St-Dug Rd Drainage\Tryon St - Dug Rd Drainage-2013-DUG-REV2.dwg

PROPILE

SCALE: 1'' = 50' HORZ.

SCALE: 1'' = 5' VERT.

( IN FEET 1 inch = 50 ft.IF SCALING FROM THIS PLAN, VERIFY SCALE WITH THE GRAPHIC SCALE PROVIDED ABOVE.

GRAPHIC SCALE

ISSUED FOR CONSTRUCTION 12/10/201 ADJUSTED FLARED END G3 LOCATION/GRADING 10/30/201 PW-9278 NO. DESCRIPTION DATE

Certified to be substantially correct

DANIEL A. PENNINGTON P.E. Reg. No. 20101

DRAWING ISSUE STATUS

TOWN OF GLASTONBURY, ENGINEERING OFFICE.

SCALE: AS SHOWN DATE: 8/15/2012 CHECKED BY: S.M.B. 8/15/2012 APPROVED BY: D.A.P. 8/15/2012 ST. FILE: DO NOT SCALE THIS DRAWING. USE THE DIMENSIONS GIVEN. IF THERE ARE ANY DISCREPANCIES OR QUESTIONS, CONTACT THE

GRID NORTH

INV. IN: 7.00 36" CPEP

CONSTRUCTION NOTES:

FOR THE STRUCTURE.

PLAN & PROFILE DEPICTING PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 1 located Behind

306 TRYON STREET GLASTONBURY, CONNECTICUT

SHEET NO

DRAINAGE

INV. IN: INV. OUT:

DRAINAGE JUNCTION CHAMBER BK8

STA.: 14+00 OFF: 0.0

INV. IN: 7.47 48" CPEP


INV. OUT: 7.47 36" CPEP

INV. OUT: 7.47 36" CPEP

T.F.: 16.73

ALL DISTURBED FEDERAL WETLAND AREAS TO BE RESTORED WITH AN APPROVED WETLAND SEED MIX.
 LIMITS OF CLEARING SHALL BE FLAGGED IN THE FIELD BY THE CONTRACTOR FOR REVIEW AND APPROVAL BY THE ENGINEER, IN PHASE 1 AREA CONTRACTOR SHALL

DISPOSE OF BRUSH, AND STOCKPILE FIREWOOD FOR USE BY PROPERTY OWNER. 3. ALL PRECAST CONCRETE STRUCTURES SHALL BE SET ON A 6" THICK BASE OF 3/4" CRUSHED STONE, WHICH SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE



PLACEMENT AND CONSTRUCTION OF A SYNTHETIC FILTER BARRIER

24+23

PROPOSED GRADING/PLANTING PLAN

PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP'8), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.

2. BEGIN AT THE TOP OF THE CHANNEL BY ANCHORING THE RECP'S IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH WITH APPROXIMATELY 12" (30 CM) OF RECP'S EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP'S WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMAPCT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF RECP'S BACK OVER SEED AND COMPACTED SOIL. SECURE RECP'S OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) ACROSS THE WIDTH OF THE RECP'S.

. ROLL CENTER RECP'S IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL. RECP'S WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECP'S MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.

. PLACE CONSECUTIVE RECP'S END OVER END (SHINGLE STYLE) WITH A 4" - 8" (10 CM -15 CM) OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10 CM) APART AND 4" (10 CM) ON CENTER TO SECURE RECP'S.

FULL LENGTH EDGE OF RECP'S AT TOP OF SIDE SLOPES MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

7. IN HIGH FLOW CHANNEL APPLICATIONS, A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT (9 M — 12 M) INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10 CM) APART AND 4" (10 CM) ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL.

NOTE;
\* IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE NECESSARY TO PROPERLY ANCHOR THE RECP'S.

B. THE TERMINAL END OF THE RECP'S MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

TYPE 'H' EROSION CONTROL MAT

INSTALLATION DETAIL

. ADJACENT RECP'S MUST BE OVERLAPPED APPROXIMATELY 2" - 5" (5 CM -12.5 CM) (DEPENDING ON RECP'S TYPE) AND STAPLED.

CHANNEL INSTALLATION

PROPOSED SILT FENCE —

<u>Common Name</u> <u>Height</u>

Red-Osler Dogwood 3'-4

American Cranberry 3'-4

PLANTING LEGEND

Symbol Botanical Name

Cornus Sericea

Viburnum Trilobum

AMERICAN

GREEN

EROSION CONTROL Products


Guaranteed SOLUTIONS

14649 HIGHWAY 41 NORTH

EVANSVILLE, IN 47725

800-772-2040

www.nagreen.com



NOT TO SCALE

(30 CM)


(10 CM)

CM - 12.5 CM)

<del>--</del>|2"-5"|<del>--</del>

4"-6" (10 CM - 15 C

1. SET POSTS AND EXCAVATE 2. ATTACH FILTER FABRIC FENCING A 6"X6" TRENCH. TO POST AND EXTEND IT TO THE SET POST DOWNSLOPE. TRENCH BOTTOM.



BACKFILL THE TRENCH AND COMPACT THE EXCAVATED SOIL.

## PLACEMENT & CONSTRUCTION OF SYNTHETIC FILTER BARRIER

FILTER FABRIC-



2155 MAIN STREET · P.O. BOX 6523 · GLASTONBURY, CONNECTICUT 06033-6523

October 28, 2013

CONSERVATION COMMISSION AND INLAND WETLANDS & WATERCOURSES AGENCY

Stephen M. Braun, P.E., Assistant Town Engineer Town of Glastonbury 2155 Main Street Glastonbury, Connecticut 0603.

Re: Application of Town of Glastonbury (Engineering Division) for an inland wetlands and watercourses permit - proposed Storm Drainage System from Dug Road and Tyron Street to the Connecticut River with new outfall (across properties of #302, 306 and assessor's lot W-20 Tryon Street)

At its Regular Meeting of October 24, 2013, the Conservation Commission/Inland Wetlands & Watercourses Agency approved an Inland Wetlands and Watercourses Permit, in accordance with the plans and conditions cited in the attached

Please read the conditions of approval carefully and comply with them. Some of the conditions may require interacting with the Environmental Planner (e.g. inspection of soil erosion and sediment control); it will be your responsibility to schedule such interactions. Any questions you may have about the stated conditions can be directed to the Office of Community Development at (860) 652-7511.

This Permit:

requires that the approved regulated activities be completed within one (1) year from commencement of said activities. is valid for five (5) years and thus expires on October 24, 2018; and may not be transferred unless authorized by the Inland Wetlands & Watercourses Agency

This Permit may be revoked if you exceed the conditions or limitations of this Permit or have secured this Permit through

Once again should you have any questions, please do not hesitate to contact this office.



## APPROVED MOTION FOR A WETLANDS PERMIT

MOVED, that the Inland Wetlands and Watercourses Agency issues and inland wetlands and watercourses permit to the Town of Glastonbury for the construction and maintenance of a stormwater drainage system and related improvements along Dug Road and Tryon Street and running cross-country on private lands to the Connecticut River, in accordance with plans on file in the Office of Community Development, and compliance with the following conditions:

- 1. The plans for this project shall be revised to the satisfaction of the Environmental Planner to indicate: the locations and design details for water stops or anti-seepage collars within the backfilled trench between the river and upgradient wetlands; a specified seed mix containing native wetland plants, along with seeding rates and seedbed preparation and planting information; and the submitted maintenance plan for stormwater facilities.
- 2. Installation of soil erosion and sedimentation control and stabilization measures shall be the Permittee's responsibility. Once installed these measures shall then be inspected by the Environmental Planner prior to land disturbance activities. Afterwards it then shall be the Permittee's responsibility to inspect these control measures during, and immediately following, substantial storm events and maintain and/or replace the control measures, when needed, on a regular basis until the site is vegetatively stabilized. Hay bales shall be replaced every 60 days. The Environmental Planner is hereby authorized to require additional soil crosion and sediment controls and stabilization measures to address situations that arise on the site.
- 3. Topsoil stockpile areas shall not be permitted within the regulated area.
- 4. In the event of a forecasted flood of the Connecticut River or a forecasted heavy rain within the Dug Road watershed, contingency measures shall be undertaken, under consultation with the Environmental Planner, in order to cease prescribed construction operations and to temporarily stabilize critical areas.
- 5. The Permittee shall be fully responsible for damages caused by all activities undertaken pursuant to this permit that may have a detrimental effect on wetlands and/or watercourses, and all such activities that cause erosion and sedimentation problems.

PROJECT NARRATIVE:

THE PROPOSED PROJECT INCLUDES THE CONSTRUCTION OF CATCH BASINS AT THE INTERSECTION OF TRYON STREET AND DUG ROAD AND THE INSTALLATION OF A 1,650 FOOT-LONG, 48-INCH DIAMETER STORM DRAINAGE DISCHARGE PIPE ALONG THE NORTH SIDE OF THE PROPERTIES LOCATED AT #302 AND #306 TRYON STREET TO A DISCHARGE AT THE LOW-LYING WETLAND AREA AT THE WESTERN LIMIT OF THE #306 PARCEL (OUTFALL #1). A SECOND 550 FOOT-LONG, 36-INCH DIAMETER STORM DRAINAGE PIPE WILL EXTEND FROM THE WEST SIDE OF THE LOW-LYING WETLAND ACROSS LOT W-20 TRYON STREET TO A NEW DISCHARGE AT THE CONNECTICUT RIVER (OUTFALL #2). THIS PIPE WILL SERVE AS AN OVERFLOW FOR THE WETLAND TO MINIMIZE INUNDATION OF ADJACENT AGRICULTURAL FIELDS BY STORMWATER FROM DUG ROAD DURING PERIODS WHEN THE RIVER IS NOT AT FLOOD STAGE. ALSO INCLUDED IN THE PROJECT ARE IMPROVEMENTS TO A DRAINAGE CHANNEL ALONG THE NORTH SIDE OF DUG ROAD TO PROVIDE FOR INFILTRATION AND A STABLE CHANNEL LINING.

#### **CONSTRUCTION SEQUENCE:**

THIS PROJECT WILL BE CONSTRUCTED IN THREE PHASES. PHASE 1 WILL CONSIST OF CONSTRUCTION OF THE 550 FOOT-LONG 36-INCH DIAMETER STORM PIPE FROM OUTFALL #2 (CT RIVER) TO THE LOW-LYING WETLAND AREA. THIS PHASE OF CONSTRUCTION WILL BE ACCESSED FROM FERRY LANE OVER EXISTING FARM ROADS. PHASE 2 WILL INCLUDE CONSTRUCTION OF THE 1,650 FOOT-LONG 48-INCH DIAMETER STORM DRAIN FROM OUTFALL #1 TO DUG ROAD. THIS PHASE WILL BE ACCESSED FROM TRYON STREET USING A COMBINATION OF EXISTING DRIVEWAYS AND FARM ROADS. PHASE 3 WILL INCLUDE ALL DRAINAGE CHANNEL IMPROVEMENTS ALONG THE NORTH SIDE OF DUG ROAD. THE EROSION AND SEDIMENTATION CONTROL PLAN FOR PHASE 3 WORK IS NOT INCLUDED IN THIS SECTION, BUT RATHER IS DESCRIBED ON SHEET 8 OF THE PLAN SET.

#### FLOOD ZONE CONSIDERATIONS:

ALL OF PHASE 1 AND A PORTION OF PHASE 2 ARE WITHIN THE CONNECTICUT RIVER FLOOD ZONE. AS SUCH, ALL CONSTRUCTION WITHIN THIS AREA WILL NEED TO TAKE PLACE AFTER THE NORMAL SPRING FLOODS HAVE RECEDED AND WITH CLOSE MONITORING OF THE CONNECTICUT RIVER FLOW CONDITIONS AND WEATHER FORECASTS TO PROTECT THE WORK AREA FROM FLOODING. ONLY THAT PORTION OF THE WORK THAT CAN BE COMPLETED AND RESTORED THAT DAY OR PRIOR TO THE NEXT FORECASTED SEVERE WEATHER EVENT SHALL BE INITIATED.

DUE TO THE ELEVATIONS OF THE PIPELINE AT OUTFALL #2, THIS OUTFALL AND A PORTION OF THE DRAINAGE SYSTEM UPSTREAM OF THE OUTFALL IS BELOW THE HIGH TIDE LINE OF THE CONNECTICUT RIVER. THIS WILL REQUIRE THAT WORK AT THE OUTFALL BE PROPERLY SEQUENCED AND STAGED TO OCCUR DURING LOW TIDE AND LOW WATER FLOWS IN THE RIVER. IF CONSTRUCTION OF OUTFALL #2 PROCEEDS AT THE BEGINNING OF PHASE 1, THE OUTFALL PIPE SHALL BE SECURELY PLUGGED TO PREVENT RISING TIDE WATER FROM ENTERING THE REMAINDER OF THE PIPELINE DURING CONSTRUCTION. IF CONDITIONS DO NOT ALLOW FOR CONSTRUCTION OF THE OUTFALL WHEN CONSTRUCTION IS INITIATED, CONSTRUCTION MAY BEGIN WITHIN 30 FEET UPSTREAM OF THE OUTFALL AND PROCEED IN SUCH A MANNER SO AS TO PRESERVE A SOIL BARRIER BETWEEN THE PIPELINE AND THE CONNECTICUT RIVER TO PREVENT INUNDATION OF THE WORK AREA.

#### PROJECT SPECIFIC SEDIMENTATION AND EROSION CONTROL PLAN

CONSTRUCTION ACTIVITIES OF CONCERN RELATIVE TO THE PROTECTION OF ADJACENT WETLANDS AND WATERCOURSES FROM SEDIMENTATION ARE AS FOLLOWS:

- 1. DEWATERING: OPEN TRENCH EXCAVATIONS WILL NEED TO BE DEWATERED AS NECESSARY FOR PROPER INSTALLATION OF THE PROPOSED PIPES. IN THESE AREAS. ALL WATER REMOVED FROM THE TRENCH SHALL BE ADEQUATELY TREATED PRIOR TO DISCHARGE USING MEASURES DESCRIBED IN SECTION 5-13 OF THE 2002 CT GUIDELINES FOR EROSION AND SEDIMENT CONTROL. THIS MAY INCLUDE A STONE SUMP AND STANDPIPE FOR PUMP INTAKE PROTECTION, AND A DIRT BAG OR PUMPING SETTLING BASIN FOR TREATMENT OF THE PUMPED WATER PRIOR TO DISCHARGE.
- 2. STOCKPILING: EXCAVATED MATERIAL SHALL NOT BE STOCKPILED WITHIN WETLAND REGULATED AREAS OR THE CONNECTICUT RIVER FLOOD ZONE TO THE EXTENT PRACTICAL, WHEN IT IS NECESSARY BASED ON THE PROPOSED METHODS OF CONSTRUCTION TO STAGE EXCAVATED MATERIAL FOR SHORT DURATIONS IN THE FLOOD ZONE, THESE MATERIALS SHALL BE ADEQUATELY PROTECTED, AND A PLAN SHALL BE IN PLACE TO REMOVE THE MATERIAL BEFORE THE NEXT SEVERE WEATHER EVENT. LONGER DURATION STOCKPILING OF MATERIAL, WHEN NECESSARY, SHALL BE ONLY IN LOCATIONS APPROVED IN ADVANCE BY THE ENGINEER. ANY SUCH STOCKPILES SHALL BE RINGED WITH A SEDIMENTATION CONTROL SYSTEM.
- 3. DISTURBED AREAS: LIMITS OF DISTURBANCE SHALL BE IN STRICT ACCORDANCE WITH THE APPROVED PLAN. ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH THE FINAL SURFACE TREATMENT AS SOON AS POSSIBLE AFTER CONSTRUCTION ACTIVITIES ARE COMPLETED. DISTURBED AREAS WITH STEEP OR LONG SLOPES AND OTHER AREAS WITH SIGNIFICANT POTENTIAL FOR CAUSING SEDIMENTATION SHALL BE PROTECTED WITH TEMPORARY STRAW MULCH, WOOD CHIPS, EROSION CONTROL MATTING, OR OTHER SUITABLE MATERIALS PRIOR TO SIGNIFICANT FORECASTED RAIN STORM EVENTS TO REDUCE EROSION POTENTIAL.
- 4. TRAVEL AREAS: A STONE CONSTRUCTION ENTRANCE SHALL BE INSTALLED AS REQUIRED TO PREVENT SOIL FROM BEING TRACKED OUT OF THE CONSTRUCTION SITE AND INTO THE ROAD. THIS CONSTRUCTION ENTRANCE SHALL BE MAINTAINED UNTIL ALL DISTURBED AREAS OF THE PROJECT HAVE BEEN RESTORED.
- 5. SEVERE WEATHER CONTINGENCY PLAN: IN ADVANCE OF A SEVERE WEATHER EVENT, ALL EROSION CONTROLS DESCRIBED ABOVE AND ELSEWHERE ON THE PLANS SHALL BE INSPECTED AND ADJUSTED AS NECESSARY. THE 100 YEAR FLOOD ELEVATION FOR THE CONNECTICUT RIVER IN THIS AREA IS 26.3 . CONTRACTOR SHALL MONITOR WEATHER FÖRECASTS AND CONNECTICUT RIVER FLOOD WARNINGS AND ADJUST OPERATIONS ACCORDINGLY. ALL EQUIPMENT AND STOCKPILED MATERIALS SHALL BE REMOVED FROM THE FLOOD ZONE PRIOR TO AN ANTICIPATED FLOOD EVENT AS PROJECTED FLOOD ELEVATIONS REQUIRE. WORK AREAS SHALL BE STABILIZED AS REQUIRED TO PROVIDE A STABLE OVERFLOW PATH FOR FLOOD WATER THROUGH OR AROUND THE WORK AREA.

## RESPONSIBLE PARTIES:

THE CONTRACTOR FOR PHASE 1 OR THE DEPARTMENT OF PHYSICAL SERVICES FOR PHASE 2 & 3 SHALL PROVIDE A REPRESENTATIVE WHO IS RESPONSIBLE FOR IMPLEMENTING THE EROSION AND SEDIMENTATION CONTROL PLAN. THIS INCLUDES THE INSTALLATION AND MAINTENANCE OF ALL CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN.

GENERAL SEDIMENTATION AND EROSION CONTROL REQUIREMENTS

DISTURBED AREAS HAVE BEEN THOROUGHLY STABILIZED

EROSION ON THE SITE.

THESE GUIDELINES SHALL APPLY TO ALL WORK CONSISTING OF ANY AND ALL TEMPORARY AND/OR PERMANENT MEASURES TO CONTROL WATER POLLUTION AND SOIL EROSION AS MAY BE REQUIRED, DURING THE CONSTRUCTION OF THE PROJECT.

IN GENERAL, ALL ACTIVITIES SHALL PROCEED IN SUCH A MANNER SO AS NOT TO POLLUTE ANY WETLANDS, WATERCOURSE, WATERBODY, AND CONDUIT CARRYING WATER, ETC. THE DEPARTMENT OF PHYSICAL SERVICES SHALL LIMIT, INSOFAR AS POSSIBLE, THE SURFACE AREA OF EARTH MATERIALS EXPOSED BY CONSTRUCTION METHODS, AND IMMEDIATELY PROVIDE PERMANENT AND TEMPORARY POLLUTION CONTROL MEASURES TO PREVENT CONTAMINATION OF ADJACENT WETLANDS, WATERCOURSES AND WATERBODIES, AND TO PREVENT, INSOFAR AS POSSIBLE,

CONSTRUCTION METHODS, IN GENERAL, SHALL BE IN ACCORDANCE WITH THE PROVISIONS SET FORTH IN THE "GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" (2002) BY THE STATE OF CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION.

- 1. ALL CONTROL MEASURES SHALL BE INSTALLED AS NOTED ABOVE AND AS SHOWN ON THE
- 2. ALL CONTROL MEASURES SHALL BE INSPECTED AND APPROVED BY THE ENGINEER PRIOR TO

COMMENCEMENT OF ANY WORK, INCLUDING PRE-CONSTRUCTION CLEARING AND GRUBBING.

- ALL CONTROL MEASURES SHALL BE MAINTAINED AND UPGRADED AS REQUIRED TO ACHIEVE PROPER SEDIMENT CONTROL THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL
- 4. NO CONTROL MEASURES SHALL BE REMOVED WITHOUT APPROVAL FROM THE ENGINEER.
- ADDITIONAL CONTROL MEASURES SHALL BE INSTALLED DURING THE CONSTRUCTION PERIOD IF DEEMED NECESSARY BY THE ENGINEER.
- 6. THE LIMITS OF CLEARING, GRADING AND DISTURBANCE, AS SHOWN ON THE PLAN(S), SHALL BE KEPT TO A MINIMUM WITHIN THE APPROVED AREA OF CONSTRUCTION. ALL AREAS OUTSIDE THE LIMITS OF CLEARING SHALL REMAIN TOTALLY INDISTURBED.
- ANY CONTROL MEASURES RETAINING SEDIMENT OVER 1/2 THEIR HEIGHT SHALL HAVE THE SEDIMENT IMMEDIATELY REMOVED, AND ALL DAMAGED CONTROL MEASURES SHALL BE REMOVED AND REPLACED.
- ALL NEW AND EXISTING CATCH BASINS LOCATED WITHIN THE PROJECT LIMITS SHALL BE PROTECTED WITH A SEDIMENTATION CONTROL SYSTEM IN GRASSED AREAS OR WITH A SEDIMENTATION CONTROL SACK IN PAVED AREAS UNTIL ALL DISTURBED AREAS HAVE BEEN THOROUGHLY STABILIZED.
- SEDIMENT REMOVED FROM CONTROL MEASURES AND DRAINAGE FACILITIES SHALL BE DISPOSED OF IN A MANNER THAT IS CONSISTENT WITH STATE AND LOCAL REGULATIONS.
- 10. THE PLANTING SEASONS FOR THE SPECIFIED SEED MIXTURE SHALL BE AS DEFINED IN THE 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL. UNLESS DIRECTED OTHERWISE BY THE TOWN ENVIROMENTAL PLANNER. OUTSIDE OF THESE SPECIFIED DATES, AREAS WILL BE STABILIZED WITH HAYBALE CHECK DAMS, FILTER FABRIC, OR WOODCHIP MULCH AS REQUIRED TO CONTROL EROSION.

## PROPOSED MAINTENANCE PLAN FOR STORMWATER FACILITIES;

THE TOWN OF GLASTONBURY HIGHWAY DEPARTMENT WILL BE RESPONSIBLE FOR MAINTENANCE OF THE PROPOSED STORM DRAINAGE SYSTEM, INCLUDING PIPING, CATCH BASINS, INFILTRATION CHAMBERS, OFFLINE PARTICLE SEPARATOR, INFILTRATION SWALE AND BASIN, AND ALL OTHER COMPONENTS OF THE DRAINAGE SYSTEM. THE TOWN CURRENTLY MAINTAINS SIMILAR FACILITIES THROUGHOUT TOWN USING A COMBINATION OF TOWN FORCES AND CONTRACTUAL SERVICES, AND ADEQUATE FUNDING IS PROVIDED IN THE ANNUAL OPERATING BUDGET FOR THE HIGHWAY DEPARTMENT TO ADDRESS THE MAINTENANCE REQUIRED FOR THE PROPOSED IMPROVEMENTS.

THE MAINTENANCE PLAN FOR THE PROPOSED DRAINAGE SYSTEM IS AS FOLLOWS:


GENERAL: THE PROPOSED DRAINAGE SYSTEM TO BE INSTALLED AS PART OF THIS PROJECT WILL REQUIRE ROUTINE MAINTENANCE IN ORDER TO MAINTAIN PROPER FUNCTION OF WATER QUALITY IMPROVEMENT FEATURES. THESE FEATURES INCLUDE THE CATCH BASIN SUMPS, THE OFF-LINE PARTICLE SEPARATOR, THE UNDERGROUND INFILTRATION SYSTEM, THE INFILTRATION SWALE, AND INFILTRATION BASIN.

ROAD SWEEPING (TRYON STREET AND DUG ROAD) SWEEPING IS PERFORMED ON A ANNUAL BASIS IN THE SPRING AS PART OF THE TOWN'S ANNUAL STREET MAINTENANCE. ADDITIONAL SWEEPING WILL BE PERFORMED ON AN AS NEEDED BASIS TO ADDRESS SEDIMENT ON THE ROADWAY.

CATCH BASINS AND OFF-LINE PARTICLE SEPARATORS (TRYON STREET) WITHIN THE FIRST YEAR AFTER CONSTRUCTION, CATCH BASIN SUMPS AND SEDIMENTATION CHAMBERS WILL BE INSPECTED QUARTERLY TO EVALUATE THE RATE OF SEDIMENT BUILD UP. THESE WILL BE CLEANED OUT AS NEEDED DURING THIS TIME PERIOD. AFTER THE FIRST YEAR, INSPECTIONS WILL BE PERFORMED SEMI-ANNUALLY, AND THESE STRUCTURES WILL BE CLEANED AT THE FREQUENCY DICTATED BY THE RATE OF SEDIMENT BUILD UP.

UNDERGROUND INFILTRATION SYSTEM (TRYON STREET) THE UNDERGROUND INFILTRATION CHAMBERS WILL BE INSPECTED ON A QUARTERLY BASIS DURING THE FIRST YEAR AFTER CONSTRUCTION IS COMPLETED, AND ON A SEMI-ANNUAL BASIS THEREAFTER TO EVALUATE THE LEVEL OF SEDIMENT BUILD UP IN THE SYSTEM. ACCESS PORTS WILL BE PROVIDED ALONG THE LENGTH OF THE CHAMBER WHICH WILL BE USED TO MEASURE AND MONITOR SEDIMENT BUILD UP USING A STADIA ROD. WHEN SEDIMENT REACHES 3-INCHES IN DEPTH, THE CHAMBERS WILL BE CLEANED OUT USING A JETVAC.


INFILTRATION BASIN AND CHANNEL (DUG ROAD) THE INFILTRATION BASIN AND CHANNEL ALONG DUG ROAD WILL BE INSPECTED ON A SEMI-ANNUAL BASIS FOR SIGNS OF SEDIMENTATION OR EROSION. SEDIMENT WILL BE REMOVED AND DISPOSED OF AS NEEDED TO MAINTAIN THE INFILTRATION CAPACITY INTO THE CHANNEL BOTTOM. THE DRYWELLS WILL BE INSPECTED AND SEDIMENT REMOVED AS NEEDED. STONE CHECK DAMS ARE INTENDED TO REMAIN AS PART OF THE PERMANENT CHANNEL. SEDIMENT WILL BE REMOVED FROM BEHIND THE CHECK DAMS OR THESE DAMS WILL BE REPLACED AS THE RATE OF SEDIMENT BUILT UP REQUIRES IN ORDER TO MAINTAIN THE FUNCTION.




DANIEL A. PENNINGTON P.E. Reg. No. 20101


DATE SPECIAL PERMIT APP'D DIRECTOR OF GOMMUNITY DEVELOPMENT FILE NO.

DRAWING ISSUE STATUS 12/10/201 ISSUED FOR CONSTRUCTION 1/4/2013 ADD EROSION CONTROL MAT DETAIL ADD GRADING / PLANTING PLAN 0/30/20 DESCRIPTION DATE



SCALE: AS SHOWN DATE: RAWN BY: C.F.S. 8/15/2013 CHECKED BY: S.M.B. | 8/15/201: APPROVED BY: D.A.P. 8/15/201: DO NOT SCALE THIS DRAWING. USE THE DIMENSIONS GIVEN. IF THERE ARE ANY DISCREPANCIES OR QUESTIONS, CONTACT THE TOWN OF GLASTONBURY, ENGINEERING OFFICE





EROSION CONTROL NOTES FOR PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 1 & 2 located at

302 & 306 TRYON STREET GLASTONBURY, CONNECTICUT

OF <u>12</u>


SHEET NO.


MANUAL REVISIONS TO THIS DOCUMENT ARE PROHIBITED. ALL REVISIONS MUST BE PERFORMED ON CADD FILE: H:\DWG\Streets\Tryon St\PW-9278 Tryon St-Dug Rd Drainage\Tryon St - Dug Rd Drainage-2013-DUG-REV2.dwg

\*\* IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 5" (15 cm) MAY BE NECESSARY TO PROPERLY ANCHOR THE RECP's.


PW-9278


ST. FILE:








CONSTRUCTION GUIDE.














STORMWATER CHAMBER SPECIFICATIONS



STORMTECH GENERAL NOTES





MANUAL REVISIONS TO THIS DOCUMENT ARE PROHIBITED.

ALL REVISIONS MUST BE PERFORMED ON CADD FILE:

PERIMETER STONE MUST ALWAYS BE BROUGHT UP EVENLY

WITH BACKFILL OF BED. PERIMETER STONE MUST EXTEND

HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH

STRAIGHT OR SLOPED SIDEWALLS.

MC-3500 INSPECTION PORT (TYP. ALL 3)

**CHAMBER LAYOUT** (69) STORMTECH MC-3500 CHAMBERS (2) STORMTECH MC-3500 END CAPS INSTALLED WITH 12" COVER STONE, 9" BASE STONE, 40% STONE VOID INSTALLED SYSTEM VOLUME (PERIMETER STONE INCLUDED): 13,848 CF

PLACE MINIMUM 17.5' OF ADS 315WTM WOVEN GEOTEXTILE (OR EQUAL) OVER BEDDING STONE FOR SCOUR PROTECTION AT ALL CHAMBER INLET ROWS

CHAMBER LAYOUT DETAIL

SCALE: 1" = 20'


TYPICAL CHAMBER TRENCH DETAIL

H: \DWG\Streets\Tryon St\PW-9278 Tryon St-Dug Rd Drainage\Tryon St - Dug Rd Drainage-2013-DUG-REV2.dwg

Certified to be substantially correct DANIEL A. PENNINGTON P.E. Reg. No. 2010

TOWN OF GLASTONBURY RURAL RESIDENCE & FLOOD ZONE PROJECT/APPLICANT ZONE #302, #306 & LOT W-20 TRYON STREET PROJECT ADDRESS DATE SPECIAL PERMIT APP'D DIRECTOR OF COMMUNITY DEVELOPMENT FILE NO.

DRAWING ISSUE STATUS ISSUED FOR CONSTRUCTION 2/10/201 ADD SED. & DIVERSION STRUCTURE DETAILS 9/30/2013 ADDED INFILTRATOR DETAILS "SHEET 6" 1/4/2013 DATE



SCALE: AS SHOWN DRAWN BY: C.F.S. 11/26/201 CHECKED BY: S.M.B. 11/26/201 APPROVED BY: D.A.P. 11/26/201 DO NOT SCALE THIS DRAWING. USE THE DIMENSIONS GIVEN. IF THERE ARE ANY


PROPOSED ELEVATIONS

MAX. ALLOWABLE GRADE (TOP OF PAVEMENT/UNPAVED):

MIN. ALLOWABLE GRADE (BASE OF FLEXIBLE PAVEMENT/UNPAVED):

MIN. ALLOWABLE GRADE (TOP OF REINFORCED CONCRETE PAVEMENT):

MIN. ALLOWABLE GRADE (UNPAVED WITH TRAFFIC):



CONSTRUCTION DETAILS FOR PROPOSED STORM DRAINAGE IMPROVEMENTS PHASE 1 & 2

located at 302 & 306 TRYON STREET OF <u>12</u>

SHEET NO.

PW-9278 DESCRIPTION ST. FILE: DISCREPANCIES OR QUESTIONS, CONTACT T TOWN OF GLASTONBURY, ENGINEERING OFFICE

TOP OF STONE:

TOP OF CHAMBER:

15" INLET PIPE INVERT

BOTTOM OF STONE:

**BOTTOM OF CHAMBER:** 

23.75

21.95

20.00

19.25

GLASTONBURY, CONNECTICUT

PROPOSED SEDIMENTATION CHAMBER

15" PRE-CORED END CAP / PART NO. MC3500TEPE15T TYP OF ALL MC-3500 TOP STUB 15" CONNECTIONS

SHEET NO. 3 OF 12

15" ADS N-12 MANIFOLD -